

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./निर्माण /2018 /453

सिस्टम टेन्डर नं. 49554

कोरबा, दिनांक 12/02/2019

द्वितीय ई-निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (रोड) दिनांक 01.01.2015 से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	नगर पालिक निगम, कोरबा क्षेत्र में टार रोड, सी. सी. रोड एवं नाली का वार्षिक मरम्मत कार्य।	00.00	10000/-	12 माह	वर्ग डी एवं प्रवर श्रेणी	27.02.2019 से


शर्तें:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नम्बर, **जी.एस.टी.** पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का **स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।**
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. निविदा उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रदाय नहीं किया जावेगा।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का **1 प्रतिशत उपकर** के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंट की खरीदी ठेकेदारों को स्वयं करनी होगी।
10. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
11. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से **15 दिवस** के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
12. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
13. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
14. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
15. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
16. रोड के मरम्मत कार्यों में डामरीकरण कार्य के निविदा हेतु ठेकेदार को स्वयं के स्वामित्व के ऑटोमेटिक ड्रम मिक्स प्लांट, रोलर एवं अन्य मशीनरी, हॉट मिक्स प्लांट, पेवर फिनिशर एवं रोड रोलर आदि मशीनों के प्रमाण पत्र ऑनलाईन संलग्न करना आवश्यक होगा तथा निविदाकार का 60 कि.मी. की परीधि में हॉट मिक्स प्लांट होना आवश्यक होगा।

कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		12.02.19	10.30	12.02.19	15.30	Release Tender
2		Bid Submission	12.02.19	15.30	26.02.19	17.30	
3	Tender Open		27.02.19	10.30	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION KORBA (C.G.)

Sub. - Maintenance Work of R.C.C. Road, Drain, Divider & B.T. Road Nigam Area.

MAINTANANCE OF C.C. ROAD

S.No.	Description	Unit	Rate	Qty	Amount
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	cum	95.00		
2	Dismantling of cement concrete pavement i/c breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials up to a lead upto 1000 meters, stacking serviceable and unserviceable materials separately and as per relevant clauses of section-200.	cum	1104.00		
3	Removal of Unserviceable Soil with Disposal up to 1000 meters including loading and unloading.	cum	85.00		
4	Add extra over item 3.1 to 3.2 & 3.7 to 3.8 above for transportation for disposal beyond 1.0 Km lead.	cum	17.00		
5	Transportation of different other material i/c loading & unloading ii) Beyond 1 Kms. And upto 10 Kms. (Add extra for every 1 Km.)				
	(E) Excavated/compacted ordinary & other soil measured as per clause.	cum	115.20		
6	Embankment Construction with Fly ash/Pond ash available from coal or lignite burning Thermal Plants as waste material. (Construction of embankment with fly ash conforming to table 1 of IRC:SP:58-2001 obtained from coal or lignite burning thermal power stations as waste material, spread and compacted in layer of 200mm thickness each at OMC, all as specified in IRC:SP:58-2001 and as per approved plans.)	cum	495.00		
7	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)	cum	1434.00		

	Dry Lean Cement Concrete Sub-base as per IRC:SP-49(Construction of dry lean cement concrete Sub-base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 26.5 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing as per clause 601.)	cum	2332.00		
9	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads)				
	(iv) P.C.C. M-30	cum	4391.00		

Signature
SIE

MAINTANANCE OF DRAIN AND DIVIDER

No.	Description	Unit	Rate	Qty	Amount
1	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead up to 1000 meters and as per relevant clauses of section-200 in				
A	c) Pre-stressed / Reinforced cement concrete grade M-20 & above	CUM	908.00		
B	(II) Brick / Tile work				
	(B) In cement mortar	cum	240.00		
2	Construction of RCC Drain/Cover/Chamber				
A	(i) Excavation in Soil (by Manual Means.) Excavation for roadway in soil using including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto1000 meters as per relevant clauses of section 300.	cum	140.00		
B	(ii) Construction of RCC drain/chamber cover, placing in position, providing shuttering and concreting by using concrete mixer, compaction by vibration etc complete as per drawings and technical specifications excluding reinforcement. with RCC M-20	cum	4146.00		
C	(iii) Supplying, Fitting and Placing un-coated HYSD bar Reinforcement in drain/cover/chamber complete as per Drawing and Technical Specifications.	MT.	56301.00		
3	Providing & laying precast interlocking concrete blocks of minimum compressive strength of 300 kg/sq.cm and approved size , shape/ pattern over coarse sand bed of thickness upto 40 mm and joints thick filled with fine sand including leveling with surface vibrator, temping and sweeping etc. complete as per IRC SP.62-2004				
	C) 80mm thick Polymer coated coloured precast interlock concrete blocks	sqm	732.00		
4	Painting on Concrete Surfaces				
	(A) Two coats on new surfaces (Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces)	sqm	62.00		
	(B) One coat on old surfaces (Painting one or two coats after cleaning all dirt & dust, filling the surface with synthetic enamel paint in all shades on old concrete surfaces)	sqm	48.00		
5	Painting on Steel Surfaces (Providing and applying two coats of ready mix paint of approved brand on steel surface after through cleaning of surface to give an even shade)	sqm	50.00		


	Painting Lines, Dashes, Arrows etc on Roads in Two Coats on Old Work (Painting lines, dashes, arrows etc on roads in two coats on old work with ready mixed road marking paint confirming to IS:164 on bituminous surface, including cleaning the surface of all dirt, dust and other foreign matter, demarcation at site and traffic control)				
	(i) Over 10 cm in width	sqm	63.00		
	(ii) Up to 10 cm in width	sqm	67.00		
7	Road Marking with Hot Applied Thermoplastic Compound with Reflectorizing Glass Beads on Bituminous Surface (Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorizing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35-1997. The finished surface to be level, uniform and free from streaks and holes.)	sqm	707.00		


Signature
S/E

BITUMINOUS MACADAM

No.	Description	Unit	Rate	Qty	Amount
1	Disposal of flexible pavements and disposal of dismantled materials up to a lead of 1000 meters, stacking serviceable and unserviceable materials separately and as per relevant clauses of section-200.				
	(A) Bituminous courses	cum	542.00		
	(B) Granular courses	cum	390.00		
2	Scarifying Existing Granular Surface to a depth of 50 mm (Scarifying the existing granular road surface to a depth of 50 mm and disposal of scarified material within all lifts and leads up to 1000 meters) as per clause 305.4.3.	sqm	18.00		
3	Scarifying existing bituminous surface to a depth of 50 mm (Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material with in all lifts and lead up to 1000 meters) as per clause 305.4.3.	cum	23.00		
4	Removal of Unserviceable Soil with Disposal up to 1000 meters including loading and unloading.	cum	85.00		
5	Add extra over item 3.1 to 3.2 & 3.7 to 3.8 above for transportation for disposal beyond 1.0 Km lead.	cum	17.00		
6	Excavation in Soil (by Manual Means.) Excavation for roadway in soil using including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	cum	95.00		
7	Transportation of different other material i/c loading & unloading ii) Beyond 1 Kms. And upto 10 Kms. (Add extra for every 1 Km.)				
	(E) Excavated/compacted ordinary & other soil measured as per clause.	cum	115.20		
8	Construction of embankment with Material Obtained from Borrow Pits/Borrow Area (Construction of embankment with approved material/selected soil having C.B.R.>5 (unless specified otherwise in the contract) obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300-2)	cum	223.00		
9	Granular Sub-base as per Table:- 400-1 Construction of granular sub-base by providing graded Material, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve the desired density, complete as per clause 401				
	(b) For Sub-base cum drainage layer or upper sub-base with (i) Grading-V Material	cum	1372.00		

	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)	cum	1434.00		
11	Prime coat (Providing and applying primer coat with oil based bitumen emulsion (SS-1, grade confirming to IS:8887) on prepared surface of granular Base including clearing of road surface and spraying primer using mechanical means as per clause 502.				
	(i) on WBM/WMM surface @0.85 Kg/sqm.	sqm	64.00		
12	Bituminous Macadam (Providing and laying bituminous macadam as per clause 504 with mixed prepared in minimum 40-60 TPH capacity hot mix plant using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired action) (A) With sensor paver finisher				
	(ii) for Grading-II(19 mm nominal maximum size, bitumen content 3.40%)	cum	6448.00		
13	Tack coat Providing and applying tack coat with bitumen emulsion (RS-1, grade confirming to IS:8887) using emulsion pressure distributor on the prepared bituminous/granular surface cleaned with mechanical broom and as per clause 503.				
	(i) Bituminous surface @ 0.25 kg /Sqm	sqm	15.00		
14	Close Graded Premix Surfacing/Mixed Seal Surfacing (Mechanical means using minimum 40-60 TPH capacity of HMP. Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness using bitumen to the required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a Smooth wheeled roller 8-10 tonne capacity, and finishing to required level and grade, complete as per clause 508) (B) With CRMB-60				
	(i) Type A (11.2 mm to 0.09 mm size aggregates)	sqm	172.00		


Sub. Engineers
Municipal Corporation
Korba (C.G.)


Astt. Engineers
Municipal Corporation
Korba (C.G.)

Ex. Engineers
Municipal Corporation
Korba (C.G.)