

कार्यालय, नगर पालिक निगम, कोरबा(छ.ग.)

फा.क्र./103/टी.पी.नगर/2022/

कोरबा, दिनांक 08.06.2022

सिस्टम टेन्डर क्र. 101999

ई-निविदा आमंत्रण सूचना

नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग में एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदाएं आमंत्रित की जाती है।

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	कोरबा जोन अंतर्गत वार्ड क 01 में दर्सी रोड पेट्रोल पंप से राताखार बाई पास तक स्ट्राम वार नाला निर्माण कार्य। (15वें वित्त आयोग)	65,00,000/-	49000/-	05 माह	वर्ग डी एवं प्रवर श्रेणी	30.06.2022 से -

शर्तें:-

- निविदा दरें प्रचलित सी.एस.आर. से कम या अधिक का उल्लेख किया जावे। सी.एस.आर. के अंतर्गत के आयटमों पर पृथक आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नंबर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्यनिधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्कैन कापी ऑनलाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिये प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिये एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में से 5 प्रतिशत परफारमेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्यनिधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र स्कैन कर अपलोड करना अनिवार्य होगा।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में पलाई ऐश ब्रिक्स का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों में असामान्य कमी प्रतीत होने पर सफल निविदादाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.सी.सी. जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- सशर्त निविदा स्वीकार नहीं की जावेगी।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- अन्य सूचनाएं नगर पालिक निगम, साकेत भवन रामपुर कोरबा कार्यालय में प्राप्त की जा सकती है।
- बिना कारण बताये निविदा स्वीकृत/अस्वीकृत या पूर्ण रूप से अमान्य करने का अधिकार सक्षम अधिकारी/प्राधिकारी को रहेगा।


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि :-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		08.06.22	13.30	08.06.22	13.30	Release Tender
2		Bid Submission	08.06.22	13.30	29.06.22	17.30	
3	Tender Open		30.06.22	10.30	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

of Work : CONSTRUCTION OF STORM WATER DRAIN FROM DARRI ROAD PETROL PUMP TO AGRASEN TIRAAHA WARD NO. 01

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015] &

P.W.D Road 01.01.2015

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1	In all types of soils.								
			1	426.00	1.80	2.50	1917.00			
			10X2	2.00	0.20	3.00	24.00			
			10	2.00	2.00	0.50	20.00			
						Total	1961.00	cum	185.00	362785.00
2	1.6	Extra for every additional lift of 1.5 m or part thereof.								
	6.1	All types of soils								
			1	426.00	1.80	1.00	766.80			
			10	2.00	2.00	0.50	20.00			
			10X2	2.00	0.20	1.50	12.00			
						Total	798.80	cum	26.50	21168.20
3	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).								
			1	426.00	1.50	0.15	95.85			
			10	2.00	2.00	0.15	6.00			
			2X.5	425.00	0.50	0.40	85.00			
			1	426.00	1.80	0.10	76.68			


N	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT	
							Total	263.53	cum	2970.00	782684.10
4	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.									
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).									
			10	2.00	2.00	0.30	12.00				
			10X2	1.80	0.30	2.00	21.60				
			10X2	1.20	0.30	2.00	14.40				
			10	1.80	1.80	0.30	9.72				
			1	426.00	1.80	0.20	153.36				
		Deduction--	10	1.80	1.80	0.20	-6.48				
							Total	204.60	cum	4163.00	851749.80
5	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:									
	12.1	Thermo-Mechanically treated bars FE 415	204.6	68.10			13933.26	kg	54.50	759362.67	
6	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:									
	1.2	Wall of any thickness including attached pilasters, buttresses etc. in super structure.									
			10	4.00	1.80	2.00	144.00				
			10	4.00	1.20	2.00	96.00				
							Total	240.00	sqm	228.00	54720.00


SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
			10	1.20	1.20		14.40			
			10	4.00	1.80	0.30	21.60			
							Total	36.00	sqm	235.00
										8460.00
7	16.1	Dismantling rammed moorum and boulders or rammed moorum and silt in foundation or under floor including all lead and lifts.	1	426.00	1.80	0.30	230.04	cum	279.00	64181.16
8	1.26	Carriage by mechanical transport upto 5 km lead:								
	26.1	Earth								
							1961.00			
							230.04			
							Total	2191.04	cum	111.00
										243205.44
9	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.					1119.66	cum	371.00	415393.86
10	9.2	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	10	49.25			492.50	Kg	66.00	32505.00
11	9.3	(PWD ROAD-01.01.2015-3)Provid and laying Reinforced Cement Concrete pipe NP 4 / prestressed concrete pipe								

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		(Laying Reinforced cement concrete pipe NP4 /prestressed concrete pipe for culverts including fixing collar with cement mortar 1:2 but excluding bedding below pipe excavation, protection works, backfilling, concrete and masonry works in head walls and parapets .)								
	C	1000 mm dia	1	426.00			426.00	Meter	6609.00	2815434.00
12	9.6	(PWD ROAD-01.01.2015-6)Provid 1 class bedding below pipes with graded sand or other granular materials passing through 5.6 mm sieve as per clause 2904.	1	426.00	1.80	0.15	115.02	Cum.	759.00	87300.18

As per Estimate Amount Rs. 6498949.41

Say Rs. 65.00 Lac


Sub Engineer
Nagar PalikNigam
Korba (C.G.)


Assistant Engineer
Nagar PalikNigam
Korba (C.G.)