

# कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क्र. 1373/2024

सिस्टम टेंडर नं. 156248

कोरबा दिनांक 18.07.2024

## द्वितीय ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता PHE –SOR Amendment 7/2022-23 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र फार्म A में निविदा आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	घरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (DD)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क्र 32 डिगापुर बस्ती रिस्दी बस्ती वार्ड क्र 34 बेलगिरी बस्ती, वार्ड क्र 30 मानिकपुर बस्ती, वार्ड क्र 31 दादर बस्ती एवं वार्ड क्र 18 में पाईप लाईन बिछाने का कार्य (15वें वित्त)	58.38	44000/-	4 माह	3000/-	वर्ग डी एवं प्रवर श्रेणी	06.08.2024 से .....

शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र/पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं घरोहर राशि FDR/TDR, शपथपत्र का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
  - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का DD एवं शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से निविदा खुलने की तिथि में दोपहर 3.00 बजे तक आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा को उपलब्ध कराना अनिवार्य होगा।
  - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
  - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का DD जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में फ्लाइंग एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का विल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का विल संलग्न करना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा प्रपत्र फार्म -ए की कंडिका 11 अनुसार एस्कलेशन देय नहीं होगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
- ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जाएगा।
- ठेकेदारों को निर्माण कार्य के दौरान निर्माण एवं अपशिष्ट प्रबंधन नियम 2016 में किये गये प्रावधानों का पालन करना होगा।

कार्यपालन अभियंता  
नगर पालिक निगम  
कोरबा (छत्तीसगढ़)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

### Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		18.07.2024	9.00	18.07.2024	10.00	Release Tender
2		Bid Submission	18.07.2024	10.00	05.08.2024	17.30	
3		Physical Document Submission	18.07.2024	10.00	06.08.2024	15.00	
4	Tender Open		06.08.2024	16.00	--	--	

  
EXECUTIVE ENGINEER  
KORBA (CG)  
For, Commissioner Korba (C.G.)

**TENDER/NIT HEADER DETAIL**

ORGANIZATION NAME	Urban Administration and Development Department (UADD)	PROCUREMENT CATEGORY	WORKS
TENDER NO.	156248	TENDER DEALING OFFICER	- Vinod kumar Sandilya (DFLT)
NUMBER OF ITEMS ALREADY ATTACHED	1	MATCHING	NO
CURRENCY	INR - INDIAN RUPEE	TENDER CATEGORY	PERCENTAGE
NIT TYPE	RESTRICTED TENDER	OFFICE/DIVISION (PWD)	COMMISSIONER, MUNICIPAL CORPORATION, KORBA
VENDOR CLASS	A, B, C, D	SECTION/CIRCLE (PWD)	TENDER SECTION
PROBABLE AMOUNT OF CONTRACT (FAC) (INR)	5837538.00	NAME	
DIVISION / DISTRICT	MUNICIPAL CORPORATION, KORBA	SECTION/CIRCLE (PWD)	
NAME		NAME	
DESCRIPTION	F.No. 1373/Const./Water Supply/2024/KMC		
DETAILED DESCRIPTION	Providing & Laying of Distribution Network PVC pipe at Ward No. 32 Dingapur Basti, Risdi Basti Khabadi, Ward No. 34 Belgiri Basti, Ward No. 30 Manikpur Basti & Ward No. 31 Dadar Basti		
IS AUCTION ENABLED?	N	BID PART NUMBER	1
NUMBER OF BID PART(S)	2		

**ATTRIBUTE (S)**

ATTRIBUTE NAME	ATTRIBUTE VALUE
BID VALIDITY PERIOD (in days)	120
Tender / Work Completion Time (in months)	4 (VALUE)
Required Past Technical Experience	As per Tender Document / NIT
Required Financial Turnover (in INR)	AS PER NIT
Required Bid Capacity (in INR)	AS PER NIT

**PAYMENT DETAILS**

DETAILS	
Tender/Processing/Bid Fees	N/A
EMD/Bid Security	44000.00 INR

**DATE-TIME DETAIL (S)**

BID SUBMISSION START DATE	Jul 18, 2024 02:30:03:PM	BID DUE DATE	Aug 5, 2024 05:30:58:PM
BID OPEN DATE (SCHEDULED)	Aug 6, 2024 04:00:04:PM	PHYSICAL DOC SUBMISSION END DATE	Aug 6, 2024 03:00:00:PM

**PRE-BID DISCUSSION DETAILS**

PRE-BID DISCUSSION NOT REQUIRED

**ALTERNATE BID DECRYPTOR (S)**

USER DETAILS
MR BUYER ADMIN (DFLT)
- MANORANJAN SARKAR (DFLT)
- Mitresh Verma (DFLT)
- ARUN KUMAR SHARMA (DFLT)
- Bhushan Ram Oraon (DFLT)
- Vinod kumar Sandilya (DFLT)
- Navneet Kant Nath (DFLT)

**TERM AND CONDITION DETAIL (S) - SPECIAL TERM (S)**

SL. NO.	CATEGORY	DESCRIPTION
1	SPECIAL TERM(S)	SPECIAL TERM(S) As per Tender Document / NIT

**TENDER SPECIFIC REQUIRED ATTACHMENT (S)**

**Envelop B**

SL. NO.	SUPPORTING DOCUMENT NAME	MANDATORY	ALLOW EXEMPTION	GROUP
2	DECLARATION FOR NOT BEING BLACK LISTED	YES	NO	OTHER
3	INCOME TAX CLEARANCE CERTIFICATE	YES	NO	OTHER
4	REGISTRATION CERTIFICATE (ANY GOVT DEPT IN CHHATTISGARH)	YES	NO	OTHER
5	GST CERTIFICATE FROM CHHATTISGARH	YES	NO	OTHER
6	DECLARATION FOR NOT ABOVE TOTAL WORK OF REGISTRATION CAPACITY	YES	NO	OTHER



# KORBA MUNICIPAL CORPORATION

**Providing & laying of distribution network PVC pipeline at ward no. 32  
Dingapur basti , Risdi basti kosabadi , ward no. 34 Belgiri basti , ward no. 30  
Manikpur basti & ward no. 31 Dadar basti.**

**BLOCK : KORBA**

**DISTRICT : KORBA**

## Abstract cum Measurement Sheet

Sr. No.	Items	Nos.	Length (In Mtr)	Breadth (In Mtr)	Height (In Mtr)	Qty.	CT :	Rate (In Rs.)	Amount
1	Earth work in excavation for pipe trench in ordinary soil areas including dressing, watering, ramming and disposal of excavated earth lead up to 50m and lift up to 1.5m, disposal earth to be levelled, neatly dressed.  For pipeline of 110mm Dia. PVC Pipe For pipeline of 160mm Dia. PVC Pipe <b>Total =</b> (CG PHE SOR Amendment No 7/ 2022-23; Item No- 18.15; Page No- 51)	1 1	2700.00 1500.00	0.60 0.60	1.00 1.00	1620.00 900.00	Cum	201.00	506520.00
2	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 m lead as per direction of engineer-in-charge.  Dismantling of Cement Concrete Pavment by mechanical means using pneumatic tools, cutter breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials up to a lead of 1000 metres, stacking serviceable and unserviceable materials separately  For pipeline of 110mm Dia. PVC Pipe For pipeline of 160mm Dia. PVC Pipe <b>Total =</b> (CG PHE SOR Amendment No 7/ 2022-23; Item No- 18.29.3; Page No- 52)	1 1	1500 500	0.60 0.60	0.20 0.20	180.00 60.00	Cum	1227.00	294480.00
3	Pumping out water caused by springs, tides or river seepage, broken water mains or drains or well or the like.  (CG PHE SOR Amendment No 7/ 2022-23; Item No- 18.21; Page No- 52)	1				1100.00	KL	71.00	78100.00
4	Supply & Filling moorum/river sand for pipe bedding or over the pipe (including supply)  (CG PHE SOR Amendment No 7/ 2022-23; Item No- 18.24; Page No- 52)	1	2250.00	0.6	0.15	202.50	Cum	864.00	174960.00
5	Providing, laying and jointing following P.V.C. pipes with solvent cement joint for 6, 8 and 10 kg/ sq. cm. pressures including testing of joints, cost of jointing materials etc. complete in all respect.  For pipeline of PVC 110mm , 8kg/cmsq For pipeline of PVC 160mm , 8kg/cmsq (CG PHE SOR Amendment No 7/ 2022-23; Item No- 7.1 ; Page No- 23 )					2700.00 1500.00	Mtr. Mtr.	470.00 855.00	1269000.00 1282500.00

6	<p>Providing, Solvent Cement Joints to PVC Pipes and fittings of 6, 8 and 10 Kg/Sq cm. Pressure including testing of joints and cost of jointing materials (i.e. socket, coupler &amp; solvent cement)</p> <p>110 MM 160 MM (CG PHE SOR 2020; Item No- 7.3 ; Page No- 24)</p>	120 85				120 85	Each Each	34.00 50.00	4080.00 4250.00
7	<p>Providing and laying in position including testing following PVC bends suitable for 6, 8 and 10 Kg/Sq. cm. pressure pipes.</p> <p>Pipeline 110 mm diameter Pipeline 160 mm diameter (CG PHE SOR Amendment No 7/ 2022-23; Item No- 7.5 ; Page No- 24)</p>	30 12				30 12	Each Each	427.00 1408.00	12810.00 16896.00
8	<p>Providing and laying in position including testing following PVC Tees, suitable for 6, 8 and 10 Kg/Sq cm. Pressure pipes.</p> <p>Pipeline 110 mm diameter Pipeline 160 mm diameter (CG PHE SOR Amendment No 7/ 2022-23; Item No- 7.6 ; Page No- 24)</p>	20 12				20 12	Each Each	267.00 693.00	5340.00 8316.00
9	<p>Providing and laying in position including testing following PVC end Cap (plugs) suitable for 6, 8 and 10 Kg/Sq cm. Pressure pipes.</p> <p>Pipeline 110 mm diameter Pipeline 160 mm diameter (CG PHE SOR Amendment No 7/ 2022-23; Item No- 7.8 ; Page No- 25 )</p>	17 10				17 10	Each Each	80.00 212.00	1360.00 2120.00
10	<p>Providing and laying in position including testing PVC coupler suitable for 6, 8 and 10 Kg/Sq. cm. Pressure pipes.</p> <p>Pipeline 110 mm diameter Pipeline 160 mm diameter (CG PHE SOR Amendment No 7/ 2022-23; Item No- 7.9 ; Page No- 25)</p>	50 20				50 20	Each Each	120.00 399.00	6000.00 7980.00
11	<p>Providing and fixing PVC Djoint (Detachable joint) in PVC pipe line suitable for classes up to 10kg/sqcm Pressure pipes. i/c nut bolt, cutting of pipe, testing of joints etc complete.</p> <p>Pipeline 110 mm diameter Pipeline 160 mm diameter (CG PHE SOR Amendment No 7/ 2022-23; Item No- 7.12 ; Page No- 26)</p>	55 25				55 25	Each Each	25.00 40.00	1375.00 1000.00

12	Providing & fixing of following Cast iron double flanged sluice valves as per I.S.:14846-2000 fitted with cast iron cap including jointing & testing with cost of jointing material such as bolts, nuts, rubber insertions etc. all complete.  150 mm Dia. Class (PN-1.6) 100 mm Dia. Class (PN-1.6) (CG PHE SOR 2020; Item No- 8.1; Page No-115)	3 5				3 5	Each Each	7559.00 5090.00	22677.00 25450.00	
13	Providing and laying in position including testing following PVC flanged tail pieces suitable for 6, 8 and 10 Kg./Sq. cm. Pressure pipes.  Pipeline 110 mm diameter Pipeline 160 mm diameter (CG PHE SOR Amendment No 7/ 2022-23; Item No- 7.7 ; Page No- 24)	6 10				6 10	Each Each	173.00 474.00	1038.00 4740.00	
14	Providing & laying mechanically mixed cement concrete 20mm nominal size graded crushed stone excluding cost of centering & shuttering.  <b>a) Reconstruction of Road (M-20 grade)</b> 1: 1.5 :3 (M-20) grade of concrete (CG PHE SOR 2020; Item No- 8.41; Page No- 53)		1810.00	0.6	0.20	217.20	Cum	6545.00	1421574.00	
15	Construction of Brick masonry valve chamber with 20 cm thick wall in 1:6 C.M. with 12mm thick 1:4 Cement Plaster and base course 10 cm. thick in M-15. Inside Dimensions 110x80x100cm M-20 RCC chamber cover size 130x100cmx120cm including cost of materials, labour etc. complete.  (CG PHE SOR Amendment No 7/ 2022-23; Item No- 18.79; Page No- 58)	7				7.00	No.	7886.00	55202.00	
16	Filling available excavated earth in trenches, lead up to 50m and lift up to 1.5m in all kind of soil excluding Watering and ramming.  <b>Back filling for 160 mm Dia.</b> Total volume of earthwork = Deducting volume of pipe = <b>Back filling for 110 mm Dia.</b> Total volume of earthwork = Deducting volume of pipe = <b>Total =</b> (CG PHE SOR Amendment No 7/ 2022-23; Item No- 18.23; Page No- 52)		0.785 x 0.160 x 0.160 x 1500 =			960.00 -6.03		1800.00 -4.75	2749.22 Cum 62.00	170451.76

17	<p>Provision for inter connection of old to new pipe line with excavation of trench as per requirement of any diameter &amp; type of pipe line in muddy area i/c dewatering the trench laying &amp; jointing of pipe and specials, back fillir / the trench i/c testing of joints cost of labour &amp; specials such as D-Joints couplers, solvent cement etc, complete job work as per approved specification and as directed by Engineer in charge..</p> <p>110 / 110 mm dia. (CG PHE SOR Amendment No 7/ 2022-23; Item No- 19.23; Page No- 67)</p>	17				17.00	No.	2854.00	48518.00
18	<p>House hold connection with 15mm S.S. tap including earth work in excavaton for pipe trench in all kinds of soil &amp; W.B.M. in areas with demolishing cement concrete road and reconstruction of same good with providing and fixing 15mm G.M./ brass ferrule 90x15mm MS/ PVC Clamp in main line 15mm dia PVC pipe heavy class from main pipe line to house of consumer up to 5 to 10 meter long as per site condition PVC specials such as 15mm PVC sockets elbows, union with all other work pertaining to it job completed, as per approved specification and as directed by Engineer incharge</p> <p>(CG PHE SOR Amendment No 7/ 2022-23; Item No- 19.14 ; Page No- 65 )</p>	200				200.00	No.	2054.00	410800.00

Total without GST = 5837538.00

Add 18% GST = 1050756.84

Total With 18% GST = 6888294.84


Say [ In Rs. ] = 6888300.00



Sub Engineer  
Municipal Corporation  
Korba(C.G)



Assistant Engineer  
Municipal Corporation  
Korba(C.G)



Executive Engineer  
Municipal Corporation  
Korba(C.G)