

10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है, तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ. डी.आर./टी.डी.आर. ऑफिस टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयकों के साथ 01 वर्ष हेतु साथ ही मरम्मत एवं संधारण प्रवृत्ति के कार्यों को छोड़कर 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी। (मरम्मत संधारण मद के कार्यों को छोड़कर)
17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. मवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1998 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कड़िका क. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
19. सू. से संबंधित निर्माण कार्यों में प्लाट्स एवम ट्रिक्स का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा प्रपत्र थवतउ-। के क्लॉज नम्बर - 11 अनुसार एस्केलेशन देय नहीं होगा।
23. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
24. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

प्रतिलिपि :- प्रोग्रामर संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नवा रायपुर छ.ग. को [www. uad.cg.gov.in](http://www.uad.cg.gov.in) में अपलोड किये जाने हेतु प्रेषित।


(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

.....

मोबाईल नं.-


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

DETAILED ESTIMATE

Item Of Work :- वार्ड क. 66, बांकीमोंगरा नं.2, उड़िया मोहल्ला, जंगल साईड, के शेड (छतदार) का मरम्मत कार्य ।
(वार्षिक दर निर्धारण)

As Per SOR :- SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING - 01.01.2015]

S. N.	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	16.17	Dismantling G.I. sheet roofing including ridges hips, valleys and gutters etc. and stacking the material with 50 m lead.								
			1	6.00		6.00	36.00			
						Total	36.00	sqm	33.50	1206.00
2	16.30	Dismantling steel work in single section in RS Joists, channels, angles, flats, I-section and T-section including dismembering and stacking within 50 Metres lead.								
							200.00	Sqm	0.70	140.00
3	16.43	Demolishing cement concrete including disposal of material within 50 metre lead.								
	43.2	1:3:6 or richer mix								
			1	4.50	4.50	0.10	2.03			
						Total	2.03	Cum	549.00	1111.73
4	16.3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.								
	3.3	In cement mortar.								
			2	4.50	0.30	1.20	3.24			
			2	3.90	0.30	1.20	2.81			
						Total	6.05	Cum	263.00	1590.62
5	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1	In all types of soils.								
			4	1.60	1.60	1.60	16.38			
			1	1.50	1.10	0.30	0.50			
						Total	16.88	Cum	185.00	3122.62

			4	0.20	0.30	1.60	0.38			
			4	0.20	0.30	3.30	0.79			
		Plinth Beam	4	4.10	0.20	0.30	0.98			
		Slab Beam	4	4.20	0.20	0.30	1.01			
		Slab	1	6.00	6.00	0.12	4.32			
			4	0.75	0.20	0.20	0.12			
						Total	10.74	Cum	4163.00	44727.27
11	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
	12.1	Thermo-Mechanically treated bars FE 415					859.52	Kg	54.50	46843.84
12	3.14	Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer.					20.00	Kg	43.50	870.00
13	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
			4	4.00	1.50	0.10	2.40			
			4	4.00	1.40	0.40	8.96			
			4	2.00	4.10	0.30	9.84			
			4	1.00		1.60	6.40			
						Total	27.60	Sqm	139.00	3836.40
	1.4	Edge of slab, breaks in floor and walls upto 200mm.								
			4	6.00			24.00			
						Total	24.00	Mtr	34.00	816.00
	1.5	Columns, Pillars, Piers and likes-rectangular or square in shape								
			4	1.00		3.00	12.00			
						Total	12.00	Sqm	297.00	3564.00
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
			1	6.00	6.00		36.00			
		Deduction (-)	4	4.10	0.20		3.28			
		Deduction (-)	4	0.20	0.30		0.24			
						Total	32.48	Sqm	235.00	7632.80
	1.8	Beams, lintels, cantilevers & walls								
			4	4.10	0.20		3.28			


			4	2.00	4.10	0.30	9.84			
			4	2.00	0.75	0.20	1.20			
			4	4.00	0.75	0.20	2.40			
						Total	16.72	Sqm	202.00	3377.44
4	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:								
	5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)								
			4	4.10	0.30	1.00	4.92			
			1	1.50	1.00	0.40	0.60			
			1	1.50	0.70	0.20	0.21			
			1	1.50	0.40	0.20	0.12			
			1	23.20	0.20	0.30	1.39			
						Total	7.24	Cum	3350.00	24260.70
15	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:								
			1	23.20	0.20	0.30	1.39			
						Total	1.39	Cum	121.00	168.43
16	9.57	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.								
	57.2	SS Grade 304					70.00	kg	525.00	36750.00
17	11.1	Providing and making 6mm thick cement plaster of mix:								
	1.2	In Cement mortar 1:4 (1 cement : 4 fine sand)					53.80	Sqm	87.00	4680.60
18	11.2	Providing and making 12mm thick cement plaster of mix								
	2.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)					6.72	Sqm	96.50	648.48
19	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:								
	3.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)					25.20	Sqm	113.00	2847.60


		Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.								
	13.1	Size 600x600mm								
			1	4.50		4.50	20.25			
			4	1.50		0.20	1.20			
			3	1.50		0.30	1.35			
						Total	20.25	Sqm	1151.00	23307.75
21	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.					85.72	Sqm	94.50	8100.54
22	14.10	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.								
	10.1	On new work (two or more coats)								
							65.80	Sqm	44.50	2928.10
23	14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								
	15.1	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)								
			4	5.60		0.30	6.72			
			4	6.00		0.30	7.20			
			4	6.00		1.00	24.00			
						Total	37.92	Sqm	56.00	2123.52

		Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete								
	76.2	110 mm dia pipe.	2	4.00			8.00	metre	267.00	2136.00
25	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
			2	6.50	1.00	0.12	1.56			
			2	4.50	1.00	0.12	1.08			
			1	23.20	0.20	0.08	0.37			
						Total	2.64	Cum	4073.00	10752.72

As per Estimate Amount Rs.
Say Rs.

251612.46


Sub Er.
Nagar Palik Nigam
Korba


Asth. Er.
Nagar Palik Nigam
Korba