



# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

दर्री जोन

फा.क्र./723,733,734,735,737 एवं 738/निर्माण (दर्री जोन)/2024/

कोरबा, दिनांक 27.08.2024

## निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 & PWD Electrical SOR 01.06.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर बंद लिफाफा के माध्यम से आमंत्रित की जाती है :-

- निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने की अंतिम तिथि - 18.09.2024 सायंकाल 3:00 बजे तक
- निविदा खुलने की अंतिम तिथि - 18.09.2024 सायंकाल 4:30 बजे

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
01	वार्ड क्र. 51 लाटा से सुनिता नाग घर से रामजुग भारिया तक सी.सी. रोड का मरम्मत कार्य। (मरम्मत एवं संधारण मद) (द्वितीय निविदा)	3,96,000/-	4,000 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	18.09.2024
02	वार्ड क्र. 47 कुमगरी नीचेपारा में मुक्तिधाम निर्माण कार्य। (प्रभारी मंत्री मद 2024-25)	10,00,000/-	7,500 /-	750/-	Form-A	04 माह	सक्षम श्रेणी	18.09.2024
03	वार्ड क्र. 48 नागिन भाठा स्वास्थ्य केन्द्र के बगल में सामुदायिक भवन निर्माण कार्य। (प्रभारी मंत्री मद 2024-25)	10,00,000/-	7,500 /-	750/-	Form-A	04 माह	सक्षम श्रेणी	18.09.2024
04	वार्ड क्र. 51 कबीर भवन के पीछे साडा कॉलोनी दर्री सामुदायिक भवन निर्माण। (प्रभारी मंत्री मद 2024-25)	10,00,000/-	7,500 /-	750/-	Form-A	04 माह	सक्षम श्रेणी	18.09.2024
05	वार्ड क्र. 52 अंतर्गत नीलगिरी बस्ती में मेन रोड से दिपांकर चक्रवर्ती, विनोद घर से दिलीप सिंह एवं दिलीप सिंह से देवांगन घर तक आर.सी.सी. नाली का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	3,93,000/-	4,000 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	18.09.2024
06	वार्ड क्र. 52 अंतर्गत नीलगिरी बस्ती में मेन रोड से कृष्णकांत साहू के घर तक तथा विजय मल्लिक के घर से नवधा पण्डाल तक सी.सी. रोड का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	3,94,000/-	4,000 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	18.09.2024

### निविदा की शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से भेजना होगा अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक

क्रमशः.....02

22. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
23. कार्य कियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
24. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।
25. ठेकेदार द्वारा संपादित किये गए कार्यों के देयको का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जाएगा।
26. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
27. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नया रायपुर (छ.ग.) को [Uad.cg.gov.in](http://Uad.cg.gov.in) में अपलोड किये जाने हेतु प्रेषित।

(ठेकेदार के हस्ताक्षर)

नाम .....

पूर्ण पता .....

.....

मोबाईल नं.- .....


कार्यपालन अभियंता  
नगर पालिक निगम  
कोरबा (छ.ग.)




ITEM DESCRIPTION		N	L	B	H/D	Qty	Unit	Rate	Amount
	Foundations, footings, base of columns and plinth beam in any shape and size.								
		10x4	1.4		0.2	11.2			
		10x2	0.35		0.9	6.3			
		10x2	0.35		0.9	6.3			
		2	28		0.3	16.8			
					Total	40.6	Sqm	139.00	5643.40
b	Columns, Pillars, Piers and likes-rectangular or square in shape								
		10x4	0.35		3.9	54.6			
		4x4	0.2		1.2	3.84			
					Total	58.44	Sqm	297.00	17356.68
c	Beams, lintels, cantilevers & walls								
	top beam	1	28		0.4	11.2			
		1	28		0.35	9.8			
		2	6		0.5	6			
		2	6		0.35	4.2			
					Total	31.2	Sqm	202.00	6302.40
d	2.1.7 Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	1	9	7		63	Sqm	235.00	14805.00
7	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.								
a	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal								
		10	1.4	1.4	0.35	6.86			
		10	0.35	0.35	5.2	6.37			
		1	28	0.2	0.3	1.68			
	slab beam	1	28	0.35	0.4	3.92			
		2	5	0.35	0.5	1.75			
	slab	1	9	7	0.12	7.56			
					Total	28.14	Cum	4163.00	117146.82
8	Providing and laying nominal Plain cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.								
a	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	4	9	1.5	0.15	8.1	cum	4073.00	32991.30

ITEM DESCRIPTION		N	L	B	H/D	Qty	Unit	Rate	Amount	
9	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire									
	Thermo-Mechanically treated bars					110 kg/cum				
						Total	3100.00	Kg	54.50	168950.00
10	Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 in foundation and plinth in:									
	Cement Mortar 1:6 (1 cement : 6 coarse sand)									
		1	28	0.3	0.8	6.72				
						Total	6.72	Cum	3350.00	22512.00
11	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.									
		1	8	6	0.35	16.8				
						Total	16.8	cum	65.00	1092.00
12	12mm thick cement plaster of mix:									
	In Cement Mortar 1:6 (1 cement : 6 fine sand)									
		10X4	0.35		4.9	68				
		2	28	1	0.6	33.6				
						Total	101.6	Sqm	96.50	9804.40
13	14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:									
	14.15.1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm	10X4	0.35		5.2	72.8				
		1	10	10.3		103				
						Total	175.8	sqm	56.00	9844.80

ITEM DESCRIPTION								
	N	L	B	H/D	Qty	Unit	Rate	Amount
14	1	8	6		48.00	Sqm	897.00	43056.00
15	1	8	6	0.3	14.40	cum	242.00	3484.80
16					175.8			
	10X4	0.35		5.2	72.8			
	1	10	9		90			
				Total	162.80	sqm	94.50	15384.60
As per SOR Total Estimate Amount Rs.								499910.72
Part B- Boundarywall Around muktidham Rs.								499948.18
Total Estimate Amount								999858.90
Say Amount Rs.								1000000.00

  
 Sub Engineer  
 Municipal Corporation  
 Korba (C.G.)

  
 Asst. Engineer  
 Municipal Corporation  
 Korba (C.G.)

**OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)  
DETAILED ESTIMATE**

Work :- Construction Of Boundary wall Muktidham At ward no.47

per Sor :- Schedule of Rates Public Works Department [ PWD BUILDING 01-01-2015]


Sno.	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
1	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).								
		1	120	1.2	1.2	175.00 150			
					Total	175	Sqm	18	3150
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	In all types of soil	42	1.2	1.2	1.2	72.576			
		1	112	0.4	0.4	17.92			
					Total	90.496	cum	185	16741.76
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
		42	1.2	1.2	0.05	3.024			
		1	112	0.4	0.05	2.24			
					Total	5.264	cum	371	1952.944
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.								
5	1:3:6 (1 cement : 3coarse sand : 6graded stone aggregate 40mm nominal size).								
		42	1.2	1.2	0.08	4.8384			
		1	112	0.4	0.08	3.584			


ITEM DESCRIPTION		N	L	B	H/D	Qty	Unit	Rate	Amount
		1	15	2.5	0.08	3			
					Total	11.4224	cum	2970.00	33924.528
6	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
7	Foundations, footings, base of columns and plinth beam in any shape and size.								
		42x4	1		0.2	33.6			
		42x2	0.2		0.9	15.12			
		42x3	0.3		0.9	22.68			
		2	112		0.25	56			
					Total	127.4	Sqm	139.00	17708.6
8	Columns, Pillars, Piers and likes-rectangular or square in shape								
		42x2	0.2		1.3	21.84			
		42x2	0.3		1.3	32.76			
					Total	54.6	Sqm	297	16216.2
9	Beams, lintels, cantilevers & walls								
	top beam	2	120		0.2	48			
					Total	48	Sqm	202	9696
10	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.								
a	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		42	1	1	0.2	8.4			
		42	0.2	0.3	2.6	6.552			
		1	120	0.2	0.3	7.2			
	top beam	1	120	0.2	0.2	4.8			
					Total	26.952	Cum	4163	112201.18
11	Providing and laying nominal Plain cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.								
a	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).					9.375			
		1	25	2.5	0.15		cum	4073	38184.375



ITEM DESCRIPTION		N	L	B	H/D	Qty	Unit	Rate	Amount
11	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:								
	Thermo-Mechanically treated bars					55kg/cum			
					Total	1500.00			
					Total	1500.00	Kg	54.5	81750
12	Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 in foundation and plinth in:								
	Cement Mortar 1:6 (1 cement : 6 coarse sand)								
		1	120	0.2	1.2	28.8			
					Total	28.8	Cum	3350	96480
13	Extra for brick work in superstructure:								
	Above plinth and upto floor five level.					26			
					Total	26	Cum	121	3146
14	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
		1	120	0.3	0.25	9			
					Total	27	cum	65	1755
15	15mm thick cement plaster on the rough side of single or half brick wall of mix:								
	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
		1	120		1.4	168			
					Total	168	Sqm	113	18984
16	12mm thick cement plaster of mix:								
	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
		1	120	1	1.4	168			
		1	100	0.2		20			
					Total	188	Sqm	96.5	18142
17	Painting on new work (two or more coats) to give an even shade with:								
		2	3.6		2.1	15.12			

ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
				Total	15.12	Sqm	55	831.6
work welded in built up sections/ work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.								
In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1				151			
				Total	151	kg	68.00	10269
14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								
14.15.1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm	2	120		1.4	336			
				Total	336	sqm	56.00	18816
As per SOR Total Estimate Amount Rs.								499948.18
Say Amount Rs.								500000.00

  
 Sub Engineer  
 Municipal Corporation  
 Korba (C.G.)

  
 Asst. Engineer  
 Municipal Corporation  
 Korba (C.G.)