OFFICE OF MUNICIPAL CORPORATION KORBA

Notice Inviting Tender

NIT No: 33730/2026 Korba Dated 16.11.2026

Commissioner, Municipal Corporation Korba invites online Tenders on behalf of Municipal Corporation Korba on Form "A" for respective applicable Schedule of Rates from eligible class registered contractors in "unified Registration system e-Registration" PWD Chhattisgarh on Govt. of-C.G. e-Procurement System (http://eproc.cgstate.gov.in)

1	System Tender No.	**204002(1st Call)**
2	Name of Work/Description of Work	Construction of Community building with all facilities in purani basti korba at ward no-06**(MLA Fund)**
3	Probable Amount of contract	₹ 21.19 Lakhs
4	Earnest Money Deposit	₹ 16000.00 (I n shape of FDR/TDR in favor of Commissioner, Municipal Corporation, Korba)
5	Cost of Tender form fees	₹ 7 5 0 /- (I n shape of Demand Draft in favor of Commissioner, Municipal Corporation, Korba)
6	Eligible class of contractor / firm	Class- D & Above.
7	Time allowed for Completion	06 Months (Including rainy season)
8	SOR Applicable	PWD Building SOR 10.06.2026 & Electrical SOR 10.06.2026
9	Financial Capacity (as per clause 3.8.1)	₹ 3.18 Lakh valid Bank solvency certificate is to be attached along with the bid.

1. In order to participate in the tenders floated using the e-Procurement System, all contractors/bidders are required to get enrolled on the e-Procurement portal http://eproc.cgstate.gov.in.

2. The bids submitted online should be signed electronically with a Digital Certificate to establish the identity of the bidder bidding online. The registered contractors may obtain information required to issuance of Digital Certificate from e-Procurement System M Junction Raipur.

3. For submitting the bids online, the contractors/bidders are required to make online payment using the electronic payments gateway service Bid Hash Submission Fee as mentioned above the different modes of electronic payments accepted on the e-Procurement System is available and can be viewed online on the e-Procurement Website (http://eproc.cgstate.gov.in).

4. Tender Download, Submit Bid Hash online, Submission of Bids and other Documents and other activities will be governed by the time schedules given under – key Dates. Also, Bidder has to submit all the mandatory/required documents, if the mandatory/required documents not submitted by bidder then bid will be disqualified without any further clarification & Joint Venture /Consortium is not allowed.

5. Any bidder/contractor who is debarred, blacklisted, banned or suspended by the

Central Government, State Government, Public Sector Undertaking (PSU), Urban Local Body (ULB), or any Government Department as on the last date of bid submission shall not be eligible to participate in this bid. During the evaluation stage if it comes under the notice that the bidder hides crucial information related to his eligibility than the firm is disqualified and their financial bid shall not be opened.

6. The Bidders has to submit (Upload Scan Copies/fill) his offer/credentials online as required in the tender in the online templates in relevant envelopes.

7. The Bidders may refer Help Manual available online to perform their online activity. The Commissioner, Municipal Corporation Korba (CG) reserves the right to reject any part of/whole tender without assigning any reason and to restrict the list of pre-qualified tenderer to any number deemed fit by it.

8. Before the deadline for submission of tender the Commissioner, Municipal Corporation, Korba (C.G.) may modify the tender document by issuing amendment. (Any amendment thus issued shall be part of the tender and shall be published on web site)

9. Tenderers are required to submit all documents/information with the technical tender as required in the NIT or elsewhere in the Tender Document, otherwise it shall lead to rejection of bids.

10. **As per Circular No. GENCOR-35/306/2026-UAD Date 21.05.2026 issued by the Urban Administration & Development Department, Government of Chhattisgarh, the BOQ/PAC has been prepared exculuding GST, Accordingly, bidders shall quote their rates excluding GST only.** Applicable GST shall be paid separately by the Municipal Corporation, Korba, subject to submission of a valid GST Tax Invoice and compliance with the provision of the GST Act. Rules and Government instructions in force.

    The aforementioned provision shall be applicable to estimates prepared on the basis of the CG PWD SOR 2026. However, in respect of estimates prepared on the basis of the CG PWD SOR 2015, the rates are inclusive of GST and all other applicable taxes. Accordingly, the bidder shall quote their rates inclusive of GST and all other applicable taxes in such cases.

11. The bidder shall quote the tender as a percentage either at par, above, or below the Schedule of Rates (SOR). Quoting item-wise rates for any SOR item shall lead to disqualification of the bid.

12. The bidders are required to submit 'Envelope "A & B" physically and online respectively as per dates Indicated in Key Dates. The Physical Envelope should contain the following: -

    A. Envelope 'A' (Key Submission - Submit physically & online)- All the required document submission is mandatory for opening of technical bid.

        i. The Earnest Money Deposit (EMD) in the form of FDR/TDR of a Nationalized or Scheduled bank of India in favour of the Commissioner, Municipal Corporation, Korba payable at District - Korba (CG). The Earnest Money of the successful Bidders will be retained as part of the security deposit.

ii. Tender Document Fee (In the shape of demand draft in favour of Commissioner, Municipal Corporation, Korba)

iii. Notarized Affidavit and Pre Contract Integrity Pact separately in Original as per prescribed format. (On ₹100/- non-judicial stamp paper each)

B. Envelope- 'B' (Technical Bid - Submit Online Only): -

i. The bidder mandatorily submits all relevant documents that demonstrate their eligibility and qualification as per the criteria outlined in the tender document. Incomplete or missing documents will result in automatic disqualification during the technical evaluation stage.

ii. Scanned copy of the Earnest Money, Tender Document Fee and Affidavit.

iii. Valid Registration Certificates. CG PWD and (Partnership Deed, registration amendment certificate as the case may be)

iv. Copy of PAN card issued by Income Tax Department.

v. Copy of Valid GST/ CGST Registration must be valid up to Bid due date as per key dates otherwise tender will be disqualified while opening.

vi. Valid Bank Solvency Certificate in Bank Letter Head. (Not older than 12 Months) mention the Bank Dispatch No. or Ref. No. or Verifiable unique number or Date otherwise tender will be disqualified while opening) The bank solvency shall be submitted by the contractor 15% on the cost put to tender.

vii. If the participating bidder is partnership firm than the memorandum of partnership of the firm.

viii. Income Tax Return acknowledgment of last three assessed financial years available as on bid due date.

ix. Documentary proof of the engineer appointment letter with appropriate date and authentication by authorized signatory along with relevant qualification certificates as well as valid photo identity proof of appointed engineer.

x. Registration certificate of EPF supported with Form 5A and ESIC. Last three months relevant payment receipt/challan copies of the dues subjected to the payments of EPF and ESIC is mandatorily needed to be enclosed.

Envelope- "C" - (Financial Bid - Submit Only Online)

If the bidder quotes his rates in physical submissions than it will lead to disqualification during evaluation of the bid.

13. Physical Submission - The sealed envelope A should be sent by registered A.D. or speed post to **Office of the Commissioner, Municipal Corporation, Saket Bhawan, ITI Rampur Chowk, Kosabadi, Pin-495677 Korba (C.G.)** before expiry of physical submission of the bid. (Please mention the Name of Work, N.I.T. No. in Physical Envelope)

14. Required documents of qualified tenderer shall be opened online on the prescribed date and time as per Notice Inviting Tender. After verification of proper and other required documents financial offers of such qualified bidders shall be opened online by the Commissioner, Municipal Corporation, Korba (C.G.) in the presence of the tenderer (s)/ representative who choose to attend at that time.

15. Additional performance shall be deposited by the successful bidder at the time of signing of agreement when the bid amount is seriously unbalanced. i.e. less than the estimated cost by more than 10% in such an event the successful bidder will deposit the additional performance security to the extent of differential cost of bid amount and 90% of the estimated cost in shape of Bank guarantee of Nationalized Bank in favor of Commissioner, Municipal Corporation, Korba (C.G.) in Additional to EMD failing which the tender in this favor shall be liable for Rejection. The same shall be released along with the normal Security Deposit.

16. It is mandatory for bidder to submit all mandatory/required documents in online in website *http://eproc.cgstate.gov.in.* Any documents which are not submitted in online but submitted physically will not be accepted.

17. Bidder has to submit all the mandatory/required documents, if the mandatory/required documents not submitted by bidder then bid will be disqualified without any further clarification.

18. If any document as required is not received as per the desired form, then the Bidder will be disqualified without any further clarification and his financial bid will not be opened.

19. The provision of Clause 11 regarding price escalation shall not be applicable under this contract. No escalation or increase in the contract price will be paid for any reason, including fluctuations in material costs, labor wages, or any other inputs, during the entire duration of the project.

20. In case of any discrepancy, ambiguity or dispute related to the interpretation of the term and condition of the tender documents, the decision of the Commissioner, Municipal Corporation Korba, shall be final and binding on all parties involved.

21. After the issuance of the work order, the successful bidder must mandatorily comply with the all-applicable rules and regulations of relevant government departments, including but not limited to those related to mining labor laws, income tax, Goods and Service tax (GST), other statutory obligations. The bidder will be solely responsible for adhering to these regulations throughout duration of the project.

22. The successful bidder shall mandatorily register himself under the Building and Other Construction Workers (Regulation of Employment and Conditions of Service) Act, 1996. Proof of such registration shall be submitted for processing of running and final bills. Further, labour cess at the rate of 1% shall be deducted from each running and final bill as applicable.

23. The evaluation of bids shall be carried out by considering the lowest aggregate amount. The bidder quoting the lowest rate shall be considered as the Lowest Bidder (L1).

24. Security deposit at the rate of 5% shall be deducted from each running and final bill and shall be refunded to the contractor after completion of the security period of one year, reckoned from the date of completion of work, subject to certification that the work is in

good condition.

25. The contractor shall also be responsible for performance of work carried out by him for a period of 36 (Thirty-Six) Month beyond the completion of work for which performance security has to be furnished by him @ 5% (five percent) of amount of contract. For this purpose, contractor has to submit to the department a Bank Guarantee of 5% amount of the value of work done on every running and final bill payable to him. If contractor fails to submit bank guarantee of 5% amount of the gross bill, then 5% amount of bill shall be deducted from his running and final bill payment. However, the contractor can get refund of such performance cash security amount deducted if he submits appropriate bank guarantee valid for the period as stated above or 36 (Thirty-Six) Month after actual completion.

26. If the successful contractor fails to execute the agreement within the stipulated time period prescribed in the tender document, action shall be taken as per the provisions contained in the tender conditions. In addition, thereto, as per the resolution passed by the Municipal Council of Municipal Corporation Korba, the contractor shall also be liable to be debarred from participating in any future tenders invited by the Municipal Corporation Korba for a period of 06 (six) months."

27. If the contractor fails to complete the work within the stipulated time period after issuance of the work order, action shall be taken against the contractor as per the terms and conditions of the agreement. In addition, thereto, as per the resolution passed by the Municipal Council of Municipal Corporation Korba, the contractor shall also be liable to be debarred from participating in any future tenders invited by the Municipal Corporation Korba for a period of 01 (one) year."

28. All OPVC/PVC/HDPE pipes shall be tested at Central Institute of Plastic Engineering & Technology (CIPET). All ductile iron pipes, if used, shall be inspected and tested through third-party inspection agencies such as SGS, RITES or equivalent, at the contractor's cost, and only pipes conforming to relevant IS standards shall be accepted; non-conforming materials shall be rejected at the contractor's risk and cost without any claim. Payments due towards the contractor will be processed only after submission of the relevant test certificates and inspection reports.

29. Upon issuance of the work order, the successful bidder shall comply with all provisions of the Construction and Demolition Waste Management Rules, 2016.

Executive Engineer
Municipal Corporation
Korba (Chhattisgarh)

Copy to :-

Programer, Directorate, Urban Administration and Develpment, Raipur for upload web site www.uad.gov.in.

SYSTEM TENDER No 204002(1st Call)

NIT No: 33730/2026 Korba Dated 16.11.2026

Key Dates

Task	Date	Time
Bid Start Date	16.11.2026	12.00 Hrs
Bid Due Date	08.12.2026	17.30 Hrs
Physical Doc Submission End Date	11.12.2026	15.00 Hrs
Bid Open Date (Scheduled)	11.12.2026	16.00 Hrs

Executive Engineer
Municipal Corporation
Korba (Chhattisgarh)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT

of Work : CONSTRUCTION OF COMMUNITY BUILDING WITH ALL FACILITIES IN PURANI BASTI KORBA AT WARD NO-06

s per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-10.06.2026]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.2	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	sqm	252	6.00	1,512.00
2	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	.1.1	In all types of soils.	cum	134.25	157.00	21,077.25
3	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	38.88	55.00	2,138.40
4	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	24.15	315.00	7,607.25
5	2.1	Providing and fixing form work including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	:.1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	103.8	118.00	12,248.40
	:.1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	90	252.00	22,680.00
	:.1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	181.92	200.00	36,384.00
	:.1.8	Beams, lintels, cantilevers & walls	sqm	157.2	172.00	27,038.40
6	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	:.1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	cum	32.66	2525.00	82,466.50
7	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. (Note :Excess/ less cement used as per design mix is payable/ recoverable separately)				
	:.2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	102.13	3539.00	361,438.07
8	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending etc. complete as per drawing including cost of binding wire. All complete.				
	12.1	Thermo-Mechanically treated bars FE 415	kg	10345	46.00	475,870.00
	:.5.1	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				

		DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		ent Mortar 1:6 (1 cement : 6 coarse sand)	cum	74.04	2774.00	205,386.96
		Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	30	103.00	3,090.00
	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	390	64.00	24,960.00
11	9.15	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	kg	240	57.00	13,680.00
12	8.166	Providing and fixing factory made uPVC white colour sliding glazed window upto 1.50 m in height dimension comprising of uPVC multi-chambered frame with in-built roller track and sash extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), appropriate dimension of uPVC extruded glazing beads and uPVC extruded interlocks, EPDM gasket, wool pile, zinc alloy (white powder coated) touch locks with hook, zinc alloy body with single nylon rollers (weight bearing capacity to be 40 kg), G.I fasteners 100 x 8 mm size for fixing frame to finished wall and necessary stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealent over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes, wire mesh and silicon sealant shall be paid separately vide chapter no. 9.51, 9.58, 9.59 Respectively) Note: For uPVC frame and sash extruded profiles minus 5% tolerance in dimension i.e. in depth & width of profile shall be acceptable.				
	D. 3	Two track two panels sliding window made of (big series) frame 67 x 50 mm & sash 46 x 62 mm both having wall thickness of 2.3 ± 0.2 mm and single glazing bead / double glazing bead of appropriate dimension . (Area of window above 1.75 sqm upto 2.50 sqm).	Sqm.	7.2	4701.00	33,847.20
13	8.151	Providing and fixing factory made P.V.C. door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet mitred at corners and joined with 2 Nos of 150mm long brackets of 15x15mm M.S. square tube, the vertical door profiles to be reinforced with 19x19mm M.S. square tube of 19 gauge, EPDM rubber gasket weather seal to be provided through out the frame. The door frame to be fixed to the wall using M.S. screws of 65/100mm size complete as per manufacturers specification and direction of Engineer-in-Charge.	metre	10.2	294.00	2,998.80
14	8.152	Providing and fixing 30mm thick factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19mm x 19mm for styles and 15x15mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and				

		DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		ufacture. M.S. frame covered with 5mm thick heat moulded PVC 'C' channel of size 30mm thickness, 70mm width out of which 50mm shall be flat and 20mm shall be tapered in 45degree angle on either side forming styles; and 5mm thick, 95mm wide PVC sheet out of which 75mm shall be flat and 20mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115mm wide PVC sheet out of which 75mm shall be flat and 20mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel. 10mm (5mm x 2) thick, 20mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail. paneling of 5mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles & rails with 7mm (5mm+2mm) thick x 15mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5mm thick PVC strip of 20mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per Manufacturer's specification including 3 nos ISI marked stainless steel hinges of size 100x58x1.9 mm complete. (for W.C. and bathroom door shutter).				
	52.2	Both side Pre-laminated panel PVC door shutter	sqm	3.78	2407.00	9,098.46
15	11.1	Providing and making 6mm thick cement plaster of mix:				
	.1.2	In Cement mortar 1:4 (1 cement : 4 fine sand)	sqm	195.15	74.00	14,441.10
16	11.2	Providing and making 12mm thick cement plaster of mix:				
	.2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	414.7	78.00	32,346.60
17	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	.3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	400.3	91.00	36,427.30
18	12.79	Providing and laying DOUBLE/MULTI CHARGE (minimum 2.0 mm thick layer) VITRIFIED floor tiles with water absorption less than 0.05% and conforming to IS:15622-2017 of 1st quality of approved make in all colours and shades and size mentioned below (+/- 10mm) laid on 20mm thick cement mortar 1:4 (1cement: 4 coarse sand) including grouting the joints with withe cement and matching pigments etc. complete.				
	79.3	Size 1000x1000mm thickness 10 to 12 mm	sqm	155.04	1518.00	235,350.72
19	14.57	Providing and applying 2mm thick white cement based Acrylic grade putty with minimum 3 coats applied @ 4.0 kg/ 10Sqm as per relevant IS code 17545:2021 (Product such as Asian trucare, Berger Happy walls Putty , Birla Opus One pro smooth) to make the surface smooth and even with all tools tackles and labour etc. complete for the work . (This Item to be use in heigher grade painting works Item No. 14.65)	Sqm	1010.5	81.00	81,850.50
20	14.59	Providing and applying Polymaric cement primer on all surface applied @ 0.80 litrs/10 sqm as per relevant I.S. code 15489:1974 (product such as Birla white primacoat/activcoat, Asian Trucare , Dulux interior cement primer, Opus Calista / I10) with all tool tackles and labour etc. complete for the work .	Sqm	1010.5	25.00	25,262.50
21	14.62	Providing and applying Acrylic washable Distemper or lite economy Plastic emulsion paint having VOC content less than 50gms/ lit Minimum two coats up to final finish applied @ 1.25 Kg/ 10Sqm as per relevant I.S. Code 428:2000 (product such as Tractor Uno, Dulux Duval, Berger Bison, Opus Style/lite economy emulsion product such as Asian Tactor Spark , Dulux Pomise sheen, Neroloc Litil Master, Berger Bison Lite, Nippon Superio.) inclusive of providing abro tape on edges and article and cleaning of door,	Sqm	633.88	54.00	34,229.52

		DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		ows, floor and surface as required with all tools tackles and labour complete for the work.				
	.67	Providing and applying on exterior surface with ECONOMY Exterior Emulsion paint of required shades to give protective and water proof finish minimum three coats applied @ 1.43 lit / 10Sqm up to final finish as per relevant I.S. Code 15489:2013 Type -2 Class D , C (Glossy /Semi Glossy finish) (Product such as Asian Ace , Dulux Promise Exterior , Berger Wall Masta , Nerolac Suraksha Plus , Nippon Shogun Opus, One Style Power Bright) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work (With 2 Year Warranty)	Sqm	334.2	60.00	20,052.00
23	14.72	Providing and applying Glossy finish Enamel paint mimimum 2 coats in all surface applying @ 0.75 lit/ 10 Sqm up to required finish as per relevent I.S. code 2932: 2013 of (Product such as Asian Apcolite Premium Enamel , Dulux Promise Premium Enamel , Nerolac Synthatic Enamel, Opus Prime enamel) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackle and labour etc. complete for the work.	Sqm	48.6	102.00	4,957.20
24	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.				
	:7.2	Size above 200x300mm	sqm	42.42	549.00	23,288.58
25	12.9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.				
	:9.2	Size above 300x300mm	sqm	12	619.00	7,428.00
26	18.1	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required :				
	:.1.3	White Orissa pattern W.C. pan of size 580x440 mm	each	2.00	2464.0	4,928.00
27	18.13	Providing and fixing white vitreous china urinal basin with waste fitting as per IS : 2556, and other couplings in C.P. brass complete:				
	13.1	Flat back half stall urinal of size 460x380x250mm	each	2.00	1510.0	3,020.00
28	18.15	Providing and fixing one piece construction white vitreous china squatting plate urinal with an integral rim longitudinal flushing pipe, standard size G.I. flush pipe for back and front flush, C.P. brass coupling complete including cutting and making good the walls and floors etc. wherever required :	each	2.00	1712.00	3,424.00
29	18.17	Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :				
	7.11	Coloured Oval or round size 550x400mm.	each	2.00	1850.0	3,700.00
30	19.5	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and				

		DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. CONCEALED WORK including cutting chases and making good the walls etc.,				
	5.2	20 mm nominal outer dia .Pipes.	metre	30.00	142	4,260.00
	5.3	25 mm nominal outer dia .Pipes.	metre	30.00	181	5,430.00
	5.4	32 mm nominal outer dia .Pipes.	metre	30.00	241.0	7,230.00
31	19.14	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:				
	14.1	Bib cock (400 grams)	each	10.00	325.	3,250.00
	14	Soap dish plate	each	4.00	139.0	556.00
	14.15	Shower rose (revolving type) (150mm)	each	2.00	229	458.00
	14.16	Towel rail (600mm long x 20mm dia)	each	2.00	287	574.00
	14.2	Long nose bib cock (500 grams)	each	2.00	362	724.00
	14.4	Piller Cock (400 grams)	each	2.00	338	676.00
	14.6	Stop cock (concealed) (600 grams)	each	10.00	420	4,200.00
32	19.15	Providing and fixing stainless steel drain jali of approved make/quality.	each	8.00	43.00	344.00
33	19.42	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	litre	1500.00	6.00	9,000.00
34	12.46	15 mm thick Table rubbed polished Granite stone slab in risers and treads of steps skirting dado and pillars laid on 12mm (Average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polishing etc. complete (single stone is to be used for risers and treads of steps and width of stone for skirting and dado shall be equal to the height of skirting & dado and length of 1.0 m).				
	16.2	Granite stone black	sqm	37.2	2311.00	85,969.20
35	9.3	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer.				
	3.1	Electric resistance or induction butt welded tubes Grade-250	kg	250	75.00	18,750.00

As per Estimate Amount Rs. 2,015,648.91

Extra for Internal Electrification Add Above 5.11 % 102,999.66

00.0 2,118,648.57

GST Add Above 18% 381,356.74

Grand Total Rs. 2,500,005.31

Say Rs.

Sub Engineer
Nagar Palik Nigam,
Korba

Astt. Engineer
Nagar Palik Nigam,
Korba