



कार्यालय नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क./316 एवं 331/दर्री जौन/2020/

कोरबा दिनांक 03.07.2020

निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियंता लोक निर्माण विभाग रायपुर द्वारा प्रचलित (PWD BUILDING SOR 01.01.2015से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरो पर तथा शेड्यूल अनुसार आईटम दरों पर मैन्युअल निविदा वेब साईट से डाउनलोड कर त्रि-लिफाफा पद्धति के माध्यम से निविदा आमंत्रित की जाती है।

- 01 निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 01.08.2020 सायंकाल 3:00 बजे तक
- 02 निविदा खुलने की अंतिम तिथि - 01.08.2020 सायंकाल 4:00 बजे तक

क.	कार्य का नाम	प्राक्कलन राशि	धरोहर राशि	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क्र.51 कबीर भवन के पास लान टेनिस कोर्ट निर्माण एवं अन्य विकास कार्य। (विधायक मद)	7,00,000/-	5,500/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01-08-20
2	वार्ड क्र. 47 डुमरमुडा एवं जमनीपाली में सार्वजनिक मंच निर्माण (विधायक मद)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01-08-20

निविदा की शर्तें :-

- निविदा दरें प्रचलित सी.एस.आर. से कम या अधिक प्रतिशत दरों पर दिया जावें, सी.एस.आर. के अंतर्गत के आईटमों पर पृथक से आईटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज हाथो - हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमो यथा कोरियर, सर्विस,साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा प्रपत्र आयुक्त नगर पालिक निगम, साकेत भवन आई.टी.आई.चौक कोरबा, जिला - कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
- निविदा प्रपत्र नगर पालिक निगम,कोरबा के वेबसाईट WWW.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form- A/B/ABC (जारी दिनांक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा प्रपत्र त्रि- लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा :-
(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र,आयकर चुकता प्रमाण पत्र,निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी एवं अमानत राशि का टी.डी.आर./एफ.डी.आर.जो कि आयुक्त नगर पालिक निगम,कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा निविदा प्रपत्र होगा।
(स) तृतीय लिफाफे में उपरोक्त दोनो लिफाफे होंगे तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
- जिन ठेकेदारों द्वारा नगर पालिक निगम,(साड़ा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साड़ा) के हित के विरुद्ध कार्य किया गया हो उनहे निविदा भरने की प्रात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनर शीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर प्रमाण पत्र/पेन नम्बर जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र,कर्मचारी भविष्य निधि संगठन,कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एन.आई.टी.) हस्ताक्षर युक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र.04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
- कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्र.मॉक,निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
- निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
- निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
- निर्धारित प्रारूप में निविदा प्रपत्र,निविदा प्रपत्र शुल्क,अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाये जाने पर ही निविदा दर संबंधित लिफाफा खोला जावेगा,अन्यथा निविदा निरस्त कर दी जावेगी।
- ठेकेदार को अपनी दरे शब्दों एवं अंको में लिखना अनिवार्य होगा।
- शासन के विभिन्न विभागों जैसे :- खनिज विभाग,श्रम विभाग,समाज कल्याण विभाग,इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों /आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
- ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्राक्धान के अंतर्गत कार्यवाही की जावेगी।
- कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई. सी.द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी संपूर्ण जवाबदारी ठेकेदार की होगी।
- सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जब की निविदा की दरों में काफी कमी हो जैसे निविदा दाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदा दाता को निविदा दर एवं

- अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर.आफिस टाईम डिपॉजिट अथवा एन.एस.सी.जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम से देय होगा, जो माग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष एवं 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिए परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी।
 17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 01 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
 18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथ पत्र कंडिया क्र.- 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
 19. ईट से संबंधित निर्माण कार्यों में फलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
 20. निविदा प्रपत्र अहस्तातरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
 21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
 22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम, कोरबा के पास सुरक्षित रहेगा।
 23. निविदा खुलने की तिथि में अवकाश होने पर अगामी तिथि को निविदा संबंधित कार्यवाही मानी जावेगी।

नोट :-


01. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगर जमा रसीद पृथक से लिफाफे में स्वीकार किये जायेगे जो आयुक्त नगर पालिक निगम, कोरबा के नाम से देय हो।
02. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

(ठेकेदार के हस्ताक्षर)

नाम.....

पूर्ण पता.....
.....

मोबाई न.-.....


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा(छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT

Name : Work const. of saarvajanik munch at dumarmuda and jamanipali w no. 47 vidhaayak mad 2019 - 20

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	19.29	185.00	3,568.65
2	1.2	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	sqm	100.00	7.20	720.00
3	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	9.64	65.00	626.60
4	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	26.95	371.00	9,998.45
5	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	cum	3.82	2970.00	11,345.40
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	11.45	4163.00	47,666.35
7	3.4	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	6.05	97.50	589.87
8	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	923.00	54.50	50,303.50
9	3.14	Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer.	kg	10.00	43.50	435.00
10	3.16	Making 50mm thick plinth protection of plain cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded crushed stone aggregate 20mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with sand including finishing the top smooth.	sqm	9.00	273.00	2,457.00
11	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to				

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)	cum	9.41	3350.00	31,523.50
	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	5.92	121.00	716.32
13	9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.				
	6.2	In gratings, frames; guard bar, ladder, railings, brackets, gates and similar works.	Kg	150.00	68.00	10,200.00
14	9.37	Providing and fixing M.S. fan clamp/hook for ceiling fan made out of 16 mm dia M.S. bar bent to shape with hooked ends in R.C.C. slabs, beams during laying including painting the exposed portion of loop.	each	2.00	97.00	194.00
15	9.57	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.				
	57.2	SS Grade 304	kg	20.00	525.00	10,500.00
16	11.1	Providing and making 6mm thick cement plaster of mix:				
	1.2	In Cement mortar 1:4 (1 cement : 4 fine sand)	sqm	16.00	87.00	1,392.00
17	11.2	Providing and making 12mm thick cement plaster of mix:				
	2.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)	sqm	39.60	96.50	3,821.40
18	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)	sqm	50.40	113.00	5,695.20
19	11.40	Making groove in cement plaster while plastering upto 10 mm deep and 10 mm wide.	metre	28.00	1.30	36.40
20	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	24.11	139.00	3,351.29
	1.4	Edge of slab, breaks in floor and walls upto 200mm.	metre	20.50	34.00	697.00
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	11.20	297.00	3,326.40
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	20.56	235.00	4,831.60
	1.8	Beams, lintels, cantilevers & walls	sqm	26.7	202.00	5,393.40
21	12.49	25 mm thick KOTA stone slab flooring over 20mm (Average) thick base of cement mortar 1:4 laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including grinding rubbing and polishing etc. complete (Area of slab to be over 0.20 sqm and upto 0.50 sqm)	sqm	16.00	897.00	14,352.00
22	12.50	KOTA stone slab 25mm thick in risers and treads of steps, skirting dado and pillar laid in 12mm (Average) thick cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete. (single stone is to be used for riser and treads of steps and the width of stone for skirting and dado shall be equal to the height of skirting/ dado up to length of 1.0 M.)	sqm	4.95	990.00	4,900.50
23	12.51	Extra for nosing in steps and treads of Kota stone slab.	metre	4.50	69.50	312.75

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
24	12.65	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm				
	55.2	Pigment Coloured (rubber mould) precast interlock concrete blocks	sqm	15.00	632.00	9,480.00
25	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	55.60	94.50	5,254.20
26	14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:				
	15.1	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	sqm	50.4	56.00	2,822.40
27	14.9	Distemping with acrylic washable distemper to give an even shade.				
	9.1	On new work (Two or more coats)				
28	18.77	Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.	sqm	55.60	38.00	2,112.80
	77.1	Tee/ Tee with door/ Bend 45° / Bend 90°				
	.1.2	110 mm				
29	18.76	Providing and fixing on wall face or. under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.	each	2.00	154.00	308.00
	76.2	110 mm dia pipe.	metre	4.00	267.00	1,068.00

As per Estimate Amount Rs. 249999.98

Say Rs. 2,50,000/-
X 02

5,00,000/-

Sub Engineer
Nagar Palik Nigam
Korba (C.G.)

Assistant Engineer
Nagar Palik Nigam
Korba (C.G.)

Executive Engineer
Nagar Palik Nigam
Korba (C.G.)