



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

बालको नगर जोन

फा.क्र./2045, 2047, 2055, 2056, 2058, 2059, 2060 एवं 2062/निर्माण(बालकोनगर जोन)/2024-25 कोरबा, दिनांक 18.10.2024

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 & PWD Electrical SOR 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाईट से डाउनलोड कर मुहरबंद लिफाफा में निविदा आमंत्रित की जाती है :-

- निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने की अंतिम तिथि - 04.11.2024 सायंकाल 3:00 बजे तक
- निविदा खुलने की अंतिम तिथि - 04.11.2024 सायंकाल 4:30 बजे

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 34 चेकपोस्ट के पास सामुदायिक भवन में नई सुविधा प्रदाय। (पार्षद मद वर्ष 2022-23)(तृतीय निविदा)	3,00,000/-	3,000 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	04.11.2024
2	वार्ड क्र. 34 में स्थित शासकीय प्राथमिक शाला चेकपोस्ट में 02 नग अतिरिक्त कक्ष का निर्माण कार्य। (जिला खनिज संस्थान न्यास मद वर्ष 2024-25) (द्वितीय निविदा)	11,64,500/-	9,000 /-	750/-	Form-A	04 माह	सक्षम श्रेणी	04.11.2024
3	वार्ड क्र. 34 चेकपोस्ट भद्रापारा में सामुदायिक भवन के सामने मंच निर्माण कार्य। (अधोसंरचना मद वर्ष 2024-25) 7.00 करोड़ (द्वितीय निविदा)	5,00,000/-	5,000 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	04.11.2024
4	वार्ड क्र. 35 हाउसिंग बोर्ड मुख्य चौक पर स्थित सामुदायिक भवन विस्तार एवं जीर्णोद्धार कार्य। (अधोसंरचना मद वर्ष 2024-25) 7.00करोड़ (द्वितीय निविदा)	10,00,000/-	7,500 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	04.11.2024
5	वार्ड क्र. 40 क्षेत्रातर्गत नेहरु नगर बालको में आर.सी.सी. कवर्ड नाली एवं सी.सी.रोड निर्माण कार्य। (अधोसंरचना मद वर्ष 2024-25) 7.00 करोड़ (द्वितीय निविदा)	10,00,000/-	7,500 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	04.11.2024
6	वार्ड क्र. 40 नेहरु नगर कृष्ण मोहन शर्मा ऑफिस के पीछे से स्वास्थ्य केंद्र तक नाली निर्माण कार्य 100 मीटर। (अधोसंरचना मद वर्ष 2024-25) 7.00 करोड़ (द्वितीय निविदा)	5,00,000/-	5,000 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	04.11.2024
7	वार्ड क्र. 41 क्षेत्रातर्गत परसाभाडा बालको में सी.सी.रोड मरम्मत कार्य। (अधोसंरचना मद वर्ष 2024-25) 7.00 करोड़ (द्वितीय निविदा)	10,00,000/-	7,500 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	04.11.2024
8	वार्ड क्र. 37 अंतर्गत अंबेडकर चौक के पास आर.सी.सी.नाली का निर्माण कार्य। (पार्षद मद वर्ष-2023-24) (द्वितीय निविदा)	7,00,000/-	5,500 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	04.11.2024

निविदा की शर्तें:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से भेजना होगा अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, आई.टी.आई. चौक साकेत भवन, जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाईट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र **Form - A/B/ABC** (जारी दिनोंक तक समस्त संशोधनों के साथ) आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा मुहरबंद लिफाफा में मान्य किया जावेगा जो निम्नानुसार होगा:-
 - (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित निविदा प्रपत्र शुल्क का डीडी, निविदाओं में निविदाकार को फिजिकल दस्तावेज के साथ निविदा सूचना प्रसारित होने के पश्चात् राशि रु. 100/- के स्टॉम्प पर निष्पादित शपथ पत्र जिसमें संबंधित कार्य का नाम एवं कार्य की निविदा क्रमांक अंकित हो प्रेषित करना अनिवार्य होगा एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
 - (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 - (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफे होंगे तथा आवश्यकता पडने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम, कोरबा के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम, कोरबा के हित के विरुद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नहीं होगी।
6. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकरी पिछले 03 वित्तीय वर्षों का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. (जीवित) पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी मविष्य निधिसंगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना ठेकेदार के हस्ताक्षर सहित निविदा दस्तावेजों के साथ प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना कर्मांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिका स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंको में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध निविदा शर्तानुसार एवं मेयर इन काउंसिल के निर्णयों के अनुरूप कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत की दर से सुरक्षा राशि रनिंग देयकों के साथ 01 वर्ष हेतु साथ ही मरम्मत एवं संधारण प्रकृति के कार्यों को छोड़कर शेष कार्यों के देयकों से 5 प्रतिशत की दर से पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जायेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।

18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित राशि रु. 100/- नॉन ज्यूडिशियल स्टॉम्प पेपर पर निम्नादित शपथ पत्र निविदा दरतावेजो के साथ संलग्न करना अनिवार्य होगा।
19. ईट से संबंधित निर्माण कार्यों में प्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं शर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त, नगर पालिक निगम कोरवा का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा में सफल निविदाकार को ऐसे कार्य जिराकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
23. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
24. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।
25. ठेकेदार द्वारा संपादित किये गए कार्यों के देयको का भुगतान वजट आवंटन और राशि उपलब्ध होने पर किया जाएगा।
26. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
27. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नया रायपुर (छ.ग.) को Uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।


(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

.....

मोबाईल नं.-



कार्यपालन अभियंता
नगर पालिक निगम
कोरवा (छ.ग.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)
ABSTRACT

Work **EXTENSION AND DEVELOPMENT WORK OF SAMUDAYIK BHAWAN SITUATED AT MAIN CHOWK HOUSING BOARD**
WARD 35
per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01 01 2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for				
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	28.32	297.00	8,411.04
2	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size)	cum	2.41	4163.00	10,032.83
3	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete				
	12.1	Thermo-Mechanically treated bars FE 415	kg	230.2	54.50	12,545.90
4	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)	cum	11.25	3263.00	36,708.75
5	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	11.25	121.00	1,361.25
6	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	75.6	75.00	5,670.00
7	9.47	Providing and fixing aluminium work for doors, windows, ventilators and partitions made out of extruded aluminium standard sections (main section with minimum 1.5mm thickness) conforming to IS: 733, IS: 1285 mitred and jointed mechanically including aluminium cleats, neoprene weather stripping gasket beveled edge beading, screws duly fixed in wall/ floor with fixing clips or hold fasteners or bolts and nuts as required aluminium sections shall be anodized transparent or dyed to approved shade according to IS: 1868, minimum anodic coating shall be of grade AC-15. (Glazing to be paid for separately:				
	17.2	For shutter of doors, windows & ventilators including providing and making provision for fixing of fitting wherever required including the cost of PVC/ neoprene gasket required (Fittings shall be paid for separately).	Kg	644.52	338.00	217,847.76
8	9.51	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete. (Cost of aluminium snap beading shall be paid in basic item):				
	51.2	With float glass panes of 5 mm thickness	sqm	125.15	708.00	88,606.20
9	11.2	Providing and making 12mm thick cement plaster of mix:				
	2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	293.94	91.50	26,895.51
10	11.3	Providing and making 15mm thick cement plaster on the rough side of single				

	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	or half brick wall of mix:				
12	14.22 In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	256.37	107.00	27,431.59
12	12.12 Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete	sqm	111.24	963.00	107,124.12
12	14.22 Painting on new work (two or more coats) to give an even shade with:				
	22.1 Satin synthetic enamel paint	sqm	4.2	55.00	231.00
13	14.13 Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	1716.68	94.50	162,226.26
14	14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:				
	15.1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	sqm	1716.68	56.00	96,134.08
				As per Estimate Amount Rs.	801226.28


 S/E
 Nagar Palik Nigam
 Korba(C.G.)


 A.E.
 Nagar palik Nigam
 korba(C.G.)

OF THE MUNICIPAL CORPORATION, KORBA (C.G.)


Abstract


:- EXTENSION & Development Work of Samudra Shivan situated at Main chowk Housing Board Ward 35

PWD (Elec. 01.06.2020)

No	Ref.	Item of Work	Unit	Rate	Qty	Amount
1	2.7	Wiring for light/ fan/ exhaust fan / call bell point with 3x1.5 sqmm FRLS PVC insulated stranded copper conductor wire for phase, neutral and earth in surface FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) with 5/6 amp modular switch, modular base and cover plate, suitable size G.I. box as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)				
	2.7.1	Short Point	Point	227.00	20.00	4540.00
	2.7.2	Medium Point	Point	347.00	40.00	13880.00
	2.7.3	Long Point	Point	465.00	20.00	9300.00
2	2.11	Wiring for power plug point with 3x4 sq mm FRLS PVC insulated stranded copper conductor wire for phase, neutral and earth in surface FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) along with modular type 16 Amp switch and 6 pin 16 amps socket outlet with modular base and cover plate, suitable size G.I. box, earthing the switch box and socket outlet with same size wire etc. as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)				
	2.11.2	Medium Point	Point	817.00	5.00	4085.00
	2.11.3	Long Point	Point	1157.00	5.00	5785.00
3	2.13	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, wire in surface FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) etc as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)				
	2.13.2	3 X 2.5 sq. mm in 20mm conduit	Metre	87.00	300.00	26100.00
4	5.4	Supplying and fixing following modular switch, socket, other accessories on the existing modular plate & switch box including connections but excluding modular plate etc. as per specification.				
	5.4.9	Fan regulator (two module size) electronic stepped type moving all rounds	Each	223.00	25.00	5575.00
	5.4.20	Ceiling rose 3 pin 5 amp	Each	40.00	60.00	2400.00
	5.4.22	Batten/ angle holder	Each	41.00	20.00	820.00
5	6.1	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, earthing etc. complete as required. P.F. should be greater than 0.9, with BEE Star rating from 3 star and above, IS: 374:2019 including all amendments.				
	6.1.3	1200 mm sweep	Each	1697.00	25.00	42425.00
6	6.6	Supplying, installation, testing and commissioning of following sizes heavy duty (continuous running) 1400 rpm exhaust fan in existing opening in wall including earthing etc. complete as per specification. P.F. should be greater than 0.9				
	6.6.3	450 mm sweep	Each	3976.00	8.00	31808.00

		ing, fixing, testing and commissioning of following LED with inbuilt electronic driver heat sink and all other accessories in existing holder/ luminaries as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio \geq 100 lumens /watt.				
	7.5	12 Watt	Each	215.00	50.00	10750.00
	6.17.7	18/20 Watt (LED Rod)	Each	266.00	20.00	5320.00
8	6.28	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Separate housing for driver etc complete as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio \geq 120 lumens /watt.				
	6.28.9	120 watt	Each	6844.00	3.00	20532.00
9	9.4	Supplying and fixing on surface/ recess horizontal type following way, 415 volts, TPN MCB distribution board of sheet steel phosphatized and powder painted, complete with tinned copper busbar, neutral busbar, earth bar, din bar, detachable gland plate, including interconnections, earthing etc. as per specification. (But without MCB/RCCB/Isolator)				
	9.4.1	4 way Single door	Each	1317.00	2.00	2634.00
10	9.10	Supplying and fixing SP MCB, 240 volts, 'B' curve, suitable for lighting and other loads in the existing MCB DB complete with connections, testing and commissioning etc. as per specification.				
	9.10.1	6 amps to 32 amps	Each	151.00	40.00	6040.00
11	9.20	Supplying and fixing following rating, 415 volts, FOUR POLES, ISOLATOR in the existing MCB DB complete with connections, testing and commissioning etc. as per specification.				
	9.20.2	63 amps	Each	621.00	2.00	1242.00
12	7.10	Providing and fixing metal clad, TP&N switch fuse unit (re- wireable), 415/500 volts, with porcelain re-wireable fuses including drilling holes on the board, connections, earthing the body etc. as per specification. (Thimbeling shall be paid separately).				
	7.10.2	63 amps	Each	1915.00	1.00	1915.00
13	12.1	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as per specification and IS Code 3043: 1987(R 2016)	Set	3243.00	1.00	3243.00
14	12.18	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ concealed conduit/ submain wiring/ cable as per specification.	Metre	19.00	20.00	380.00
					Total Rs.	198774.00


Sub Engineer
Municipal Corporation,
Korba (C.G.)


Assitt. Engineer
Municipal Corporation,
Korba (C.G.)

Executive Engineer
Municipal Corporation,
Korba (C.G.)