कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

क्र.क./456/निर्माण कोरबा जोन/2018 कोरबा, दिनांक 27.12.2018

निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में निर्माण कार्य हेतु पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर एवं शेड्यूल अनुसार कार्यो हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइड से डाउनलोड कर आमंत्रित की जाती है :–

क	कार्य का नाम (निगम मद)	प्राक्कलन राशि	धरोहर राशि	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने हेतु आवेदन प्रस्तुत करने की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1.	सेपटेज मैनेजमेंट हेतु फिक्ल स्लज ट्रीटमेंट प्लांट का निर्माण कार्य। (निगम मद)	1,15,700/–	1,200 /–	750/–	01 माह	सक्षम श्रेणी	10.01.2019	11.01.2019	16.01.2019

शर्तें :–

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथके से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा प्रपत्र की प्रतियों नगर पालिक निगम, साकेत भवन रामपुर, कोरबा कार्यालय से उपरोक्त कार्यों हेतु नाम के सम्मुख अंकित राशि नगद जमा कर उपरलिखि तिथि तक सायं 5.00 बजे तक अवकाश के दिनों को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मांगाना हो तो रू. 50/– अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नही होगी।
3. निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात प्राप्त निविदाऐं स्वीकार नही की जावेंगीं।
4. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य ना किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरूद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नही होगी।
5. निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड)की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकरी पिछले वित्तीय वर्ष का आय प्रमाण पत्र/पेन नम्बर पत्र, जी. एस. टी. प्रमाण पत्र एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र एवं धरोहर राशि निविदा प्रपत्र प्राप्त करने के तिथि के 5.30 बजे तक अनिर्वाय होगा।
6. निविदा प्रपत्र उन्ही ठेकेदारो को दिया जायेगा जिन्हे इस प्रकार के कार्यों का अनुभव हो।
7. पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती है और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहे तो उनके समक्ष खोले जावेंगे।
8. सम्पूर्ण किये गये कार्यों के लिये प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिये एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में प्रत्येक चल देयकों में से 03 वर्ष के लिये रोकी जावेगी।
9. आवेदन के साथ रू. 10.00 लाख या उससे अधिक लागत के निर्माण कार्यो की निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत् पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
10. ठेके से संबंधित निविदा प्रपत्र उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
11. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यो का विवरण राशि सहित मूलप्रति में शपथ पत्र देना अनिवार्य होगा।
12. कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंन्ट की खरीदी ठेकेदारों को स्वयं करनी होगी।
13. निविदा प्रपत्र अहस्तांतरणीय होगा।
14. निविदा दरों असमान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
15. सशर्त निविदाओं पर विचार नही किया जावेगा।
16. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधिनस्त अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
17. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
18. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा (कोरबा जोन) से प्राप्त किये जा सकते है।

नोटः–
1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जाव

कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

ESTIMATE FOR PLANTED DRYING BED
[Size 7.50m x 5.00m]

Itm. No	Particulars	No.	L	B	H		Quantity	Rate	Per	Amount (Rs.)
1	2	3	4	5	6		7	8	9	10
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.									
	In all types of soils.	1	8.10	5.60	0.40		18.144	185.00	Cum	3357.00
	(PWD SOR Item no.1.1/ Page no.9)									
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.									
	(PWD SOR Item no.1.18/ Page no.11)	1	8.10	5.60	0.10		4.536	371.00	Cum	1683.00
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size). (PWD SOR Item no.3.1.2/ Page no.23)	1	8.10	5.60	0.10		4.536	2659.00	Cum	12061.00
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size). (PWD SOR Item no.3.1.4/ Page no.23)									
	For bed concrete	1	8.10	5.60	0.10		4.54			
	For Coping at top of brick masonary	2	5.00	0.20	0.05		0.10			
		2	7.90	0.20	0.05		0.16			
	Coping at top on walls of welded mesh	3	1.00	0.20	0.05		0.03			
						Total	4.82	3552.00	Cum	17135.00
5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 for superstructureCement Mortar 1:4 (1 cement : 4 coarse sand) (3452) (PWD SOR Item no.7.5.2/ Page no.45)									
	long walls	2	7.90	0.20	1.30	4.11				
	Short walls (Inlet)	1	5.00	0.20	1.20	1.20				
	Short walls (Outlet)	1	5.00	0.20	1.40	1.40				
	Inlet chamber walls	3	1.00	0.20	1.20	0.72				
	For Outlet Chambers	2	0.60	0.20	0.65	0.16				
		2	0.80	0.20	0.65	0.21				

Itm. No	Particulars	No.	L	B	H		Quantity	Rate	Per	Amount (Rs.)
1	2	3	4	5	6		7	8	9	10
						7.79	7.79	3762.00	Cum	29314.00
6	Providing and making 12 mm thick cement plaster with under layer of 12mm thick cement plaster 1:4									
	(PWD SOR Item no.11.2.2/ Page no.103)									
	For Inside	2	7.50		1.30	19.50				
		1	5.00		1.20	6.00				
		1	5.00		1.40	7.00				
		6	1.00		1.20	7.20				
		4	0.60		0.65	1.56				
		4	0.80		0.65	2.08				
						43.34	43.34	103.00	Sqm	4464.00
7	Providing and making 15 mm thick cement plaster with under layer of 15mm thick cement plaster in C.M.1:4									
	(PWD SOR Item no.11.3.2/ Page no.103)	2	7.9		1.30	20.54				
		1	5.0		1.20	6.00				
	For Outside	1	5.0		1.40	7.00				
					Total	33.54	33.54	120.00	Sqm	4025.00
8	Supply of mineral aggregate like broken stone/ crush stone (crushed in mechanical crusher) as per clause 520 at road site including all lead and stacking etc complete									
	(PHED SOR Item no.24.11/ Page no.)									
	a) 45 mm standard size crushed stone	1	7.50	5.00	0.30	11.25				
	Deduct volume of inside chambers									
	Outlet chamber	2	0.80	0.80	0.30	0.38				
	(PWD SOR Item no.1.5(iv)/ Page no.7)				Net	10.87		1083.00	Cum	11768.00
	b) 22.4 mm standard size crushed stone	1	7.50	5.00	0.20	7.50				
	Deduct volume of inside chambers									
	Outlet chamber	2	0.80	0.80	0.20	0.26				
	(PWD SOR Item no.1.5(v)/ Page no.7)					7.24		1380.00	Cum	9997.00
	c) 6.7 mm standard size crushed stone	1	7.50	5.00	0.15	5.63				
	Deduct volume of inside chambers									
	Outlet chamber	2	0.80	0.80	0.15	0.19				
	(PWD SOR Item no.1.5(viii)/ Page no.7)					5.43		1573.20	Cum	8547.00
9	Steel work welded in built up sections/ framed work including cutting,hoisting,fixing in position and applying a priming coat of red oxide zinc chromate primer									
	(PWD SOR Item no.9.6.2/ Page no.80)	1				72.29		68.00	Kg	4916.00
	square mesh in 6 mm dia bars at 25 mm c/c of size 1.10 m x 2.20 m.NO. of bars along short span=1100/25=44 Nos.of L=2.20 Mtr. Total Length=1.10x 88= 96.80 m and No. of bars along long span=2220/25= 88 No.of L=1.10 mtr.Total Length=2.20x44=96.80mtr,TOTAL Length of 6 MM dia. BARS=193.60 MX 0.22 kg/m=42.59 KG									
	M.S.Angle for Frame -50x50x6 mm MSA-[2x1.10+2X2.20]=6.60 mtr@4.5 Kg/mtr=29.7 Kg									
	TOTAL - 42.59+29.7=72.29 KG									

Itm. No	Particulars	No.	L	B	H		Quantity	Rate	Per	Amount (Rs.)
1	2	3	4	5	6		7	8	9	10
10	Plantation of phytorite in the tank including cost of plant, labour etc complete.									
	(Market Rate)	1						2500.00	Job	2500.00
11	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete									
	(PWD SOR Item no.18.76.3/ Page no.170)									
	150 mm dia PVC Pipes	1	4.50			4.50				
		1	0.50			0.50				
						5.00		440.00	Rmt	2200.00
12	Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion									
	(PWD SOR Item no.18.77/ Page no.170)									
	BEND 150mm dia (18.77.1.3)	1						273.00	Each	273.00
	End Cap 150 mm dia(18.77.4.2)	1						59.00	Each	59.00
13	Providing and constructing soak pit 1.20x1.20x1.20m filled with brick bats including SW drain pipe 100 mm dia.and 1.20 m long complete as per standard design									
	(PWD SOR Item no.20.31/ Page no.195)	1.0					1.0	1709	No	1709.00
14	Color washing such as green ,blue or buff with lime to give an even shade									
	(PWD SOR Item no.14.7.1/ Page no.132)									
	Inner side- Qty same as item No.6					43.34				
	Out side- Qty same as Item NO.7					33.54				
	Total QTY.	1		Total		76.88	71.8	12	Sqm	862.00
15	Painting on new work(two or more coats) to give an even shade with premium synthetic enamel paint to welded mesh									
	(PWD SOR Item no.14.22.1/ Page no.134)	1	2.10	1.10			2.31	47.00	Sqm	108.57
16	Lettering with black japan paint per cm height									
	Height of letter to be painted 15 cm- 43 Nos	62					62	10.50	No	651.00
	(PWD SOR Item no.14.41/ Page no.136)									
	Rs.0.70/ per letter per cm height(15 X 0.70= Rs.10.50 /per letter									
								TOTAL	Rs.	115630

Say ₹ 1,15,700/-

5/15