



# कार्यालय नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क्र./264,265/दर्श जोन/2018-19/

कोरबा दिनांक 04.01.2019



## निविदा आमंत्रण सूचना

लोक निर्माण विभाग द्वारा एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित निर्माण कार्य हेतु प्रमुख अभियंता लोक निर्माण विभाग (भवन), रायपुर द्वारा 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर मैनूअल/ऑन लाईन निविदा वेब साईड से डाउनलोड कर आमंत्रित की जाती है।

क.	कार्य का नाम	प्राक्कलन राशि	धरोहर राशि	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने हेतु आवेदन जमा करने की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की तिथि
1	वार्ड क्र. 46 अंतर्गत अयोध्यापुरी मध्य चौक मंच,नाली,एवं सी.सी.रोड़ का मरम्मत कार्य (प्रथम निविदा)	3,90,500/-	4,000/-	750/-	02 माह	वर्ग "डी" एवं उपर की श्रेणी	14.01.19	18.01.19	25.01.19
2	वार्ड क्र. 43 राजीव नगर में सार्वजनिक सांस्कृतिक मंच निर्माण।	5,00,000/-	5,000/-	750/-	02 माह	वर्ग "डी" एवं उपर की श्रेणी	14.01.19	18.01.19	25.01.19


शर्तें

- निविदा दरें प्रचलित सी.एस.आर. से कम या अधिक प्रतिशत दरों पर दिया जावें, सी.एस.आर. के अंतर्गत के आईटमो पर पृथक से आईटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र की प्रतियाँ नगर पालिक निगम, साकेत भवन रामपुर कोरबा कार्यालय से उपरोक्त कार्य हेतु नाम के सम्मुख अंकित राशि नगद जमा कर उपर लिखे तिथि को साँय 5.30 बजे तक अवकाश के दिन को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मँगाना हो तो रु. 50.00 अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी। साथ ही निविदा प्रपत्र निगम के वेब साईड से डाउनलोड करने पर निविदा प्रपत्र के साथ में (अ) धरोहर राशि एवं निविदा प्रपत्र शुल्क (ब) अर्हता संबंधित समस्त दस्तावेज एवं (स) निविदा प्रपत्र के साथ प्रस्तुत दर-तीन पृथक- पृथक लिफाफे में दी जावें, शुल्क एवं दस्तावेज परीक्षण उपरांत सही पाये जाने पर ही निविदा दर खोली जावेगी।
- निविदा प्रपत्र केवल स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किये जावेगे। निर्धारित तिथि को साँय 3.00 बजे के पश्चात प्राप्त निविदाओं पर विचार नहीं किया जावेगा।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो, उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने के इच्छुक ठेकेदारों को आवेदन के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनर शीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर प्रमाण पत्र/पैन नम्बर एवं छत्तीसगढ़ वाणिज्यिक पंजीयन प्रमाण पत्र एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, अमानत राशि का एफ.डी.आर./टी.डी.आर./नगद जमा की रसीद एवं निविदा प्रपत्र वेब साईड से डाउनलोड करने पर निविदा प्रपत्र शुल्क के रूप में डिमांड ड्राफ्ट अथवा नगद जमा रसीद संलग्न करना अनिवार्य होगा, अन्यथा प्रस्तुत निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र उन्ही ठेकेदारों को दिया जावेगा जिन्हे इस प्रकार के कार्यों का अनुभव हो।
- पूर्ण रूप से भरे निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती हैं। और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहें तो उनके समक्ष खोली
- सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ एवं 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफॉरमेंस सिक्यूरिटी के रूप में रोकी जावेगी।
- आवेदन के साथ रु 10.00 लाख या उससे अधिक लागत के निर्माण कार्यों की निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं शेवा शर्तों का विनमय) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन करना आवश्यक होगा। तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- निविदा उन्ही ठेकेदारों को प्रदाय किये जावेगें जो कि कर्मचारी भविष्यनिधि संगठन एव कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
- ईट से संबंधित निर्माण कार्यों में प्लाई एस ब्रिक्स का उपयोग किया जाना अनिवार्य होगा।
- कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेन्ट की खरीदी ठेकेदारों को स्वयं करनी होगी।
- निविदा प्रपत्र अहस्तान्तरणीय होगी एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा दरें एस.ओ.आर.से असामान्य होने पर सफल निविदाकार से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर. पोस्ट ऑफिस का टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा के संबंध में किसी भी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधिनस्त अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम,कोरबा के पास सुरक्षित रहेगा।
- ठेकेदारों को उपरोक्त कार्य हेतु लगे श्रमिकों का भुगतान बैंक के माध्यम से किया जाना अनिवार्य होगा।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि

19. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा की वेब साइट [www.korbamunicipal.in](http://www.korbamunicipal.in) एवं साकेत भवन स्थित सूचना पटल एवं निर्माण शाखा (दर्सी जोन) पर भी यह टेन्डर उपलब्ध है।

**नोट :-**

1. उपरोक्त निविदा तिथियों में कोई शासकीय अथवा स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय /स्थान माना जावे।
2. अमानत राशि के रूप में एफ.डी.आर/टी.डी.आर/अथवा नगद जमा राशि की रसीद आवेदन के साथ ही स्वीकार किये जावेंगे। जो कि आयुक्त नगर पालिक निगम कोरबा के नाम पर देय होगा।

  
कार्यपालन अभियंता  
नगर पालिक निगम  
कोरबा (छ.ग.)


**OFFICE OF THE NAGAR PALIK NIGAM, ZONE-DARRI, KORBA ( C.G.)**  
**ABSTRACT**


Name of Work CONSTRUCTION OF R.C.C.CULTURAL COMMUNITY MUNCH AT RAJIV NAGAR WARD 43 (M.L.A. FUND)  
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	24.25	185.00	4,486.25
2	1.2	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	sqm	48.75	7.20	351.00
3	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	5.60	65.00	364.00
4	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	22.77	371.00	8,447.67
5	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	cum	17.60	2970.00	52,272.00
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	15.24	4073.00	62,072.52
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	13.36	4163.00	55,617.68
7	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	1930.00	54.50	105,185.00
8	3.14	Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer.	kg	18.00	43.50	783.00
9	3.16	Making 50mm thick plinth protection of plain cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded crushed stone aggregate 20mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with sand including finishing the top smooth.	sqm	2.30	273.00	627.90
10	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all				

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	12.32	139.00	1,445.60
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	20.4	297.00	6,058.80
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	35.75	235.00	8,401.25
	1.8	Beams, lintels, cantilevers & walls	sqm	45.10	202.00	9,110.20
	1.13	Weather shade, chhajja, Cornices and mouldings	sqm	1.08	294.00	317.52
11	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)	cum	18.7	3350.00	62,645.00
12	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	15.50	121.00	1,875.50
13	9.2	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	Kg	86.00	66.00	5,676.00
14	11.1	Providing and making 6mm thick cement plaster of mix:				
	1.2	In Cement mortar 1:4 (1 cement : 4 fine sand)	sqm	35.75	87.00	3,110.25
15	11.2	Providing and making 12mm thick cement plaster of mix:				
	2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	72.60	91.50	6,642.90
16	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	72.60	107.00	7,768.20
17	12.3	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.				
	3.3	75 mm thick	sqm	33.00	345.00	11,385.00
18	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	180.00	94.50	17,010.00
19	14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.				
	14.1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	180.00	41.00	7,380.00
20	14.10	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.				
	10.1	On new work (two or more coats)	sqm	180.00	44.50	8,010.00
21	9.11	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer.	sqm	15.75	3330.00	52,447.50

As per Estimate Amount Rs. 499757.  
 Selu - 500,000

  
 Sub Engg.

  
 B.F.