

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क.595 / निर्माण / 2023

सिस्टम टेंडर नं: 151129

कोरबा दिनांक 08.01.2024

तृतीय ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र फार्म A में निविदा आमंत्रित की जाती है :-

क.	कार्य का नाम	प्राक्कलन राशि(लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (DD)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क 06 रवि साउंड दुकान से नवरंग लाल दुकान तक आर.सी.सी.नाली का निर्माण कार्य	40.00	30000.00	4 माह	1500.00	वर्ग डी एवं प्रवर श्रेणी	20.01.2024 से

शर्तें:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र/पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का DD एवं शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से निविदा खुलने की तिथि में दोपहर 3.00 बजे तक आयुक्त,नगर पालिक निगम,कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा को उपलब्ध कराना अनिवार्य होगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का DD जो कि आयुक्त, नगर पालिक निगम,कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में फलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों अस्मान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा प्रपत्र फार्म -ए की कंडिका 11 अनुसार एस्कलेशन देय नहीं होगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।

7
कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		08.01.2024	15.00	08.01.2024	13.00	Release Tender
2		Bid Submission	08.01.2024	13.00	19.01.2024	17.30	
3		Physical Document Submission	08.01.2024	13.00	20.01.2024	15.00	
4	Tender Open		20.01.2024	16.00	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)
ABSTRACT


Name of Work : CONSTRUCTION OF RCC DRAIN FROM RAVI SOUND DUKAN TO NAVRANG LAL SHOP WARD NO. 06
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	16.42	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	cum	243.12	768.00	186,716.16
2	16.43	Demolishing cement concrete including disposal of material within 50 metre lead.				
	13.2	1:3:6 or richer mix	cum	118.15	549.00	64,864.35
3	16.3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.				
	3.3	In cement mortar.	cum	2.73	263.00	717.99
4	1.26	Carriage by mechanical transport upto 5 km lead:				
	26.3	Dismantled Building debris (Mulba)	cum	364	91.50	33,306.00
5	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	1309.2	185.00	242,202.00
6	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	92.70	371.00	34,391.70
7	1.7	Extra rate for quantity of work executed in or under water and/ or liquid mud including pumping out water.	cum	324.45	51.00	16,546.95
8	1.10	Pumping out water caused by springs tidal or river seepage, broken water main or drains and like during Excavation or during Excavation and laying of base concrete (volume to be calculated taking height from water level to bottom of pit and to be measured and paid) .	cum	324.45	146.00	47,369.70
9	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	cum	93.65	2970.00	278,140.50
10	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	321.85	4163.00	1,339,861.55
11	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	18828.22	54.50	1,026,137.99
12	3.9	Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but	cum	66.92	469.00	31,385.48

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	excluding reinforcement.				
13	12.65 Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm				
	55.2 Pigment Coloured (rubber mould) precast interlock concrete blocks	sqm		632.00	
14	3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.5 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	41.2	4073.00	167,807.60
15	1.26 Carriage by mechanical transport upto 5 km lead:				
	26.1 Earth	cum	1109.00	111.00	123,099.00
16	2.1 Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1 Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	1573	139.00	218,647.00
	1.7 Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	112.50	235.00	26,437.50
17	9.15 Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	kg	2340.00	67.50	157,950.00

As per Estimate Amount Rs. 3995581.46

Say Rs 40.00 Lakhs



Sub Engineer
Nagar PalikNigam
Korba (C.G.)



Assistant Engineer
Nagar PalikNigam
Korba (C.G.)