

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

कोरबा दिनांक 14.08.2025

फा.क्र.329/2025

सिस्टम टेंडर नं.173802

चतुर्थ ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 एवं विद्युत हेतु (01.06.2020) से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्चरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है:-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि - 05.09.2025 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 05.09.2025 सायंकाल 4.00 बजे से

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	परिवहन नगर जोन अंतर्गत स्थित प्रेस कामप्लेक्स में महिला एवं पुरुष शौचालय का निर्माण कार्य (जिला खनिज न्यास मद)	10.00	7500/-	02 माह	750/-	वर्ग डी एवं प्रवर श्रेणी	03.09.2025 से

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र, पैन नम्बर, वैध जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई. चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा के पते पर भेजना होगा। निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
- अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे एवं कर्मचारी भविष्य निधि संगठन (ई.पी.एफ.) एवं विभिन्न प्रावधानों को धारा 1952 के तहत निविदाकार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत तीन माह की अवधि में जमा किये गये TRRN Payment Detail चालान की प्रति प्रस्तुत करना तथा ऑनलाईन अपलोड किया जाना अनिवार्य होगा।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कंडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
16. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
17. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।

प्रतिलिपि:-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

कार्यपालक अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		14.08.2025	15.30	14.08.2025	15.30	Release Tender
2		Bid Submission	14.08.2025	15.30	01.09.2025	17.30	
3		Physical Document Submission	14.08.2025	15.30	03.09.2025	15.00	
4	Tender Open		03.09.2025	16.00	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Name of work:- Construction Of Male and female Toilet block at Press Complex
Transport nagar at T.P. Nagar zone

As per SOR: Schedule of rates public works department [PWD BUILDING-01-01-2015]

S. N.	SOR Ref.	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1	In all types of soil								
			12	1.20	1.20	1.20	20.74			
			4	2.60	0.60	0.60	3.74			
			4	1.60	0.60	0.60	2.30			
			1	3.50	2.80	1.80	17.64			
						Total=	44.42	Cum	185.00	8218.44
2	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels for:								
	1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
			48	0.50	0.30		7.20			
			24	0.20	0.6		2.88			
			24	0.30	0.6		4.32			
			16	4.50	0.300		21.60			
			16	3.10	0.300		14.88			
						Total=	50.88	Sqm	139.00	7072.32
	5	Columns, Pillars, Piers and likes- rectangular or square in shape								
			24	0.20		2.10	10.08			
			24	0.30		2.10	15.12			
						Total=	25.20	sqm	297.00	7484.40
	7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
			4	4.60	3.00		55.20			
		chhajja	4	3.00	0.60		7.20			
			2	3.00	2.40		14.40			
						Total=	76.80	sqm	235.00	18048.00
	8	Beams, lintels, cantilevers & walls								
			16	4.50	0.300		21.60			
			16	3.10	0.300		14.88			
						Total=	36.48	sqm	202.00	7368.96


		Wall of any thickness including attached pilasters, buttresses etc. in super							
		soplic tank	8	3.00	1.00		43.20		
			12	2.40	1.00		61.64		
						Total=	95.04	sqm	228.00
3	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moonum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.							21669.12
			12	1.20	1.20	0.10	1.73		
			8	2.00	0.60	0.10	1.25		
			8	1.00	0.00	0.10	0.77		
			4	3.00	2.00	0.00	20.10		
			4	3.00	1.50	0.10	1.00		
						Total=	25.70	Cum	371.00
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.							
	3	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).							
			12	1.20	1.20	0.10	1.73		
			8	2.60	0.60	0.10	1.25		
			8	1.60	0.60	0.10	0.77		
			4	3.00	2.80	0.10	3.38		
			4	3.00	1.50	0.10	1.80		
			4	3.00	3.50	0.10	4.20		
						Total=	13.10	Cum	2659.00
5	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a							
							44.42		
						Total=	44.42	Cum	65.00
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.							
	1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).							
			12	1.10	1.10	0.25	3.63		
			12	0.50	0.50	0.30	0.90		
			12	0.20	0.30	0.80	0.43		
			8	4.50	0.20	0.60	4.32		
			8	3.10	0.20	0.30	1.49		
			16	0.20	0.30	2.10	2.02		
			4	4.50	0.20	0.30	1.08		

		8	3.10	0.20	0.30	1.49			
		4	4.60	3.00	0.13	6.90			
		4	3.00	0.20	1.80	4.32			
		3	2.40	0.20	1.80	2.59			
		2	3.00	2.80	0.13	2.10			
		4	3.00	0.60	0.10	0.72			
		8	1.40	0.20	0.30	0.67			
		4	3.10	0.20	0.30	0.74			
7	3.4	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:				Total=	33.40	Cum	4163.00
							0.00	Cum	97.50
8	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:							
	1	Thermo-Mechanically treated bars FE							
		1	80	33.40		2672.16			
						Total=	2672.16	kg	54.50
9	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:							
	3	Cement Mortar 1:6 (1 cement : 6 coarse sand)							
		8	3.40	0.20	0.60	3.26			
		8	2.60	0.20	0.60	2.50			
		8	1.20	0.20	0.40	0.77			
		4	2.20	0.20	0.40	0.70			
		8	3.40	0.20	2.10	11.42			
		8	2.60	0.20	2.10	8.74			
		8	5.00	0.20	0.30	2.40			
		8	4.00	0.20	0.30	1.92			
		4	3.50	1.50	0.20	4.20			
		6	1.50	0.30	0.20	0.54			
		2	7.50	0.20	2.10	6.30			
					Total=	42.75	Cum	3263.00	139499.78

[illegible]

		4	In Cement Mortar 1:6 (1 cement : 6 fine sand)										
		8		4.00			3.90	124.80					
		8		3.00			3.90	93.60					
							Total=	218.40	sqm	91.50		19983.60	
17	11.3		Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:										
		4	In Cement Mortar 1:6 (1 cement : 6 fine sand)										
		8		3.80			2.40	72.96					
		8		2.60			2.40	49.92					
		8		1.20			2.40	23.04					
		2		2.20			2.40	10.56					
							Total=	156.48	sqm	107.00		16743.36	
18	14.13		Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.					381.28					
							Total=	381.28	sqm	94.50		36030.96	
19	14.1		Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.					212.88	sqm	44.50		9473.16	
		1	On new work (Two or more coats)										
20	14.14		Finishing walls with water proofing cement paint of required shade to give an even shade.				Total=	218.40	sqm	41.00		8954.40	
		1	On new work (Two or more coats)										
21	8.13		Providing and fixing flush door shutters, conforming to IS 2202 (Part 1), interior grade, commercial type, core of block board construction with frame of first class hard wood and well matched commercial ply veneering with vertical grains, cross bands and face veneers on both faces of shutters excluding hinges.										
		2	35 mm. thick (single leaf)+8.15										
		4		1.00			2.10	8.40	sqm	1370.00		11508.00	
22	8.141		Providing and fixing Stainless steel "D" shape door handles made of 10mm dia rod with necessary stainless steel screws etc complete.										
			8.141.2 150 mm				Total=	12.00	nos	49.50		594.00	
23	8.58		Providing and fixing bright finished brass butt hinges with brass polished MS screws complete:										
			8.58.1 125x85x5.50 mm (Heavy Type)				Total=	12.00	nos	245.00		2940.00	
24	8.143		Providing and fixing stainless steel hanging door stopper with necessary stainless steel screws complete.										
		1	Single				Total=	6.00	nos	47.00		282.00	

8.149	Providing and fixing factory made PVC door shutters of specified thickness made of styles and rails of n UPVC hollow section of specified size 59x24 mm and wall thickness 2 mm $\pm$ 0.2 mm with inbuilt edging on both sides. The styles and rails mitred and joined at the corners by means of M.S. galvanised/ plastic brackets of size 75x220 mm having wall thickness 1.0 mm and stainless steel screws.								
2	8.149.1 24 mm thick door shutters with	8	0.80	2.00		12.80			
					Total=	12.80	sqm	2399.00	30707.20
								TOTAL=	817732.00


 Asstt. Engineer
 Municipal Corporation
 Korba (C.G.)



 Sub Engineer
 Municipal Corporation
 Korba (C.G.)

PART - B SANITATION WORK

15	Providing and fixing on wall face UV stabilized Unplasticized Rigid PVC pipe (single wall) having 3.2mm wall thickness conforming to IS : 13592 (heavy) including required accessories with seal ring conforming to IS : 5552 having 10 mm gap for thermal expansion etc complete.								
1	10 mm dia pipe.	1	50.00			50.00	metre	182.00	9100.00
2	110 mm dia pipe.	1	30.00			30.00	metre	267.00	8010.00
16	Providing and fixing water closet flushing cistern (Indian type W.C. pan) 1.22m and 0.8m P or S type 10 mm dia rigid P.V.C. flushing cistern (same cistern) conforming to IS : 7231, with flush down and other fittings and fixtures complete including cutting and making good the walls and floors wherever required.					4	each	2899.00	11596.00
17	White China pattern W.C. pan of size 1000x440 mm								
18	Providing and fixing various china ware basin with C.I. brackets 32 mm C.I. basin waste of standard pattern, including painting of brackets cutting and making good the walls wherever required.					4	each	2899.00	11596.00
19	White Size 300x450 mm								
20	Providing and fixing on wall face UV stabilized Unplasticized - PVC moulded fittings accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) cutting with seal ring conforming to IS : 5552 leaving 10 mm gap for thermal expansion.								
1	Tee/ Tee with door/ Bend 45°/ Bend 90°								
1	75 mm					5.00	each	113.00	565.00
2	110 mm					10.00	each	154.00	1540.00
3	Vent cover								
1	75 mm					6.00	each	34.00	204.00
2	110 mm					6.00	each	90.50	543.00
6	Nether trap 110x75mm								

19.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.								
1	15 mm nominal outer dia .Pipes.				110.00	metre	110.00		12100.00
3	25 mm nominal outer dia .Pipes.				80.00	metre	199.00		11940.00
4	32 mm nominal outer dia .Pipes.				40.00	metre	271.00		10840.00
6	19.13 Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved								
1	Bib cock (250 grams)				12.00	each	185.00		2220.00
7	19.14 Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:								
6	Stop cock (concealed) (600 grams)				14.00	each	484.00		6916.00
4	Filler Cock (400 grams)				6.00	each	395.00		2388.00
8	19.13 Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:								
1	Bib cock (400 grams)				8.00	each	382.00		3056.00
2	Long nose bib cock (500 grams)				4.00	each	455.00		1820.00
11	Hand shower set with flexible extension pipe				2.00	each	754.00		1508.00
9	19.15 Providing and fixing stainless steel drain jali of approved make/quality.				15.00	each	51.00		765.00
10	19.16 Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end):								
1	25 mm nominal bore				6.00	each	436.00		2616.00
2	32 mm nominal bore.				8.00	each	510.00		3080.00
11	19.51 Constructing masonry Chamber 60x60x75 cm, inside with modular well burnt clay bricks of 35 kg/ cm ² in cement mortar 1:4 (1 cement : 4 coarse sand) for fire hydrants, with C.I. surface box 350x350 mm top and 165 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) necessary excavation foundation concrete 1:5:10 (1 cement : 5 fine sand:10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick finished with a floating coat of cement.				4.00	each	4356.00		17424.00

19.42	Providing and placing on terrace (at all levels) polyethylene water storage tank (SI marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank					2000.00	litre	7.30	14800.00
TOTAL =									134407.00
Part A									817732.00
									952139.00
									47806.95
Electrification work 5%									999745.95
Say Rs.=									1000000.00


 Asstt. Engineer
 Municipal Corporation
 Korba (C.G.)


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)