



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

पं.रविशंकर शुक्ल नगर जोन

कोरबा, दिनांक 21.11.2024

फा.क्र./208 एवं 209/निर्माण (पं.रविशंकर शुक्ल नगर जोन)/2024/

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 & PWD Electrical SOR 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर मुहरबंद लिफाफा में निविदा आमंत्रित की जाती है :-

- निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने की अंतिम तिथि - 06.12.2024 सायंकाल 3:00 बजे तक
- निविदा खुलने की अंतिम तिथि - 06.12.2024 सायंकाल 4:30 बजे

| क्र. | कार्य का नाम | प्राक्कलन राशि में | धरोहर राशि रु में | निविदा प्रपत्र का मूल्य | निविदा प्रपत्र | कार्यावधि | ठेकेदार का वर्ग | निविदा खुलने की अंतिम तिथि |
|------|--|--------------------|-------------------|-------------------------|----------------|-----------|-----------------|----------------------------|
| 1 | वार्ड क्र. 25 हेलीपेड के पास सामुदायिक भवन निर्माण कार्य। (प्रभारी मंत्री मद 2024-25) (द्वितीय निविदा) | 10,00,000/- | 7,500 /- | 750/- | Form-A | 04 माह | सक्षम श्रेणी | 06.12.2024 |
| 2 | वार्ड क्र. 30 मानिकपुर उरांव मोहल्ला में सामुदायिक भवन निर्माण। (प्रभारी मंत्री मद 2024-25) (द्वितीय निविदा) | 10,00,000/- | 7,500 /- | 750/- | Form-A | 04 माह | सक्षम श्रेणी | 06.12.2024 |

निविदा की शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से भेजना होगा अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, आई.टी.आई. चौक साकेत भवन, जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
- निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनांक तक समस्त संशोधनों के साथ) आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा मुहरबंद लिफाफा में मान्य किया जावेगा जो निम्नानुसार होगा:-
(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित निविदा प्रपत्र शुल्क का डीडी, निविदाओं में निविदाकार को फिजिकल दस्तावेज के साथ निविदा सूचना प्रसारित होने के पश्चात् राशि रु. 100/- के स्टॉम्प पर निष्पादित शपथ पत्र जिसमें संबंधित कार्य का नाम एवं कार्य की निविदा क्रमांक अंकित हो प्रेषित करना अनिवार्य होगा एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
(स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफे होंगे तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
- जिन ठेकेदारों द्वारा नगर पालिक निगम, कोरबा के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम, कोरबा के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीडी) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी पिछले 03 वित्तीय वर्षों का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. (जीवित) पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधिसंगठन,कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना ठेकेदार के हस्ताक्षर सहित निविदा दस्तावेजों के साथ प्रस्तुत करना अनिवार्य होगा।
- कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।

क्रमशः.....02

8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लेवें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
 9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिका स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
 10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
 11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
 12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
 13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
 14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध निविदा शर्तानुसार एवं मेयर इन काउंसिल के निर्णयों के अनुरूप कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
 15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
 16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत की दर से सुरक्षा राशि रनिंग देयकों के साथ 01 वर्ष हेतु साथ ही मरम्मत एवं संधारण प्रकृति के कार्यों को छोड़कर शेष कार्यों के देयकों से 5 प्रतिशत की दर से पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्युरिटी के रूप में रोकी जायेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
 17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
 18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित राशि रु. 100/- नॉन ज्यूडिशियल स्टॉम्प पेपर पर निष्पादित शपथ पत्र निविदा दस्तावेजों के साथ संलग्न करना अनिवार्य होगा।
 19. ईट से संबंधित निर्माण कार्यों में फलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
 20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
 21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त, नगर पालिक निगम कोरबा का निर्णय अंतिम एवं सर्वमान्य होगा।
 22. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
 23. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
 24. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।
 25. ठेकेदार द्वारा संपादित किये गए कार्यों के देयको का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जाएगा।
 26. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
 27. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।
- प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नया रायपुर (छ.ग.) को Uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।


(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

.....

मोबाईल नं.-



कार्यपालक अभियंता
Executive Engineer
नगर/पालिक निगम
Municipal Corporation
कोरबा (C. G.)


| ITEM DESCRIPTION | | N | L | B | H/D | Qty | Unit | Rate | Amount |
|------------------|---|---|---|---|-----|---------|------|---------|-----------|
| | | | | | | 35.00 | sqm | 297.00 | 10395.00 |
| | ended floors, roofs, access platform, balconies surfaces) and shelves (cast in situ) | | | | | | | | |
| | Weather shade, chhajja, Cornices and mouldings | | | | | 78.65 | sqm | 235.00 | 18482.75 |
| | Beams, lintels, cantilevers & walls | | | | | 30.68 | sqm | 294.00 | 9019.92 |
| | | | | | | 51.42 | sqm | 202.00 | 10386.84 |
| 6 | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone Aggregate 20mm nominal size). | | | | | | | | |
| | | | | | | 32.80 | cum | 4163.00 | 136559.31 |
| 7 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415 | | | | | 3297.00 | kg | 54.50 | 179686.50 |
| 8 | 7.5 Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in Cement Mortar 1:6 (1 cement : 6 coarse sand) | | | | | | | | |
| | | | | | | 41.93 | Cum | 3263.00 | 136824.12 |
| 9 | Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth: | | | | | | | | 3540.46 |
| | | | | | | 29.26 | Cum | 121.00 | |
| 10 | 12.13 Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. | | | | | | | | |
| | | | | | | 61.05 | sqm | 1151.00 | 70268.55 |
| 2 | Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete Size upto 200x300mm | | | | | | | | |
| | | | | | | 46.62 | sqm | 587.00 | 27365.94 |


| ITEM DESCRIPTION | N | L | B | H/D | Qty | Unit | Rate | Amount |
|---|---|---|---|-----|--------|------|---------|----------|
| Providing and laying ceramic glazed floor tiles according to IS : 15522 of approved size, make, color shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. | | | | | | | | |
| (Size above 300x300mm) | | | | | 10.26 | sqm | 728.00 | 7469.28 |
| 14 15 mm thick Table rubbed polished Granite stone slab in risers and treads of steps skirting dado and pillars laid on 12mm (Average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polishing etc. complete (single stone is to be used for risers and treads of steps and width of stone for skirting and dado shall be equal to the height of skirting & dado and length of 1.0 m). | | | | | | | | |
| Granite stone grey/pink | | | | | 3.60 | sqm | 1869.00 | 6728.40 |
| 15 Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, tamping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm | | | | | | | | |
| Pigment Coloured (rubber mould) precast interlock concrete blocks | | | | | 17.50 | sqm | 632.00 | 11060.00 |
| 16 Providing and constructing soak pit 1.20x1.20x1.20m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design. | | | | | 2.00 | each | 1709.00 | 3418.00 |
| 7 Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer. | | | | | 480.00 | kg | 75.00 | 36000.00 |
| Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer. | | | | | | | | |
| Providing and making 6mm thick cement plaster of mix: | | | | | 6.30 | sqm | 3330.00 | 20979.00 |

| ITEM DESCRIPTION | | N | L | B | H/D | Qty | Unit | Rate | Amount |
|------------------|--|---|---|---|-----|--------|------|---------|----------|
| | at mortar 1:4 (1 cement : 4 fine sand) | | | | | | | | |
| | ing and making 12mm thick cement plaster of | | | | | 100.92 | sqm | 87.00 | 8780.04 |
| | Cement Mortar 1:5 (1 cement : 5 fine sand) | | | | | | | | |
| | 13 Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix | | | | | 133.76 | Sqm | 96.50 | 12907.84 |
| | In Cement Mortar 1:5 (1 cement : 5 fine sand) | | | | | | | | |
| 22 | Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth | | | | | 188.10 | Sqm | 113.00 | 21255.30 |
| 23 | 14.11 Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade | | | | | 422.78 | Sqm | 94.50 | 39952.71 |
| | On new work (two or more coats) | | | | | | | | |
| 24 | 14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: | | | | | 234.68 | Sqm | 52.50 | 12320.70 |
| | On new work (Two or more coats applied @1.43 ltr/10 sqm over. | | | | | | | | |
| 25 | 14.22 Painting on new work (two or more coats) to give an even shade with: | | | | | 188.10 | Sqm | 56.00 | 10533.60 |
| | Satin synthetic enamel paint | | | | | | | | |
| | | | | | | 40.44 | Sqm | 55.00 | 2224.20 |
| | 18.4 Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : | | | | | | | | |
| | White pedestal type | | | | | | | | |
| | | | | | | 1.00 | each | 2882.00 | 2882.00 |
| 6 | Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required : | | | | | | | | |
| | White Long pattern W.C. pan of size 580 mm | | | | | 1.00 | each | 2459.00 | 2459.00 |
| | Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required : | | | | | | | | |
| | White Size 550x450 mm | | | | | 2.00 | each | 1430.00 | 2860.00 |

| | ITEM DESCRIPTION | N | L | B | H/D | Qty | Unit | Rate | Amount |
|----|--|---|---|---|-----|---------|-------|---------|---------|
| | Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single ended), having 3.2mm wall thickness conforming to IS : 13592 (heavy) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete. | | | | | | | | |
| | 110 mm dia pipe. | | | | | 30.00 | metre | 267.00 | 8010.00 |
| 29 | Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. | | | | | | | | |
| | Tee/ Tee with door/ Bend 45°/ Bend 90° | | | | | | | | |
| | 110 mm | | | | | 7.00 | each | 154.00 | 1078.00 |
| | Nahani trap 110x75mm | | | | | 5.00 | each | 90.50 | 452.50 |
| 30 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. CONCEALED WORK including cutting chases and making good the walls etc., | | | | | | | | |
| | 15 mm nominal outer dia .Pipes. | | | | | 20.00 | metre | 133.00 | 2660.00 |
| | 25 mm nominal outer dia .Pipes. | | | | | 15.00 | metre | 213.00 | 3195.00 |
| 31 | Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: | | | | | | | | |
| | Bib cock (350 grams) | | | | | 4.00 | each | 237.00 | 948.00 |
| | Stop cock (350 grams) | | | | | 4.00 | each | 237.00 | 948.00 |
| | Providing and fixing stainless steel drain jali of approved make/quality. | | | | | 4.00 | each | 51.00 | 204.00 |
| 2 | Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required: | | | | | | | | |
| | Basin mixer pillar tap with spout (1000 grams) | | | | | 2.00 | each | 1248.00 | 2496.00 |
| 3 | Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank | | | | | 1000.00 | litre | 7.30 | 7300.00 |

| ITEM DESCRIPTION | N | L | B | H/D | Qty | Unit | Rate | Amount |
|--|---|---|---|-----|-----|------|---------|------------|
| <p>ing masonry Chamber 60x60x75 cm, inside modular well burnt clay bricks of 35 kg/ cm² in nt mortar 1:4 (1 cement : 4 coarse sand) for sluice e, with C.I. surface box 100mm. top diameter, 160 m bottom diameter and 180 mm deep (inside) with hained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) necessary excavation foundation concrete 1:5:10 (1cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size)and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand)12 mm thick finished with a floating coat of neat cement complete as per standard design :</p> | | | | | 1 | each | 4644.00 | 4644.00 |
| As per SOR Total Estimate Amount Rs. | | | | | | | | 970198.55 |
| For Internal Electrification Work (PWD ELECTRICAL SOR 01.06.2020) | | | | | | | | 29801.45 |
| Net Amount | | | | | | | | 1000000.00 |
| Say Amount Rs. | | | | | | | | 1000000.00 |


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asst. Engineer
 Municipal Corporation
 Korba (C.G.)