

कार्यालय, नगर पालिक निगम, कोरबा(छ.ग.)

फा.क्र./95/कोरबा/2022/

कोरबा, दिनांक 06.06.2022

सिस्टम टेन्डर क्र. 101865 ई-निविदा आमंत्रण सूचना


नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग में एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोच्युरमेंट (E-Tendering) के माध्यम से निविदाएं आमंत्रित की जाती है।

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	कोरबा जोन वार्ड क 12 अंतर्गत एस.ई.सी. एल. मेन गेट से मुड़ापार तालाब होते हुए शारदा विहार नाला तक आर.सी.सी. नाला निर्माण कार्य (15वें वित्त आयोग)	1,42,28,000/-	1,07,000/-	06 माह	वर्ग सी. एवं प्रवर श्रेणी	28.06.2022 से - -----

शर्तें:-

- निविदा दरें प्रचलित सी.एस.आर. से कम या अधिक का उल्लेख किया जावे। सी.एस.आर. के अंतर्गत के आयटमों पर पृथक आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नंबर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्यनिधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्कैन कापी ऑनलाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिये प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिये एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में से 5 प्रतिशत परफारमेंस सिक्क्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्यनिधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र स्कैन कर अपलोड करना अनिवार्य होगा।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में फ्लाइ एश ब्रिक्स का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों में असामान्य कमी प्रतीत होने पर सफल निविदादाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.सी.सी. जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- सशर्त निविदा स्वीकार नहीं की जावेगी।
- निविदा में भाग लेने वाले निविदाकार को विगत 03 वर्षों में सामान्य प्रवृत्ति के कार्य (आर.सी.सी. नाला) का निविदा लागत राशि का 80 प्रतिशत का एकल कार्यादेश (Single Work Order) अंतर्गत पूर्ण कार्य का अनुभव प्रमाण पत्र जमा किया

- जाना आवश्यक है। तत्संबंध में सक्षम अधिकारी कार्यपालन अभियंता या उससे वरिष्ठ अधिकारी का अनुभव प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा।
14. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय एवं सर्वमान्य होगा।
 15. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
 16. अन्य सूचनाएं नगर पालिक निगम, साकेत भवन रामपुर कोरबा कार्यालय में प्राप्त की जा सकती है।
 17. बिना कारण बताये निविदा स्वीकृत/अस्वीकृत या पूर्ण रूप से अमान्य करने का अधिकार सक्षम अधिकारी/प्राधिकारी को रहोगा।


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि :-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT

Name of Work CONSTRUCTION OF RCC NALA FROM SECL MAIN ROAD VIA MUDAPAR TALAB TO SHARDA VIHAR NAALA AT WARD NO. 12

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]


S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	16.5	Demolishing stone rubble masonry including arches, stacking of serviceable material and disposal of unserviceable material within 50 Metres lead.				
	5.2	In cement mortar	cum	595.2	527.00	313,670.40
2	16.43	Demolishing cement concrete including disposal of material within 50 metre lead.				
	43.2	1:3:6 or richer mix	cum	310.00	549.00	170,190.00
3	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	2921.44	185.00	540,466.40
4	1.7	Extra rate for quantity of work executed in or under water and/ or liquid mud including pumping out water.	cum	1190.40	51.00	60,710.40
5	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.2	In ordinary rocks.	cum	180.00	267.00	48,060.00
6	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	744.00	65.00	48,360.00
7	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	375.72	371.00	139,392.12
8	1.26	Carriage by mechanical transport upto 5 km lead:				
	26.1	Earth	cum	2900.00	111.00	321,900.00
	26.2	Sludge	cum	1190.00	89.00	105,910.00
9	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	2269.2	139.00	315,418.80
	1.2	Wall of any thickness including attached pilasters, buttresses etc. in super structure.	sqm	3968.00	228.00	904,704.00
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	175.00	235.00	41,125.00
	1.8	Beams, lintels, cantilevers & walls	sqm	96.00	202.00	19,392.00
10	3.1	Providing and laying nominal mix plain cement concrete with crushed				


S.	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.3	1:3 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	cum	301.32	2970.00	894,920.40
11	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	1220.17	4163.00	5,079,567.71
12	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	95363.01	54.50	5,197,284.04
13	3.9	Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	cum	57.00	469.00	26,733.00

As per Estimate Amount Rs. 14227804.27

Sy/ks 142.28 lakh


Sub Engineer
Nagar Palik Nigam,
Korba


Asst. Engineer
Nagar Palik Nigam,
Korba


कार्यपालक अभियंता,
नगर पालिक निगम,
कोरबा (छ. ग.)