

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. / निर्माण/2022/51

सिस्टम टेंडर नं. 97210


कोरबा दिनांक 12.04.2022

ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत राक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा सड़क कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुरूपी पर (निविदा खुलने के दिनांक तक रागरत रांशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदाएं आमंत्रित की जाती है :-

क.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	गुरु घासीदास चौक से एरा.ई.सी.एल. कोरबा प्रवेश द्वार तक सड़क चौड़ीकरण कार्य।	65.63	49500/-	3 माह (वर्षा ऋतु छोड़कर)	वर्ग डी एवं प्रवर श्रेणी	05.05.2022 से

- निविदा दर प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की राख्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पैन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रपिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का रकने कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- निविदा उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि रांगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रदाय नहीं किया जावेगा।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- सशर्त निविदा स्वीकार नहीं की जावेगी। निविदा उन्हीं ठेकेदारों को दी जाएगी जिन्हें इस प्रकार के कार्य का अनुभव हो।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- अन्य सूचनाएं नगर पालिक निगम, साकेत भवन रामपुर कोरबा कार्यालय में प्राप्त की जा सकती है।
- बिना कारण बताये निविदा स्वीकृत/अस्वीकृत या पूर्ण रूप से अमान्य करने का अधिकार राक्षम अधिकारी/प्राधिकारी को रहेगा।
- डामरीकरण कार्य का निविदा प्रपत्र कय करते समय ठेकेदार को स्वयं के स्वामित्व के आटोमेटिक ड्रम मिक्स प्लांट, रोलर एवं अन्य मशीनरी, हॉट मिक्स प्लांट, पेवर फिनिशर एवं रोड रोलर आदि मशीनों के प्रमाण पत्र आवेदन के साथ संलग्न करना आवश्यक होगा तथा निविदाकार का 60 किमी. की परिधि में हॉल मिक्स प्लांट होना आवश्यक है।
- ठेकेदार द्वारा 60/70 ग्रेड का डामर IOC, BPCL, HPCI से ही कय कर लगाना होगा। ठेकेदार को तेल कंपनी को दी जाने वाली प्रदाय आदेश की प्रतिलिपि इस कार्यालय को देनी होगी।
- कार्य में प्रयुक्त डामर खरीदी के देयक (बिल) कार्यालय में प्रस्तुत करने पर ही भुगतान किया जायेगा।
- जब निविदा के दरों में असामान्य कमी प्रतीत हो तब सफल निविदादाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी, जबकि निविदा की दरों में काफी कमी हो, जैसे निविदादाता को अनुमानित लागत से 10 प्रतिशत से कम निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत के अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर. पोस्ट ऑफिस टाईम डिपॉजिट, एन.एस.सी. जो कि संबंधित निकाय के आयुक्त/मुख्य नगर पालिका अधिकारी के नाम से देय होगा, जमा कराना अनिवार्य होगा उपरोक्त राशि को जमा न कराने की दशा में निविदा निरस्त कर दी जावेगी।


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		12.04.22	15.30	12.04.22	15.30	Release Tender
2		Bid Submission	12.04.22	15.30	04.05.22	17.30	
3	Tender Open		05.05.22	10.30	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION KORBA (C.G.)

ABSTRACT

Name of Work : CONSTRUCTION & WIDNING OF B.T. ROAD FROM GURUGHASI DAS CHOWK TO SECL WELCOME GATE.

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD ROAD-01.01.2015]

S.NO.	SOR NO.	PARTICULAR	UNIT	QTY	RATE	AMOUNT
1	3.2	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.				
			Cum	268.00	95.00	25460.00
2	3.15	Compacting Original Ground				
	(ii)	Compacting Original Ground supporting embankment Loosening, leveling and compacting original ground to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at O.M.C. and then compacted by rolling so as to achieve minimum dry density as given in table 300-2 for embankment construction.				
			Cum	752.70	28.00	21075.60
3	4.1	Granular Sub-base as per Table:- 400-1 Construction of granular sub-base by providing graded Material, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve the desired density, complete as per clause 401 A Plant mix method (with Mechanically crushed stone only) b) For Sub-base cum drainage layer or upper sub-base with (i)Grading-V Material				
			Cum	536.00	1372.00	735392.00
4	4.10	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)				
			Cum	520.00	1434.00	745680.00
5	5.1	Prime coat (Providing and applying primer coat with oil based bitumen emulsion (SS-1, grade conforming to IS:8887) on prepared surface of granular Base including clearing of road surface and spraying primer using mechanical means as per clause 502.				
	(i)	on WBM/WMM surface @0.85 Kg/sqm.				
			Sqm	2680.00	64.00	171520.00
6	5.3	Bituminous Macadam (Providing and laying bituminous macadam as per clause 504 with mixed prepared in minimum 40-60 TPH capacity hot mix plant using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and				
	B	With mechanical paver finisher				
	(II)	for Grading-II(19 mm nominal maximum size, bitumen content 3.40%)				
			Cum	358.00	6255.00	2239290.00
7	5.2	Tack coat Providing and applying tack coat with bitumen emulsion (RS-1, grade conforming to IS:8887) using emulsion pressure distributor on the prepared bituminous/granular surface cleaned with mechanical broom and as per clause				
	(i)	Bituminous surface @ 0.25 kg /Sqm				
			Sqm	8680.00	15.00	130200.00

Executive Engineer
Municipal Corporation
KORBA (C. G.) E.S.

	(ii)	Granular surfaces treated with primes @ 0.30 kg /Sqm	Sqm	2680.00	17.00	45560.00
8	5.24	Close Graded Premix Surfacing/Mixed Seal Surfacing (Mechanical means using minimum 40-60 TPH capacity of HMP. Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness using bitumen to the required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a Smooth wheeled roller 8-10 tonne capacity, and finishing to required level and grade, complete as per clause 508)				
	ii	With mechanical paver finisher				
	A	With bitumen				
	(ii)	Type B (13.2 mm to 0.09 mm size aggregates)	Sqm	4480.00	146.00	654080.00
9	4.13	Construction of Shoulders (Construction of shoulders as per clause 408 with selected soil from borrow pits / borrow areas having CBR not less than 12 and shall have L.L. and P.I. not more than 25% and 6% respectively, inclusive of all leads and lifts, including clearing and scrapping of existing surface, providing required cross fall, compacting, watering rolling and royalty charges etc. complete.				
	A	With vibratory roller	Cum	499.20	291.00	145267.20
10	3.20	Construction of RCC open drain				
	(ii)	Construction of RCC open drain 1.0m x 1.0m inside dimension lined with 150 mm thick RCC M-20 walls, 150 mm thick CC M-20 foundation, over 100 mm thick (Av) leveling course in PCC M-15 including excavation , dressing of sides and bottom, provision of HYSD reinforcement consisting 10 mm dia horizontal bars @ 150 mm c/c and L-shaped 10 mm dia vertical bars @ 150 mm c/c (L=1400 mm) including cutting, bending and binding wire, placing in position, providing shuttering and concreting by using concrete mixer, compaction by vibration etc complete as per drawings and technical specifications.				
			Mtr	300.00	4905.00	1471500.00
11	8.13	Road Marking with Hot Applied Thermoplastic Compound with Reflectorizing Glass Beads on Bituminous Surface (Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorizing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35-1997. The finished surface to be level, uniform and free from streaks and holes.)				
			Sqm	252.20	707.00	178305.40
				TOTAL		6563330.20
				SAY RS:		6563000.00

Sub. Engineer
Municipal Corporation
Korba (C.G.)

Asstt Engineer
Municipal Corporation
Korba (C.G.)

Exe. Engineer
Municipal Corporation
Korba (C.G.)