

# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./479,524,525,526/निर्माण कोरबा जोन/2019

कोरबा, दिनांक 02.08.2019

## निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में निर्माण कार्य हेतु पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर एवं रोडयूल अनुसार कार्यों हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइट से डाउनलोड कर आमंत्रित की जाती है :-

क्र	कार्य का नाम (मरम्मत एवं संधारण मद)	प्राक्कलन राशि	धरोहर राशि	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने हेतु आवेदन प्रस्तुत करने की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1.	वार्ड क्र. 10, में आर.सी.सी. नाली एवं सीमेंट कांक्रीट सड़क का मरम्मत एवं निर्माण कार्य। (मरम्मत एवं संधारण मद)	3,97,000/-	4,000 /-	750/-	03 माह	सक्षम श्रेणी	19.08.2019	20.08.2019	26.08.2019
2.	वार्ड क्र. 01, में डालिया गोदाम से ठेला मोहल्ला तक आर.सी.सी. नाली एवं सीमेंट कांक्रीट रोड का मरम्मत कार्य। ( मरम्मत एवं संधारण मद)	4,00,000/-	4,000 /-	750/-	03 माह	सक्षम श्रेणी	19.08.2019	20.08.2019	26.08.2019
3.	वार्ड क्र. 04, आदिले चौक के पास सीमेंट कांक्रीट रोड एवं नाली का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	4,00,000/-	4,000 /-	750/-	03 माह	सक्षम श्रेणी	19.08.2019	20.08.2019	26.08.2019
4.	वार्ड क्र. 04, में दुरपा रोड मुक्तिघाम का मरम्मत एवं रख-रखाव कार्य। (मरम्मत एवं संधारण मद)	4,00,000/-	4,000 /-	750/-	02 माह	सक्षम श्रेणी	19.08.2019	20.08.2019	26.08.2019

शर्त :-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथके से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र की प्रतियों नगर पालिक निगम, साकेत भवन रामपुर, कोरबा कार्यालय से उपरोक्त कार्यों हेतु नाम के सम्मुख अंकित राशि नगद जमा कर उपरलिखित तिथि तक साथ 5.00 बजे तक अवकाश के दिनों को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मांगाना हो तो रु. 50/- अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी।
- निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात प्राप्त निविदाएँ स्वीकार नहीं की जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य ना किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड)की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय प्रमाण पत्र/पैन नम्बर पत्र, जी. एस. टी. प्रमाण पत्र एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र एवं धरोहर राशि निविदा प्रपत्र प्राप्त करने के तिथि के 5.30 बजे तक अनिवार्य होगा।
- निविदा प्रपत्र उन्ही ठेकेदारों को दिया जायेगा जिन्हे इस प्रकार के कार्यों का अनुभव हो।
- पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती है और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहे तो उनके समक्ष खोले जावेगे।
- सम्पूर्ण किये गये कार्यों के लिये प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिये एवं मरम्मत एवं संधारण प्रवृत्ति के कार्य को छोड़कर 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में प्रत्येक चल देयकों में से 03 वर्ष के लिये रोकी जावेगी।
- आवेदन के साथ रु. 10.00 लाख या उससे अधिक लागत के निर्माण कार्यों की निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ठेके से संबंधित निविदा प्रपत्र उन्ही ठेकेदारों को प्रदाय किये जावेगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में शपथ पत्र देना अनिवार्य होगा।
- कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंट की खरीदी ठेकेदारों को स्वयं करनी होगी।
- निविदा प्रपत्र अहस्तांतरणीय होगा।








OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)


DETAILED ESTIMATE

As per SOR : PART A [PWD BUILDING-01-01-2015] & PART B [NON SOR ITEM]

S.N.	NAME OF WORK	AMOUNT
1	Repair and Maintenance Work at Durpa Road Muktidham at Ward No. - 4 (PART A + PART B)	399832.50

Say Rs.= 400000.00

  
Asstt. Engineer  
Municipal Corporation  
Korba (C.G.)

  
Sub Engineer  
Municipal Corporation  
Korba (C.G.)



**OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)**  
**DETAILED ESTIMATE (PART A)**


Repair and Maintenance Work at Durpa Road Muktidham at Ward No. - 4


As per SOR: Schedule of rates public works department [PWD BUILDING-01-01-2015]

S. N.	SOR Ref.	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	1.2	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).								
			1	40.00	32.00		1280.00			
			1	62.00	32.00		1984.00			
			Total=						3264.00	Sqm
2	1.4	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.								
			5	16.00	10.00		800.00			
			2	20.00	12.00		480.00			
			1	80.00	3.00		240.00			
Total=						1520.00	Sqm	3.70	5624.00	
3	12.50	KOTA stone slab 25mm thick in risers and treads of steps, skirting dado and pillar laid in 12mm (Average) thick cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete. (single stone is to be used for riser and treads of steps and the width of stone for skirting and dado shall be equal to the height of skirting/ dado up to length of 1.0 M.)								
			6	10.00		0.20	12.00			
			Total=						12.00	Sqm
4	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
			1	In all types of soil						
			1	30.00	2.00	0.20	12.000			
Total=						12.000	Cum	185.00	2220.00	
5	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
			3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).						
			1	30.00	2.00	0.10	6.00			
Total=						6.00	Cum	2970.00	17820.00	



6	12.7	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm											
	2	Pigment Coloured (rubber mould) precast interlock concrete blocks											
			1	30.00	2.00		60.00						
						Total	60.00	Sqm	632.00			37920.00	
7	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.											
	5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).											
			1	11.00	5.00	0.06	3.30						
						Total=	3.30	Cum	4073.00			13440.90	
8	14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:											
	2	On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)											
			4	20.00		2.00	160.00						
			2	270.00		2.10	1134.00						
			4	9.00	4.00		144.00						
						Total	1438.00	Sqm	37.00			53206.00	
9	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:											
	4	Cement Mortar 1:6 (1 cement : 6 coarse sand)											
			2	30.00	0.20	0.300	3.60						
						Total=	3.60	Cum	3263.00			11746.80	
10	11.2	Providing and making 12mm thick cement plaster of mix											
	3	In Cement Mortar 1:5 (1 cement : 5 fine sand)											
			2	30.00		0.60	36.00						
						Total=	36.00	Sqm	96.50			3474.00	
											TOTAL =	180832.50	

  
 Asstt. Engineer  
 Municipal Corporation  
 Korba (C.G.)

  
 Sub Engineer  
 Municipal Corporation  
 Korba (C.G.)




# OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)


## DETAILED ESTIMATE (PART B)

Repair and Maintenance Work at Durpa Road Muktidham at Ward No. - 4

NON SOR ITEM

S. N.	NON SOR	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	NS 1	Maintenance of Lawn & watering on plant, cleaning of road, shed etc. complete including all consumable such as broom, detergent etc. complete.								
			1	365.00			365.00			
						Total=	365.00	Day	600.00	219000.00
									TOTAL =	219000.00

  
 Asstt. Engineer  
 Municipal Corporation  
 Korba (C.G.)

  
 Sub Engineer  
 Municipal Corporation  
 Korba (C.G.)