

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क्र. 640 / 2025

सिस्टम टेंडर नं. 170846

कोरबा दिनांक 25.06.2025

ई-निविदा आमंत्रण सूचना


कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है:-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि — 22.07.2025 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि — 22.07.2025 सायंकाल 4.00 बजे से

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	प्रधानमंत्री आवास योजना(शहरी) अंतर्गत कॉर्पोरेशन साईट में निर्मित आवास हेतु सी.सी. रोड एवं बाउण्ड्रीवाल का निर्माण कार्य (जि.ख. न्या. मद)	36.88	28000/-	05 माह	1500/-	वर्ग डी एवं प्रवर श्रेणी	22.07.2025 से

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र, पैन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा के पते पर भेजना होगा। निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात् का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असमान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म —ए की कंडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
16. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
17. कार्य कियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।


अधीक्षक अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि:-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		25.06.2025	15.30	25.06.2025	15.30	Release Tender
2		Bid Submission	25.06.2025	15.30	18.07.2025	17.30	
3		Physical Document Submission	25.06.2025	15.30	22.07.2025	15.00	
4	Tender Open		22.07.2025	16.00	--	--	


SUPRINTENDENT ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION KORBA (C.G.)

Name of work:- Construction of Cement concrete Road at 132 dues PMAY Corporation site Korba(C.G.)

PWD ROAD SOR 01.01.2015

S NO	SOR NO	PARTICULAR	NO	L	B	D	QTY	UNIT	RATE	AMOUNT
3	3.20	Excavation in Soil (by Mechanical Means) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per								
			1	70 0	9 0	0.25	157 5			
			1	130 0	5 0	0.25	162 5			
			2	10 0	1 0	1.20	24 0			
							344 00	Cum	95.00	32680.00
2	3.12	Construction of embankment with Material Obtained from Borrow Pits/Borrow Area (Construction of embankment with approved material/selected soil having C.B.R.>5 (unless specified otherwise in the contract) obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300-2)								
			1.00	70 00	8 00	0.20	112.00			
			1.00	130 00	5 00	0.20	130.00			
							242.00	cum	223.00	53966.00


		Construction of sub-grade with Material Obtained from Borrow Pits/Borrow Area								
		Construction of sub-grade with approved material/selected soil having C B R >8 (unless specified otherwise in the contract) obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and								
			1	70 0	8 0	0 20	112.0			
			1	130 0	5 0	0 20	130 0			
							242.00	Cum	250.00	60500.00
5	3.15	Compacting Original Ground (i) Compacting Original Ground supporting sub-grade Loosening of the ground upto a level of 500 mm below the subgrade level , watered, graded and compacted in layers to meet requirement of table 300-2 for sub grade	Qty Same as Item no 8/3 13				242 00	Cum	50 00	12100.00
6	4.10	Granular Sub-base as per Table - 400-1								
		Construction of granular sub- base by providing graded Material , carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve the desired density.								
	A	Plant mix method (with Mechanically crushed stone only)								
	(a)	For Lower Sub-base with								
	(i)	Grading-III Material (4 Lane Road)	1	70.0	8 00	0 20	112.0			
			1	130.0	4 80	0 20	124.8			

		Construction of Shoulders as per clause 408 with selected soil from borrow pits / borrow areas having CBR not less than 12 and shall have L.L. and P.I. not more than 25% and 6% respectively, inclusive of all leads and lifts, including clearing and scrapping of existing surface, providing required cross fall, compacting watering rolling and royalty charges etc.					236.80	Cum	1423.00	336966.40
	A	With vibratory roller (4 Lane Road) (Shoulder deduction cseb chock 100m)								
			2	70.0	1.50	0.20	42.00			
							42.00	Cum	291.00	12222.00
9	6.10	Dry Lean Cement Concrete Sub-base as per IRC SP-49 (Construction of dry lean cement concrete Sub-base over a prepared sub-grade with coarse and fine aggregate conforming to IS-383, the size of coarse aggregate not exceeding 26.5 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/cum, optimum moisture content to be determined during trial)								
			1	70.0	6.30	0.10	44.10			
			1	130.0	4.80	0.10	62.40			
			2	10.0	1.00	0.10	2.00			
							108.50	Cum.	2332.00	253022.00

	10	Cement Concrete Pavement (Construction of un-reinforced, dowel jointed, plain cement concrete pavement as per IRC 58 over a prepared sub-base, coarse and fine aggregate conforming to IS 383 and graded as per table 600-3 mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous										
	(I)	With Cement concrete grade M-30 and minimum cement content @ 375 kg/cum	1	70.0	6.00	0.20	84.00					
			1	130.0	4.50	0.20	117.00					
							201.00	Cum	4750.00		954750.00	
	9.40	Providing and laying Reinforced Cement Concrete pipe NP 3 / prestressed concrete pipe on first class bedding (Laying Reinforced cement concrete pipe NP3 /prestressed concrete pipe for culverts on first class bedding of granular material including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets) 600 mm dia										
							20.00	m	2617.00		52340.00	

Road Marking with Hot Applied Thermoplastic Compound with Reflectorizing Glass Beads on Bituminous Surface (Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorizing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35-1997)									
			2	200.0	0.15		60.00		
			0.5	70.0	0.15		5.25		
							65.25	Sqm	707.00
									45131.75
TOTAL=									1814578.15
Say rs.=									1815000.00


 ASST Engineer
 Municipal Corporation
 Korba (C.G.)


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Name of work - Construction of Boundary wall at 132 dues PMAY of Corporation site Korba (C G)

As per SOR Schedule of rates public works department [PWD BUILDING-01-01-2015]

S N	SOR Ref	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	11	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area) including dressing and leveling of								
	1	In all types of soil								
		column	140	1.20	1.20	1.20	241.92			
		EXPANSION	5	1.20	1.20	1.20	8.64			
		GATE	2	1.80	1.80	1.80	11.66			
		below plinth	1	406.50	0.30	0.30	36.59			
						Total	298.81	Cum	185.00	55279.67
2	21	Providing and fixing form work including centring, shuttering, strutting, staging, propping, bracing etc. complete and including its removal at all levels, for								
	1	Foundations, footings, bases of columns, plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
			145	4	1.10	0.25	159.50			
			145	1.00		1.00	145.00			
			2	4.00	1.50	0.35	4.20			
			2	4.00	1.00	0.60	4.80			
		plinth beam	2	180		0.30	108.00			
						Total	421.50	Sqm	139.00	58588.50
	5	Columns, Pillars, Piers and likes- rectangular or square in shape								
			145	1.00		1.5	217.5			
			2	1.60		6	19.2			
			1	6.00		1.6	9.6			
						Total	246.30	sqm	297.00	73151.10
3	118	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including								
		column	145	1.20	1.20	0.10	20.88			
		below plinth	1	406.50	0.30	0.10	12.20			
						Total	33.08	Cum	371.00	12270.83
4	31	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								

		1	450.00	0.20	0.05	4.50			
					Total	4.50	Cum	4073.00	18328.50
11.2	Providing and making 12mm thick cement plaster of mix								
	In Cement Mortar 1:6 (1 cement 6 fine sand)								
		1	450.00		1.80	810.00			
					Total	810.00	sqm	91.50	74115.00
12	11.3 Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix								
	In Cement Mortar 1:6 (1 cement 6 fine sand)								
		1	450.00		1.80	810.00			
					Total	810.00	sqm	107.00	86070.00
13	14.15 Painting exterior surface with SMOOTH exterior emulsion paint manufactured with the cow					1570.00	sqm	58.00	87920.00
	On new work (Two or more coats)								
17	9.6 Steel work welded in built up sections/ framed work including cutting, bolting, fixing in position and applying a priming coat of red oxide zinc								
	9.6.1 In stringers treads, landings etc of stair cases including use of chequered plate wherever required. all complete								
	gate				500	kg	70		35000
								TOTAL=	1873184.94
								Say rs. =	1873000.00


 Asstt Engineer
 Municipal Corporation
 Korba (C.G.)


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)