



कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फ़ैक्स : 07759-221929, पो. बॉक्स नं. - 12 पिन कोड - 495677

Website : www.korbamunicipal.in, Email : kosabadizone3@gmail.com

फा.क./468,471,472/निर्माण (कोसा.)/2018

कोरबा, दिनांक 05.01.2019

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइट से डाउनलोड कर आमंत्रित की जाती है :-

क्र	कार्य का नाम	प्राक्कलन राशि में	घरोहर राशि रु में	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने आवेदन की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र० 25 रिकान्डो रोड कुआ भट्टा इंडियन ब्रायलर फार्म हाउस के पास आर० सी० सी० शेड का निर्माण कार्य (विधायक मद)	4,00,000/-	4000/-	750/-	02 माह	सक्षम श्रेणी	25.01.2019	28.01.2019	05.02.2019
2	मंच का निर्माण कार्य (वार्ड क्र० 29 पार्षद मोहल्ला जयप्रकाश कौशिल घर के पास (सरगुजा एवं उत्तर विकास प्राधिकरण)	2,50,000/-	2500/-	750/-	02 माह	सक्षम श्रेणी	25.01.2019	28.01.2019	05.02.2019
3	मंच का निर्माण कार्य (वार्ड क्र० 18 चेकपोस्ट) डबरीपारा (सरगुजा एवं उत्तर विकास प्राधिकरण)	2,50,000/-	2500/-	750/-	02 माह	सक्षम श्रेणी	25.01.2019	28.01.2019	05.02.2019

शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र की प्रतियाँ नगर पालिक निगम, साकेत भवन रामपुर, कोरबा कार्यालय से उपरोक्त कार्य हेतु नाम के सममुख अंकित राशि नगद जमा कर उपर लिखि तिथि तक सायं 5:00 बजे तक अवकाश के दिनों को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मंगाना हो तो रु. 50/- अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी।
- निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं की जावेंगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।

क्रमशः पृष्ठ 02

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT


Name of Work :- Const. of R.C.C. Shed at Ricondo Road Kuan Bhattha Near Indian Boyler Form House


Work No.- 25

As per Sor :- Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]

Sno.	ITEM DESCRIPTION	Qty	Unit	Rate	Amount
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), In all types of soil	38.35	Cum	185.00	7094.75
2	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead	38.35	Cum	65.00	2492.75
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing	1.94	Cum	371.00	721.74
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm)	5.49	Cum	2659.00	14597.71
5	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all Foundations, footings, base of columns and plinth beam in any shape and Columns, Pillars, Piers and likes- rectangular or square in shape Beams, lintels, cantilevers & walls Suspended floors, roofs, access platform, balconies (plain surfaces) and Weather shade, chhajja, Cornices and mouldings	26.64	Sqm	139.00	3702.96
		20.40	Sqm	297.00	6058.80
		22.95	Sqm	202.00	4635.90
		36.40	Sqm	235.00	8554.00
		5.64	Sqm	294.00	1658.16
6	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm)	16.37	Cum	4163.00	68156.21
7	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and	8.66	Cum	97.50	844.05
8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	1670.00	kg	54.50	91015.00
9	Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	11.65	Cum	3263.00	38020.95
10	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	7.87	cum	121.00	952.27
11	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting	350.00	Kg	67.50	23625.00
12	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with	14.50	Sqm	3330.00	48285.00
13	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	59.53	Sqm	87.00	5179.01

Sr	ITEM DESCRIPTION	Qty	Unit	Rate	Amo
14	Providing and making 12mm thick cement plaster of mix: Cement Mortar 1:6 (1 cement : 6 fine sand)	54.00	Sqm	91.50	49
15	12mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	66.84	Sqm	107.00	71
16	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface	180.37	Sqm	94.50	170
17	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size Size 600x600mm	29.76	Sqm	1151.00	3425
18	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade. On new work (two or more coats)	180.37	Sqm	44.50	802
19	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	53.24	Sqm	55.00	292
Total amount as per SOR Rs.					39993
Say amount Rs.					40000


Sub Engineer
Municipal Corporation
Korba (C.G.)


Asst. Engineer
Municipal Corporation
Korba (C.G.)