

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 1499/2026

सिस्टम टेंडर नं. 189656

कोरबा दिनांक 24.04.2026

द्वितीय ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता PHE-USOR 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्चुरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र फार्म A में निविदा आमंत्रित की जाती है :-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि - 14.05.2026 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 14.05.2026 सायंकाल 4.00 बजे से


क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (DD)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क 1 रामसागर पारा तिवारी मोहल्ला एवं वार्ड क 14 चिमनीभट्टा आंगनबाड़ी के पास डिस्ट्रीब्यूशन पी.व्ही.सी. पाईप लाईन बिछाने एवं लगाने का कार्य (ग्री.का.पे.ज.सं.नि.)	14.50	11000/-	04 माह	750/-	वर्ग डी एवं प्रवर श्रेणी	14.05.2026 से

शर्त:-

1. निविदा दरे एस.ओ.आर. को कम या अधिक प्रतिशत दरों पर दिया जावे एवं आयटमों पर पृथक से आयटम दरों का उल्लेख किया जावे।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र/पेन नम्बर, वैध जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का DD एवं शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से निविदा खुलने की तिथि में दोपहर 3.00 बजे तक आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई. चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा को उपलब्ध कराना अनिवार्य होगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का DD जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकੀ जावेगी।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे एवं कर्मचारी भविष्य निधि संगठन (ई.पी.एफ.) एवं विभिन्न प्रावधानों को धारा 1952 के तहत निविदाकार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत तीन माह की अवधि में जमा किये गये TRRN Payment Detail चालान की प्रति प्रस्तुत करना तथा ऑनलाईन अपलोड किया जाना अनिवार्य होगा।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में फ्लाइंग एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कंडिका 11 अनुसार एस्कलेशन देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जाएगा।
16. ठेकेदारों को निर्माण कार्य के दौरान निर्माण एवं अपशिष्ट प्रबंधन नियम 2016 में किये गये प्रावधानों का पालन करना होगा।
17. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. सफल निविदाकार को कार्य संपादन के दौरान पाईप बिछाये जाने के पूर्व पाईप एवं फिटिंग इत्यादि का CIPET से अभिप्रमाणित जांच प्रमाण पत्र सहित SGS/RITES आदि संस्था के माध्यम से Thirt party inpection report प्रस्तुत करना अनिवार्य होगा। संबंधित दस्तावेज की अनुपलब्धता पर देयक भुगतान की कार्यवाही नहीं की जाएगी।


प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।


Executive Engineer,
Municipal Corporation,
KORBA (Chhattisgarh)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		24.04.2026	15.30	24.04.2026	15.30	Release Tender
2		Bid Submission	24.04.2026	15.30	11.05.2026	17.30	
3		Physical Document Submission	24.04.2026	15.30	14.05.2026	15.00	
4	Tender Open		14.05.2026	16.00	--	--	


EXECUTIVE ENGINEER
KORBA (C.G.)
Municipal Corporation
For, Commissioner Korba (C.G.)
KORBA (Chhattisgarh)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Work Name :- Providing & laying of Distribution PVC pipeLine at ward no. 01 Ramsagar Para Tiwari Muhalla & Ward No. 14 Chimnibhatta Near Aanganbadi


(CG PHE SOR Amendment No 7/ 2022-23;


S.N.	ITEM DESCRIPTION	N	L	W	D	QTY	UNIT	RATE	AMOUNT
1	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 m lead as per direction of engineer-in-charge. Dismantling of Cement Concrete Pavment by mechanical means using pneumatic tools, cutter breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials up to a lead of 1000 metres, stacking serviceable and unserviceable materials separately								
		1	250.00	0.60	0.20	30.00			
						30.00	Cum	1227.00	36810.00
2	Earth work in excavation for pipe trench in ordinary soil areas including dressing, watering, ramming and disposal of excavated earth lead up to 50m and lift up to 1.5m, disposal earth to be levelled, neatly dressed.								
		1	720.00	0.60	1.00	432.00			
						432.00	Cum	201.00	86832.00
3	Earth work in excavation for pipe trench in all kinds of rocks in areas including dressing, stacking of useful material and disposal of unserviceable material up to lead up to 50m and lift up to 1.5m.								
	Soft rock with or without blasting or bituminous pavement / cement concrete road	1	400.00	0.60	1.00	240.00			
						240.00	Cum	465.00	111600.00
4	Supply & Filling moorum/river sand for pipe bedding or over the pipe (including supply)								
						720.00			
						720.00	Cum	864.00	622080.00
5	Providing, laying and jointing including testing following socket & spigot centrifugally cast (Spun) Ductile Iron pressure pipes with inside cement mortar lining (class K- 7) conforming to IS: 8329/ 2000 with suitable Rubber Gasket (Push on) joints as per IS:5382/2018								
A	For pipeline of 110mm Dia. PVC Pipe 6Kg/cmsq								
						720.00			
						720.00	Mtr.	331.00	238320.00

	Providing, Solvent Cement Joints to PVC Pipes and fittings of 6, 8 and 10 Kg/Sq cm. Pressure including testing of joints and cost of jointing materials (i.e. socket, coupler & solvent cement)								
	110 mm dia								
						90.00			
7	Providing and laying in position including testing following PVC bends suitable for 6, 8 and 10 Kg/Sq. cm. pressure pipes					90.00	Each	34.00	3060.00
	110 mm dia								
						12.00			
						12.00	Each	427.00	5124.00
8	Providing and laying in position including testing following PVC Tee suitable for 6, 8 and 10 Kg/Sq. cm. pressure pipes								
	110 mm dia								
						3.00			
						3.00	Each	267.00	801.00
9	Providing and laying in position including testing following PVC end Cap (plugs) suitable for 6, 8 and 10 Kg/Sq cm. Pressure pipes.								
	pipe line 110 m diameter								
						3.00			
						3.00	Each	80.00	240.00
10	Providing and laying in position including testing PVC coupler suitable for 6, 8 and 10 Kg/Sq. cm. Pressure pipes								
	pipe line 110 m diameter								
						35.00			
						35.00	Each	120.00	4200.00
11	Provision for inter connection of old to new pipe line with excavation of trench as per requirement of any diameter & type of pipe line in muddy area i/c dewatering the trench laying & jointing of pipe and specials, back filling the trench i/c testing of joints cost of labour & specials such as D-Joints couplers, solvent cement etc, complete job work as per approved specification and as directed by Engineer in charge.								
	110/110 mm dia								
						2.00			
						2.00	Each	2854.00	5708.00
12	Pumping out water caused by springs, tides or river seepage, broken water mains or drains or well or the like.								
						450.00			
						450.00	KL	71.00	31950.00

	Construction of Brick masonry valve chamber with 20 cm thick wall in 1:6 M. with 12mm thick 1:4 Cement Plaster and base course 10 cm. thick in M-15. Inside Dimensions 10x80x100cm M-20 RCC chamber cover size 130x100cmx120cm including cost of materials, labour etc. complete								
								2.00	
								2.00	Each 7886.00 15772.00
14	Providing and fixing PVC Djoint (Detachable joint) in PVC pipe line suitable for classes up to 10kg/sqcm Pressure pipes. i/c nut bolt, cutting of pipe, testing of joints etc complete.								
	pipe line 110 m diameter						10.00	Each	157.00 1570.00
	pipe line 160 m diameter						3.00	Each	244.00 732.00
15	Providing & laying mechanically mixed cement concrete 20mm nominal size graded crushed stone excluding cost of centering & shuttering.								
	Reconstruction of road (m-20 Grade)								
	1:31/2:3 (M-20)								
		1	250.00	0.60	0.20		30.00	Cum	6545.00 196350.00
19	Providing and Laying including testing Ductile Iron Double Socket branch flange Tee conforming to IS:9523/2000 having dimension as per table 21 of IS:9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS:9523/2000.								
	300 mm x 100 mm						1.00	Each	7160.00 7160.00
20	Providing and Laying including testing Ductile iron Mechanical joint collar with follower glands conforming to IS: 9523/2000 having dimension as per table 24 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen and internal cement mortar lining								
	100 mm Dia						6.00	Each	2647.00 15882.00
	150 mm Dia						3.00	Each	3896.00 11688.00
	300 mm Dia						2.00	Each	8901.00 17802.00
21	Providing & fixing of following Cast iron double flanged sluice valves as per I.S.:14846-2000 fitted with cast iron cap including jointing & testing with cost of jointing material such as bolts, nuts, rubber insertions etc. all complete								
	150mm dia						2.00	Each	7559.00 15118.00
	100mm dia						1.00	Each	5090.00 5090.00

	Providing and Laying including testing ductile iron PN 16 type flanged sockets conforming to IS:9523/2000 having dimension as per table 23 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS:9523/2000.								
	100mm					4.00	Each	1033.00	4132.00
	150mm					2.00	Each	1608.00	3216.00
23	Providing and Laying including testing ductile PN 16 type iron flanged spigot conforming to IS:9523/2000 having dimension as per table 24 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS: 9523/2000.								
	100mm					4.00	Each	1148.00	4592.00
	150mm					2.00	Each	1837.00	3674.00
								Rs.	1449503.00
								Say rs.	1449600.00


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asstt. Engineer
 Municipal Corporation
 Korba (C.G.)