



# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

(कोसाबाड़ी जोन)

फा.क्र./ 8815 / 8814 / 8822 / 8823 / 8821 / कोसाबाड़ी जोन / 2023

कोरबा, दिनांक 05.10.2023

## द्वितीय निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 एवं प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Electrical SOR 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर मुहरबंद लिफाफे में निविदा आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 23.10.2023 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 23.10.2023 सायंकाल 4:30 बजे तक

| क्र. | कार्य का नाम   | प्राक्कलन राशि में | धरोहर राशि रु में | निविदा प्रपत्र का मूल्य | निविदा प्रपत्र | कार्यावधि | ठेकेदार का वर्ग | निविदा खुलने की अंतिम तिथि |
|------|--|--------------------|-------------------|-------------------------|----------------|-----------|-----------------|----------------------------|
| 1    | वार्ड क्र. 22 शिवाजी नगर अंतर्गत आदिवासी सांस्कृतिक भवन में अतिरिक्त विकास कार्य। (महापौर मद 2023-24)              | 10,00,000/-        | 7,500 /-          | 750/-                   | Form-A         | 04 माह    | सक्षम श्रेणी    | 23.10.2023                 |
| 2    | वार्ड क्र. 29 पोड़ीवहार काली मंदिर के पास स्थित सामुदायिक भवन में विकास कार्य।(महापौर मद 2023-24)                  | 5,00,000/-         | 5,000/-           | 750/-                   | Form-A         | 03 माह    | सक्षम श्रेणी    | 23.10.2023                 |
| 3    | वार्ड क्र. 33 रामपुर बस्ती ठाकुरदिया देव स्थल के पास चबुतरा निर्माण। (महापौर मद 2023-24)                           | 5,00,000/-         | 5,000/-           | 750/-                   | Form-A         | 03 माह    | सक्षम श्रेणी    | 23.10.2023                 |
| 4    | वार्ड क्र. 33 रामपुर बस्ती ठाकुरदिया देव स्थल के पास सामुदायिक भवन अन्य सुविधाओं का विस्तार। (महापौर मद 2023-24)   | 10,00,000/-        | 7,500 /-          | 750/-                   | Form-A         | 04 माह    | सक्षम श्रेणी    | 23.10.2023                 |
| 5    | वार्ड क्र. 33 रामपुर में बालिका गृह के पास निर्मित सामुदायिक भवन में अन्य सुविधाओं का विस्तार। (महापौर मद 2023-24) | 10,00,000/-        | 7,500 /-          | 750/-                   | Form-A         | 04 माह    | सक्षम श्रेणी    | 23.10.2023                 |

### निविदा की शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज हाथों-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट [www.korbamunicipal.in/uad.cg.gov.in](http://www.korbamunicipal.in/uad.cg.gov.in) डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनोंक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा प्रपत्र मुहरबंद लिफाफे से मान्य किया जावेगा जो निम्नानुसार होगा:-  
(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।

क्रमशः.....02

(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।

(स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।

5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई. सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस, टाईम डिपॉजिट अथवा एन.एस. सी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष हेतु साथ ही 05 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्कुरिटी के रूप में रोकी जावेगी।
17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन ) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कंडिका क. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
19. ईट से संबंधित निर्माण कार्यों में फ्लाइ एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
23. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।


प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नवा रायपुर (छ.ग.) को Uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।

(ठेकेदार के हस्ताक्षर)

नाम .....

पूर्ण पता .....

मोबाईल नं.- .....

  
कार्यपालन अभियंता  
नगर पालिक निगम  
कोरबा (छ.ग.)

-114

**OFFICE OF THE MUNICIPAL CORPORATION, KORBA ( C.G.)**  
**ABSTRACT**

Name of Work **CONSTRUCTION OF CHABUTRA NEAR THAKURDIYA DEV STHAL IN RAMPUR BAST AT WARD NO-33**  
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

| S.N | REF   | ITEM DESCRIPTION   | UNIT | QTY   | RATE    | AMOUNT    |
|-----|-------|--|------|-------|---------|-----------|
| 1   | 1.1   | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.   |      |       |         |           |
|     | 1.1   | In all types of soils.   | cum  | 16.06 | 185.00  | 2,971.10  |
| 2   | 1.17  | Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.   | cum  | 16    | 65.00   | 1,040.00  |
|     | 3.3   | In cement mortar.  | cum  | 2.56  | 263.00  | 673.28    |
| 3   | 16.43 | Demolishing cement concrete including disposal of material within 50 metre lead.   |      |       |         |           |
|     | 13.1  | 1:4:8 or leaner mix  | cum  | 1.6   | 329.00  | 526.40    |
| 4   | 1.18  | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.  | cum  | 15.2  | 371.00  | 5,639.20  |
| 5   | 1.26  | Carriage by mechanical transport upto 5 km lead:   |      |       |         |           |
|     | 26.3  | Dismantled Building debris (Mulba)   | cum  | 12.80 | 91.50   | 1,171.20  |
| 6   | 3.1   | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.   |      |       |         |           |
|     | 1.5   | 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).   | cum  | 1.6   | 4073.00 | 6,516.80  |
| 7   | 7.5   | Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:  |      |       |         |           |
|     | 5.4   | Cement Mortar 1:6 (1 cement : 6 coarse sand)   | cum  | 18.34 | 3263.00 | 59,843.42 |
| 8   | 11.1  | Providing and making 6mm thick cement plaster of mix:  |      |       |         |           |
|     | 1.2   | In Cement mortar 1:4 (1 cement : 4 fine sand)  | sqm  | 21.16 | 87.00   | 1,840.92  |
| 9   | 11.2  | Providing and making 12mm thick cement plaster of mix:   |      |       |         |           |
|     | 2.2   | In Cement Mortar 1:4 (1 cement : 4 fine sand)  | sqm  | 82    | 103.00  | 8,446.00  |
| 10  | 11.3  | Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:  |      |       |         |           |
|     | 3.3   | In Cement Mortar 1:5 (1 cement : 5 fine sand)  | sqm  | 83.6  | 113.00  | 9,446.80  |
| 11  | 12.46 | 15 mm thick Table rubbed polished Granite stone slab in risers and treads of steps skirting dado and pillars laid on 12mm (Average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polishing etc. complete (single stone is to be used for risers and treads of steps and width of stone for skirting and dado shall be equal to the height of skirting & dado and length of 1.0 m). |      |       |         |           |
|     | 16.1  | Granite stone grey/pink  | sqm  | 12.8  | 1869.00 | 23,923.20 |
|     | 16.3  | Granite stone lakha red/ shahi red   | sqm  | 16    | 4273.00 | 68,368.00 |

| S.N | REF   | ITEM DESCRIPTION  | UNIT  | QTY    | RATE    | AMOUNT    |
|-----|-------|---|-------|--------|---------|-----------|
| 12  | 12.15 | Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm                                       |       |        |         |           |
|     | 55.2  | Pigment Coloured (rubber mould) precast interlock concrete blocks   | sqm   | 120    | 632.00  | 75,840.00 |
| 13  | 2.1   | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:   |       |        |         |           |
|     | 1.1   | Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.  | sqm   | 29.36  | 139.00  | 4,081.04  |
|     | 1.4   | Edge of slab, breaks in floor and walls upto 200mm.   | metre |        | 34.00   |           |
|     | 1.5   | Columns, Pillars, Piers and likes- rectangular or square in shape   | sqm   | 12     | 297.00  | 3,564.00  |
|     | 1.7   | Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)   | sqm   | 21.16  | 235.00  | 4,972.60  |
|     | 1.8   | Beams, lintels, cantilevers & walls   | sqm   | 18.4   | 202.00  | 3,716.80  |
| 14  | 3.1   | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.  |       |        |         |           |
|     | 1.3   | 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).  | cum   | 5.16   | 2970.00 | 15,325.20 |
| 15  | 3.2   | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.   |       |        |         |           |
|     | 2.1   | 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).  | cum   | 11.51  | 4163.00 | 47,916.13 |
| 16  | 3.12  | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:  |       |        |         |           |
|     | 12.1  | Thermo-Mechanically treated bars FE 415   | kg    | 1151   | 54.50   | 62,729.50 |
| 17  | 9.2   | Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.  | Kg    | 125.00 | 66.00   | 8,250.00  |
| 18  | 9.13  | Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.   | kg    | 50     | 75.00   | 3,750.00  |
| 19  | 9.15  | Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.  | kg    | 30     | 67.50   | 2,025.00  |
| 20  | 12.13 | Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. |       |        |         |           |

| S.N | REF   | ITEM DESCRIPTION   | UNIT  | QTY    | RATE    | AMOUNT    |
|-----|-------|--|-------|--------|---------|-----------|
|     | 3.1   | Size 600x600mm   | sqm   | 19.89  | 1151.00 | 22,893.39 |
| 21  | 14.49 | Ammendment No.65011/spy/SOR/Dt.I3/12/2022 -Wallpaintingwithpremium emulsion(plastic) manufactured with the cow dung processing emulsion paint of required shade to give an even shade  |       |        |         |           |
|     | 49.1  | On new work (two or more coats)  | Sqm   | 73.96  | 69.00   | 5,103.24  |
| 22  | 14.50 | Ammendment No.65011/spy/SOR/Dt.I3/12/2022- Painting exterior surface with SMOOTH exterior emulsion paint manufactured with the cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with:                                      |       |        |         |           |
|     | 50.1  | On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over   | Sqm   | 196.00 | 79.00   | 15,484.00 |
| 23  | 14.51 | Ammendment No.65011/spy/SOR/Dt.I3/12/2022 - Providing and applying 2mm thick ready mix exterior grade putty (manufactured with cow dung processing ) on walls to make the surface smooth and even.   | sqm   | 269.96 | 101.00  | 27,265.96 |
| 24  | 16.3  | Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.   |       |        |         |           |
|     | 3.3   | In cement mortar.  | cum   | 9.6    | 263.00  | 2,524.80  |
| 25  | 16.18 | Dismantling asbestos sheet roofing including ridges, hips valley and gutters and stacking the materials with 50 m lead.  | sqm   | 25     | 16.50   | 412.50    |
| 26  | 16.26 | Dismantling doors chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead.  | each  | 1.00   | 100.00  | 100.00    |
| 27  | 16.28 | Taking out door shutters (steel or wood) including stacking within 50 metres lead.   | each  | 1.00   | 46.50   | 46.50     |
| 28  | 16.43 | Demolishing cement concrete including disposal of material within 50 metre lead.   |       |        |         |           |
|     | 13.2  | 1:3:6 or richer mix  | cum   | 1.6    | 549.00  | 878.40    |
| 29  | 9.39  | Providing and fixing in position G.I. barbed wire (93.8gram/m) to concrete/ wooden/ angle iron posts (straight or diagonal) including securing and screwing with G.I. tying wire, G.I. stapples, G.I.U-nails or steel pins etc., complete(Cost of posts, struts to be paid for separately) | metre | 240.00 | 9.40    | 2,256.00  |

As per Estimate Amount Rs. 499541.38

54 - 5,00,000/-

  
Sub Engineer  
Nagar Palik Nigam,  
Korba

  
Astt. Engineer  
Nagar Palik Nigam,  
Korba