

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क. 132/निर्माण/2017

सिस्टम टेंडर नं. 49334

कोरबा, दिनांक 08.02.2019


द्वितीय ई-निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 एवं सड़क दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ई-निविदा आमंत्रित की जाती है :-

क	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क 46 अंतर्गत अयोध्यापुरी में मुक्तिधाम का निर्माण कार्य	29,00,000.00	22000.00	4 माह	वर्ग डी एवं प्रवर श्रेणी	23.02.2019 से


शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नही होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नम्बर, **जी.एस.टी.** पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का **स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।**
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. निविदा उन्हीं ठेकेदारों को प्रदाय किये जावेगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रदाय नहीं किया जावेगा।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में **निविदा डालने की तिथि से 30 दिवस पूर्व का नोटरी सत्यापित शपथपत्र** देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का **1 प्रतिशत उपकर** के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंट की खरीदी ठेकेदारों को स्वयं करनी होगी।
10. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
11. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से **15 दिवस** के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
12. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
13. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
14. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
15. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।


 कार्यपालन अभियन्ता
 नगर पालिक निगम
 कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		06.02.19	18.00	06.02.19	18.00	Release Tender
2		Bid Submission	06.02.19	18.00	22.02.19	17.30	
3	Tender Open		23.02.19	10.30	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

WARD NO. ~~55~~ ^{46 Ayodhyapuri} BALGATTAR ME MUKTIDHAM OR BOUNDRY WALL KA NIRMAN KARY.

BASED ON P.W.D. BUILDING SOR 01-01-2015

ABSTRACT

S.N	REF	ITEM DESCRIPTION	Unit	Qty.	Rates	Amount
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	Cum	344.09	185.00	63656.65
	1.1	In all types of soils.				
2	1.2	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	Sqm	7641.00	7.20	55015.20
3	1.9	Extra rate for lead for every 50m lead or part thereof and upto 150 m beyond 50 m free lead and 1.5 m free lift by manual means only.				
	9.1	For Soils	Cum	180.00	33.00	5940.00
	9.2	For Rock	Cum		49.50	
4	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50m and lift upto 1.5 M.	Cum	47.50	65.00	3087.50
5	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	Cum	73.16	371.00	27142.36
6	1.19	Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	Cum	23.10	242.00	5590.20
7	1.25	Diluting chemical emulsion (chlorpyrifos/ lindane) in water as per manufacturers recommendation and injecting for pre-constructional curative cum preventive anti-termite treatment:(Five year service guarantee bond to be signed by contractor)				
	25.1	Surface treatment by spreading emulsion under floor, over the plinth area before laying base concrete @ 5 litres / sqm	Sqm	118.52	27.50	3259.30

8	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	Cum	61.74	2970.00	183367.80
9	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	Cum	74.26	4073.00	302460.98
10	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	Cum	136.46	4163.00	568082.98
11	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	Kg	10464	54.50	570288/- 530228
				11500.00		626750.00
12	3.14	Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer.	Kg	20.00	43.50	870.00
13	3.16	Making 50mm thick plinth protection of plain cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded crushed stone aggregate 20mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with sand including finishing the top smooth.	Sqm	21.00	273.00	5733.00
14	3.4	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	Cum	65.82	97.50	6417.45
15	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	Sqm	449.47	139.00	62476.33
	1.4	Edge of slab, breaks in floor and walls upto 200mm.	Sqm	33.20	34.00	1128.80
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	Sqm	181.28	297.00	53840.16
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	Sqm	192.81	235.00	45310.35

	1.8	Beams, lintels, cantilevers & walls	Sqm	74.00	202.00	14948.00
	4.13	Grading roof for water proofing treatment with:				
	13.1	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	Cum	2.06	3817.00	7863.02
17	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)	Cum	92.55	3350.00	310042.50
18	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	Cum	1.92	121.00	232.32
19	9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.				
	6.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	Kg	430.00	68.00	29240.00
20	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.2	Wall of any thickness including attached pilasters, buttresses etc. in super structure.	Sqm	32.56	228.00	7423.68
21	11.1	Providing and making 6mm thick cement plaster of mix:				
	1.2	In Cement mortar 1:4 (1 cement : 4 fine sand)	Sqm	304.70	87.00	26508.90
22	11.2	Providing and making 12mm thick cement plaster of mix:				
	2.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)	Sqm	489.63	96.50	47249.30
23	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)	Sqm	496.05	113.00	56053.65
24	12.56	25mm thick Local RAJIM/ Red Flag stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid over & jointed with grey cement slurry mixed with pigments to match the shade of the stone i/c grinding, rubbing and polishing.	Sqm	32.00	516.00	16512.00
25	12.57	25mm thick Local RAJIM/ Red Flag stone slab in riser of steps, skirting, dado and pillars laid on 12mm (Average) thick cement mortar 1:4 (1 cement : 4 coarse sand) and joint with grey cement slurry mixed with pigments to match the shade of the slab i/c grinding, rubbing and polishing.	Sqm	39.72	595.00	23633.40

	12.37	Chequered precast cement concrete tiles 22mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tile including cleaning of joint etc complete on 20 mm thick bed of cement mortar 1:4 (1 cement :4 coarse sand) :	Sqm	57.76	640.00	36966.40
27	14.9	Distemping with acrylic washable distemper to give an even shade.				
	9.1	On new work (Two or more coats)	Sqm	164.05	38.00	6233.90
28	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alitek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	Sqm	364.13	94.50	34410.29
29	14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.				
	14.1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm	1153.33	41.00	47286.53
30	14.22	Painting on new work (two or more coats) to give an even shade with:				
	22.1	Satin synthetic enamel paint	Sqm	23.68	55.00	1302.40
31	1.6	Extra for every additional lift of 1.5 m or part thereof.				
	6.1	All types of soils	Sqm	5.29	26.50	140.19
32	14.41	Lettering with black Japan paint, per cm height.	Per Letter	1000.00	0.70	700.00
33	18.76	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 11592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.				
	76.2	110 mm dia pipe.	Metre	84.00	267.00	22428.00
34	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	Cum	15.18	2659.00	40363.62
35	7.4	Brick work with modular well burnt (open bhatta) clay bricks of crushing strength not less than 20 kg/sqcm and water absorption not more than 25% in foundation and plinth in:				
	4.1	Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	Cum	21.41	3263.00	69860.83
36	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:		68.59	121.00	8299.39
37	11.2	Providing and making 12mm thick cement plaster of mix:				
	2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	Sqm	84.72	91.50	7751.88

38	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	Sqm	81.00	107.00	8667.00
39	12.9	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.				
	9.1	Size 300x300mm	Sqm	72.96	692.00	50488.32
40	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.				
	7.1	Size upto 200x300mm	Sqm	55.92	587.00	32825.04
41	1.4	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.		900.00	3.70	3330.00
42	14.1	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.				
	10.1	On new work (two or more coats)	Sqm	53.60	44.50	2385.20
43	12.45	15 mm thick Table rubbed polished Granite stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry including rubbing and polishing etc. complete. (Area of slab should be 0.50 sqm and above)				
	15.2	Granite stone black	Sqm	8.55	2646.00	22623.30
44	12.51	Extra for nosing in steps and treads of Kota stone slab.		8.00	69.50	556.00
As Per Estimate Amount Rs.						2956454.11
						<u>29,00,000</u>

Sub Engineer
Nagar Palik Nigam
Korba

Astt. Engineer
Nagar Palik Nigam
Korba

E.E. Engineer
Nagar Palik Nigam
Korba