



कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फ़ैक्स : 07759-221929, पो. बॉक्स नं. - 12 पिन कोड - 495677

Website : www.korbamunicipal.in, Email : kosabadizone3@gmail.com

फा.क./43, 45, 46, 47, 48, 50, 51, 52, 53, 54, 55 /निर्माण (कोसा.)/2019

कोरबा, दिनांक 29.07.2019

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पजीयन प्रणाली अंतर्गत सहाय श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइट से डाउनलोड कर आमंत्रित की जाती है :-

क्र	कार्य का नाम	प्राक्कलन राशि में	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1	वार्ड क्रमांक 20 काशीनगर अंतर्गत पप्पू पटेल से लोचन राठौर घर तक नाली का मरम्मत एवं निर्माण कार्य। (मरम्मत एवं संधारण मद)	3,98,883/-	21.08.2019	27.08.2019
2	वार्ड क्रमांक 21 बुधवारी बाजार में नाली का मरम्मत कार्य।(मरम्मत एवं संधारण मद)	3,99,000/-	21.08.2019	27.08.2019
3	वार्ड क्रमांक 21 के विभिन्न स्थानों में नाली एवं कलवर्ट का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	3,85,000/-	21.08.2019	27.08.2019
4	वार्ड क्र. 23 अंतर्गत सामुदायिक भवन के समीप नाली का मरम्मत एवं निर्माण कार्य। (मरम्मत एवं संधारण मद)	3,99,618/-	21.08.2019	27.08.2019
5	वार्ड क्र. 21 अंतर्गत बुधवारी में नाली का मरम्मत एवं निर्माण कार्य। (मरम्मत एवं संधारण मद)	3,99,618/-	21.08.2019	27.08.2019
6	वार्ड क्र. 30 के सामुदायिक भवन का मरम्मत एवं विभिन्न कार्य। (मरम्मत एवं संधारण मद)	3,52,000/-	21.08.2019	27.08.2019
7	वार्ड क्र. 29 पोड़ीबहार में कैलाश यादव घर एवं गणेश चौक के समीप सी.सी. सड़क का मरम्मत एवं संधारण कार्य। (मरम्मत एवं संधारण मद)	4,00,000/-	21.08.2019	27.08.2019
8	वार्ड क्र. 29 पोड़ीबहार में आदर्श नगर नीचे मोहल्ला में आर.सी.सी. ड्रेन एवं सी.सी. रोड का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	4,00,000/-	21.08.2019	27.08.2019
9	वार्ड क्र. 30 मानिकपुर के विभिन्न सी.सी. सड़क का मरम्मत एवं संधारण कार्य। (मरम्मत एवं संधारण मद)	3,98,000/-	21.08.2019	27.08.2019
10	वार्ड क्र. 30 मानिकपुर नीचे मोहल्ला डीपरापारा में आर.सी.सी. नाली एवं सी. सी. रोड का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	4,00,000/-	21.08.2019	27.08.2019
11	वार्ड क्र. 30 मानिकपुर यादव मोहल्ला में आर.सी.सी. ड्रेन का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	4,00,000/-	21.08.2019	27.08.2019

उपरोक्त कार्यों की निविदा की सामान्य शर्तें, धरोहर राशि, विस्तृत निविदा विज्ञप्ति, निविदा दस्तावेज व अन्य जानकारी कार्यालयीन अवधि में कार्यालय से प्राप्त की जा सकती है साथ ही यह जानकारी विभागीय वेबसाइट Website : www.korbamunicipal.in एवं www.uad.cg.gov.in में देखा एवं डाउनलोड किया जा सकता है। उक्त निविदा में किसी भी प्रकार का संशोधन किया जाता है तो विभागीय वेबसाइट पर देखा जा सकता है।

कार्यपालन अभियन्ता

नगर पालिक निगम

कोरबा (छ.ग.)

॥ स्वच्छ भारत निर्माण में योगदान दें ॥

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

ABSTRACT

Name of Work **CONSTRUCTION AND MAINTANCE OF DRAIN BUDHWARI W.N21**

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	16.43	Demolishing cement concrete including disposal of material within 50 metre lead.				
	13.1	1:4:8 or leaner mix	cum	5	329.00	1,645.00
2	16.3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.				
	3.3	In cement mortar.	cum	12	263.00	3,156.00
3	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	60.00	185.00	11,100.00
4	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	12	371.00	4,452.00
5	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	12.00	2659.00	31,908.00
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	6.00	4073.00	24,438.00
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	37	4163.00	154,031.00
7	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	2220	54.50	120,990.00
8	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	160	139.00	22,240.00
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	24	235.00	5,640.00
9	3.9	Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	cum	8.4	469.00	3,939.60

S.N	DEF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
10		Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	20	65.00	1,300.00
11	1.26	Carriage by mechanical transport upto 5 km lead:				
	26.1	Earth	cum	70	111.00	7,770.00
12	1.10	Pumping out water caused by springs tidal or river seepage, broken water main or drains and like during Excavation or during Excavation and laying of base concrete (volume to be calculated taking height from water level to bottom of pit and to be measured and paid) .	cum	48.00	146.00	7,008.00

As per Estimate Amount Rs. 399617.60

Say Rs 4.00 crores

Wala
Sub Engineer
Nagar Palik Nigam
Korba(C.G.)

Tgs
Asst. Engineer
Nagar palik Nigam
korba(C.G.)

Excutive. Engineer
Nagar palik Nigam
korba(C.G.)