कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क्र./निर्माण /2019/474 सिस्टम टेन्डर नं. 50599 कोरबा, दिनांक 07/03/2019

ई–निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्युल अनुसार आयटम दरो पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई–निविदा आमंत्रित की जाती है :–

क्र.	कार्य का नाम	प्राक्कलन राशि लाख में	धरोहर राशि रू में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क 11 (नई बस्ती) में सामुदायिक सेन्टर का विकास कार्य	29.73	22300/–	06 माह	वर्ग डी एवं प्रवर श्रेणी	29.03.2019 से ....

शर्तें:–

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरूद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नही होगी।
3. इच्छुंक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यो की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नम्बर, **जी.एस.टी.** पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का **स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।**
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यो का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत् पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का **1 प्रतिशत उपकर** के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईंट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
10. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से **15 दिवस** के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
11. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नही किया जावेगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते है।

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		07.03.19	10.30	07.03.19	10.30	Release Tender
2		Bid Submission	07.03.19	10.30	28.03.19	17.30	
3	Tender Open		29.03.19	10.30	--	--	

EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

DETAILED ESTIMATE

Name of Work : DEVELOPMENT OF COMMUNITY CENTER AT WARD NO 11
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1	In all types of soils.								
			30	1.50	1.50	1.20	81.00			
		-B/WALL	28	2.70	0.60	0.60	27.21			
		-DRAIN	1	80.00	1.00	0.80	64.00			
		-COMMUNITY CENTER FILLING	1	80.00	60.00	1.20	5760.00			
						Total	5932.21	cum	185.00	1097458.85
2	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).								
		-COLUMN	30	1.50	1.50	0.10	6.75			
			28	2.70	0.60	0.10	4.53			
		-DRAIN	1	80.00	1.00	0.10	8.00			
						Total	19.28	cum	2970.00	57261.60
3	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in								

SN	RE.	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		all works upto plinth level excluding cost of form work.								
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		-FOOTING	30	1.20	1.20	0.20	8.64			
		-COUMN	30	0.30	0.30	1.00	2.70			
		-P BEAM	1	84.60	0.30	0.30	7.61			
		-COLUMN	30	0.30	0.30	1.50	4.05			
		-TOP COPING	1	84.60	0.20	0.10	1.69			
		-DRAIN	1	80.00	1.00	0.15	12.00			
			2	80.00	0.20	0.60	19.20			
		-PRECOST	161	1.00	0.50	0.10	8.05			
						Total	63.94	cum	4163.00	266182.22
4	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
	12.1	Thermo-Mechanically treated bars FE 415								
				63.94	80.00		5115.20			
						Total	5115.20	kg	54.50	278778.40
5	3.9	Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.								
			161	1.00	0.50	0.10	8.05			
						Total	8.05	cum	469.00	3775.45
6	2.1	Providing and fixing form								

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
			30X4	1.20	0.20		28.80			
			30X4	0.30	1.00		36.00			
		-P BEAM	2	84.60	0.30		50.76			
		-DRAIN	2X2	80.00	0.60		192.00			
						Total	307.56	sqm	139.00	42750.84
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape								
		-COLUMN	30X4	0.30	1.50		54.00			
						Total	54.00	sqm	297.00	16038.00
7	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:								
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)								
			1	84.60	0.30	0.40	10.15			
			1	84.60	0.20	1.50	25.38			
						Total	35.53	cum	3263.00	115934.39
8	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:								
							35.53			
						Total	35.53	cum	121.00	4299.13
9	1.17	Filling from available								

SN	R...	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
		-COMMUNTY CENTER FILLING	1	80.00	60.00	1.20	5760.00			
						Total	5760.00	cum	65.00	374400.00
10	1.26	Carriage by mechanical transport upto 5 km lead:								
	26.1	Earth								
			1	80.00	60.00	1.20	5760.00			
						Total	5760.00	cum	111.00	639360.00
11	11.2	Providing and making 12mm thick cement plaster of mix:								
	2.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)								
			1	84.60	1.80		152.28			
			1	84.60	0.20		16.92			
						Total	169.20	sqm	96.50	16327.80
12	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:								
	3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
			1	84.60	1.60		135.36			
						Total	135.36	sqm	107.00	14483.52
13	9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.								

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
	6.1	..n stringers, treads, landings etc. of stair cases including use of chequered plate wherever required, all complete.								
		-GATE	1	3.00	1.50	100.00	450.00			
						Total	450.00	Kg	70.00	31500.00
14	14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.								
	14.1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)								
							169.20			
							135.36			
						Total	304.56	sqm	41.00	12486.96
15	14.22	Painting on new work (two or more coats) to give an even shade with:								
	22.1	Satin synthetic enamel paint								
		-GATE	2X2	3.00	1.50		18.00			
						Total	18.00	sqm	55.00	990.00

As per Estimate Amount Rs. 2972027.16

Say Rs.

Sub Engineer
Nagar Palik Nigam
Korba (C.G.)

Astt. Engineer
Nagar Palik Nigam
Korba (C.G.)

E.E. Engineer
Nagar Palik Nigam
Korba (C.G.)