

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क्र. 506/2026

सिस्टम टेंडर नं. 190872

कोरबा दिनांक 13.05.2026

ई-निविदा आमंत्रण सूचना


कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015, सड़क हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है:-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि - 05.06.2026 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 05.06.2026 सायंकाल 4.00 बजे से

क.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	सी.एण्ड.डी. प्लांट हेतु एप्रोच रोड, शेड निर्माण एवं अन्य विकास कार्य (14वें विल्ल मद)	30.68	23500/-	05 माह	1500/-	वर्ग डी एवं प्रवर श्रेणी	05.06.2026 से

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र, पेन नम्बर, वैध जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा के पते पर भेजना होगा। निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे एवं कर्मचारी भविष्य निधि संगठन (ई.पी.एफ.) एवं विभिन्न प्रावधानों को धारा 1952 के तहत निविदाकार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत तीन माह की अवधि में जमा किये गये TRRN Payment Detail चालान की प्रति प्रस्तुत करना तथा ऑनलाईन अपलोड किया जाना अनिवार्य होगा।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में फ्लाइंग एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कंडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
16. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
17. कार्य कियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।



कार्यपालक अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		13.05.2026	15.30	13.05.2026	15.30	Release Tender
2		Bid Submission	13.05.2026	15.30	03.06.2026	17.30	
3		Physical Document Submission	13.05.2026	15.30	05.06.2026	15.00	
4	Tender Open		05.06.2026	16.00	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)


OFFICE OF MUNICIPAL CORPORATION KORBA (C.G.)

ESTIMATE FOR CONSTRUCTION OF SHED, APPROACH ROAD AND OTHER DEVELOPMENT WORK FOR C & D PLANT AT VEHICLE STAND, MUNICIPAL CORPORATION KORBA (C.G.)

CG PWD Road SOR 2025 and Building SOR 2015

Approach Road

No.	PARTICULAR	NO.	L	B	H/D	QTY.	UNIT	RATE (in Rs.)	AMOUNT (in Rs.)
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.								
	AS PER VOLUME CALCULATION SHEET	1	65.00	6.00	0.50	195.00			
		1	45.00	6.00	0.50	135.00			
	(PWD ROAD SOR NO. 3.2)					TOTAL	330.00	CUM	103.00
									33990.00
2	Removal of Unserviceable Soil Removal of Unserviceable Soil and Disposal with all leads including loading and unloading.								
	Qty. as per Item No. (1)					330.00	CUM	83.00	27390.00
	(PWD ROAD SOR NO. 3.9)								
3	Transportation of different other material ic/ loading & unloading								
(e)	Excavated/compacted ordinary & other soil measured as per clause 301.8, 304.4 and 305.8								
	Qty. as per Item No. (4)					330.00	CUM	120.00	39600.00
	(PWD ROAD SOR NO. 1.2)								
4	Granular Sub-base as per Table :- 400-1 Construction of granular sub base by providing close graded material carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface watering rolling and compacting with vibratory power roller at OMC to achieve the desired density complete as per clause 401								
	A Plant mix method (with Mechanically crushed stone only) (ii) Grading-IV Material	1	65.00	6.00	0.20	78.00			
	(PWD ROAD ITEM NO.-4.1(A)ii/15)	1	45.00	6.00	0.20	54.00			
						TOTAL	132.00	CUM	1586.00
									209352.00
5	Providing and laying cement concrete for plain concrete/ reinforced concrete i/ c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-10								
	(PWD ROAD SOR NO.-6.3 i/32)	1	65.00	6.00	0.15	58.50			
		1	45.00	6.00	0.15	40.50			
						99.00	CUM	3449.00	341451.00
6	Providing and laying Un-reinforced Cement Concrete without Dowel bars including formwork and expansion, contraction & longitudinal joints as per design and as per IRC-62, over a prepared base as per approved mix design and finishing to lines and grade as per Drawing for Pavement thickness less than 200mm in Low Volume Roads. With Cement concrete grade M-30 and minimum cement content (ij) 375 kg/cum								
	(ROAD SOR. ITEM NO.-6.4/33)	1	65.00	6.00	0.20	78.00			
		1	45.00	6.00	0.20	54.00			
						132.00	CUM	4,748.00	626736
(A) Total Rs.									1278519.00



and Other Development

PARTICULAR	NO.	L	B	H/D	QTY.	UNIT	RATE (in Rs.)	AMOUNT (in Rs.)
ation for all types and sizes of foundations, trenches and drains for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
In all types of soil	48	1.50	1.50	1.50	162.00			
(BUILDING SOR ITEM NO.-1.1.1/9)					TOTAL	CUM	185.00	29970.00
2 Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/height including disposal of rubbish upto 1.5 m lift and lead upto 50 m (at least 5m away from the dressed area).								
	1	65.00	6.00		390.00			
	1	45.00	6.00		270.00			
(BUILDING SOR ITEM NO.-1.2/9)					TOTAL	CUM	7.20	4752.00
3 Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
Qty. as per Item No. (1)	0.3	162.00			48.60	CUM	65.00	3159.00
(BUILDING SOR NO. 1.17)								
4 Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
For Columns								
Total Excavation					162.00			
Less P.C.C.					-16.2			
Less Footing					-23.928			
Less Back filling qty					-48.60			
For Interlocking Concrete Blocks	1	32.00	12.60	0.15	60.48			
1.18								
					133.752	cum	371.00	49622.00
5 Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
Foundations, footings, base of columns and plinth beam in any shape and size.								
2.1.1	48	5.4		0.15	38.88			
	48	1.2		1.1	63.36			
					102.24	sqm	139.00	14212.00
6 Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.								
1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).								
3.1.3	48	1.50	1.50	0.15	16.20			
	1	32.00	12.00	0.15	57.60			
	1	30.00	12.00	0.15	54.00			
					127.80	CUM	2970.00	379566.00
7 Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.								
1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
For Footing	48	1.35	1.35	0.15	13.122			
For trapezodial portion	48	1.8225	0.16	3.063	6.054			
For Columns up to plinth	48	0.3	0.3	1.1	4.752			
3.2.1					23.928	cum	4163.00	99613.00
8 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:								
Thermo-Mechanically treated bars	1	23.928	100	1	2392.80	kg	54.50	130408.00
3.14.1								

	Concrete Flooring with (1:2:4) Cement concrete ment : 2 Sand:4 graded stone aggregate 12.5mm (final size) finished with floating coat of neat cement.								
	Unit: Sqm	1	40	12.5		500.00	SQM	222.00	111000.00
10	12.3.1 Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer.								
	9.3.2 Electric resistance or induction butt welded tubes Grade-300 PWD S.O.R.-P-80/1-9.3.1 For Truss								
	65x65x3	12	27.5	5.85		1930.50			
	40x40x3	264	0.8	3.49		737.09			
	For Gusset etc				Add 20%	533.52			
	For Purlin 50x50x3.5	4	30	4.93		591.60			
	For Vertical supports 75x75x3	48	3.2	7.01		1076.74			
	For base plate etc					500.00			
						5369.44	Kg	93.50	502042.79
11	Supply and fixing of polymer pre-coated galvalume profile sheets (PPGL) of approved size, shape and pitch of corrugation, total coated thickness (TCT) 0.60 mm +/- 5%, epoxy primer on both side of the sheet and colour polyester top coat 18-20 microns and 6-7 microns on bottom. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.								
	Sheeting work (For both ends)	1	32.00	12.60		403.20			
						403.20	Sqm	693.00	279417.60
12	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint (top most approved branded quality)	12	27.50	0.26		85.80			
		264	0.80	0.16		33.79			
		4	30.00	0.20		24.00			
		48	3.20	0.30		46.08			
	Extra for base plate etc	20%				37.93			
						103.87	sqm	55.00	5712.96
13	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint (top most approved branded quality)	12	27.50	0.26		85.80			
		264	0.80	0.16		33.79			
		4	30.00	0.20		24.00			
		48	3.20	0.30		46.08			
	Extra for base plate etc	20%				37.93			
						103.87	sqm	55.00	5712.96

...ing & laying 60mm thick precast interlocking
 concrete blocks of approved size (approx 305 sqcm)
 and shape/ pattern, over 40 mm thick average
 concrete coarse sand bed with joints of 3mm thick
 filled with fine sand including leveling with surface
 vibrator, temping and sweeping etc. complete of
 minimum compressive strength of 250 kg/sq.cm

12.65.1 Plain/ normal coloured precast interlock concrete block	1	32.00	12.50		400.00	sqm	436.00	174400.00
(B) Total Rs.								1789588.31
Or Say Rs.								1790000.00
Total (A+B) Rs.								3299000.00
(TOTAL RS THIRTY TWO LAKH NINETY NINE THOUSAND ONLY)								

[Signature]
 18/02/26

Sub. Engg.
 Municipal Corporation
 Korba (C.G.)

[Signature]

Astt. Engg.
 Municipal Corporation
 Korba (C.G.)