

कार्यालय, नगर पालिक निगम, कोरवा (छत्तीसगढ़)

फा.क. 307/2025

सिस्टम टेंडर नं. 173757

कोरवा दिनांक 14.08.2025

ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरवा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015, विद्युत हेतु दिनांक 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक रामस्त शोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि - 10.09.2025 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 10.09.2025 सायंकाल 4.00 बजे से

क.	कार्य का नाम	प्राक्कलन राशि (लाख में)	घरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड 29 अंतर्गत मुड़ापार दशहरा मैदान के पास मंच निर्माण कार्य (जि.ख.न्या.मद) (प्रथम निविदा)	10.00	7500/-	03माह	750/-	वर्ग डी एवं प्रवर श्रेणी	10.09.2025 से

शर्तें-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जायेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशिप डीडे) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र, पेन नम्बर, वैध जी.एस.टी. प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी शपथपत्र का रकने काफी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त, नगर पालिक निगम, कोरवा साकेत गवन, आई.टी.आई.चौक रामपुर कोसावाड़ी पिन- 495677 कोरवा के पते पर भेजना होगा। निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम, कोरवा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संचारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जायेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे एवं कर्मचारी भविष्य निधि संगठन (ई.पी.एफ.) एवं विभिन्न प्रावधानों को धारा 1952 के तहत निविदाकार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत तीन माह की अवधि में जमा किये गये TRRN Payment Detail चालान की प्रति प्रस्तुत करना तथा ऑनलाईन अपलोड किया जाना अनिवार्य होगा।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जायेगी।
7. ईट से संबंधित निर्माण कार्यों में पलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरो असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरवा के नाम पर देय होगा जो माग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जायेगी।
10. निविदा अहस्तातारणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
12. निविदा के सवध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरवा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयको का भुगतान कार्य विशेष हेतु बजट आवंटन एवं राशि उपलब्ध होने पर किया जाएगा।
16. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
17. कार्य कियान्चयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रदहन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

कार्यपालन अभियंता
नगर पालिक निगम
कोरवा (छ.ग.)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		14.08.2025	15.30	14.08.2025	15.30	Release Tender
2		Bid Submission	14.08.2025	15.30	09.09.2025	17.30	
3		Physical Document Submission	14.08.2025	15.30	10.09.2025	15.00	
4	Tender Open		10.09.2025	16.00	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT

Name of Work :- Construction of Munch Near Mudapar Dashahara Maidan Under Ward No. 29


As Per Sor :- Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]


S No	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
	16.41 Demolishing cement concrete including disposal of material within 50 metre lead								
	1:3:6 or richer mix					10.500	cum	549.00	5764.50
	Dismantling G.I sheet roofing including ridges hips, valleys and gutters etc. and stacking the material with 50 m lead.					70.00	sqm	33.50	2345.00
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (At least 5m away from the excavated Area), including dressing and leveling of pits								
	In All Types of soils.					49.58	cum	185.00	9171.38
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.					4.52	cum	371.00	1675.07
3	Filling from available excavated stuff (Excluding rock) In trenches, plinth, sides of foundation etc. In layers not exceeding 20cm In depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.					49.58	cum	65.00	3222.38
	Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm In depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.					69.70	cum	242.00	16866.43
4	Providing and laying nominal mix plain cement concrete with crushed stone Aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone Aggregate 40mm nominal size).					18.49	cum	2659.00	49174.22
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone Aggregate 20mm nominal size).					4.54	cum	4073.00	18475.13
5	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and All Type of wall below plinth level.					95.32	sqm	139.00	13249.48
	Columns, Pillars, Piers and likes- rectangular or square in shape					38.50	sqm	297.00	11434.50

S No	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
	Beams, lintels, cantilevers & walls					60.80	sqm	202 00	12281 60
	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)					86.71	sqm	235 00	20376 85
	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work								
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone Aggregate 20mm nominal size)					37.42	cum	4163 00	155794 86
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. Complete As Per drawings including cost of binding wire in foundation and plinth all complete:								
	Thermo Mechanically treated bars FE 415					3742.37	kg	54 50	203959 17
8	12.13 Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.								
						82.78	sqm	1151 00	95279 78
	12.46 15 mm thick Table rubbed polished Granite stone slab in risers and treads of steps skirting dado and pillars laid on 12mm (Average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polishing etc. complete (single stone is to be used for risers and treads of steps and width of stone for skirting and dado shall be equal to the height of skirting & dado and length of 1.0 m).								
						16.20	sqm	2719 00	44047 80
9	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer.					21.60	Sqm	3330 00	71928 00
10	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3 00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including Applying a Priming coat of red oxide zinc chromate Primer.								
						169.29	kg	75 00	12696 75
11	7.5 Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS: 12894-2002 of class designation 4.0 in foundation and plinth in								
	Cement Mortar 1:6 (1 cement : 6 coarse sand)								
						33.33	Cum	3263 00	108768 84

S.No.	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
12	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:								
						22.64			
						22.64	Cum	121.00	2739.68
	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:								
						23.13			
						23.13	Cum	97.50	2255.34
	9.57 Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete								
	SS Grade 304								
						27.00			
						27.00	Kg	525.00	14175.00
	12.65 Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm								
13	Providing and making 6mm thick cement plaster of mix:					28.60	sqm	632.00	18075.20
	In Cement mortar 1:4 (1 cement : 4 fine sand)								
14	Providing and making 12mm thick cement plaster of mix:					77.44	sqm	87.00	6737.28
	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
15	11.3 Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix					131.48	Sqm	91.50	12030.42
	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
						99.60	Sqm	107.00	10657.20
16	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.								
						308.52	Sqm	94.50	29155.14
	14.11 Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade.								
	On New Work (two or more coats)								
						208.92	Sqm	52.50	10968.30

No.	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
17	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with								
	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)								
						99.60	Sqm	56.00	5577.60
18	14.22 Painting on new work (two or more coats) to give an even shade with:								
	Satin synthetic enamel paint								
						37.80	Sqm	55.00	2079.00
As Per SOR Total Estimate Amount Rs.									970961.88
For Internal Electrification Work (PWD Electrical Sor 01.06.2020)									29038.09
Net Amount									999999.97
Say As Rs.									1000000.00


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asst. Engineer
 Municipal Corporation
 Korba (C.G.)